Clearspring

Stormwater Management & Stream Restoration Project







November 6, 2014 Public Meeting

Montgomery County Department of Environmental Protection Watershed Management Division



Today's Agenda

- Introductions
 - Rebecca Winer-Skonovd Project Manager; Montgomery County DEP/JV
 - Paul Bogle– Senior Engineer; Montgomery County DEP
 - Jeff Blass SWM Project Designer; Charles P. Johnson & Associates, Inc.
 - Gabrielle Myers Stream Project Designer
- Background Information Why County is Doing This
- Stormwater Management Overview
- Project Objectives
- Project Costs and Benefits
- Design and Permitting Timeline
- What to Expect During Construction

Montgomery County, MD

- 500 sq. miles
- 1,000,000 people
 - Second only to Baltimore City within Maryland in average people per square mile
 - 184 languages spoken
- About 12% impervious surface overall
 - About the size of Washington DC
- Over 1,500 miles of streams
- Two major river basins:
 - Potomac
 - Patuxent
- Eight local *watersheds*

District of Columbia Impervious: Not allowing water to soak through the ground.



What is a Watershed?

- A *watershed* is an area from which the water above and below ground drains to the same place.
- Different scales of watersheds:
 - Chesapeake Bay
 - Eight local watersheds
 - Neighborhood (to a storm drain)



What is Runoff?

Water that does not soak into the ground becomes surface runoff. This runoff flows over hard surfaces like rooftops, driveways and parking lots collecting potential contaminants and flows:

- Directly into streams
- Into storm drain pipes, eventually leading to streams
- Into stormwater management facilities, then streams

<u>Two Major Issues:</u> Volume/Timing of Runoff Water Quality



Watershed 101

Urban Impacts to Streams



Stream in a Watershed with 8% impervious cover.



Stream in a Watershed with 20% Impervious Cover



Stream in a Watershed with 30% impervious Cover.

Watershed 101

- What is the County doing to protect our Streams?
- Must meet regulatory requirements
 - Federal Clean Water Act permit program
 - MS4 = <u>M</u>unicipal <u>S</u>eparate <u>S</u>torm <u>S</u>ewer <u>S</u>ystem
- Applies to all large and medium Maryland jurisdictions
- County Programs
 - Restore our streams and watersheds
 - Add runoff management
 - Meet water quality protection goals
 - Reduce pollutants getting into our streams
 - Educate and engage all stakeholders
 - Individual actions make a difference
 - Focus on watersheds showing greatest impacts



What is the County Doing to Protect our Streams?

- Montgomery County is responsible for:
 - What goes into our storm drain pipes
 - What comes out of them
 - What flows into the streams
- DEP is adding stormwater management for 20 % of impervious surfaces
 - (4,292 acres = 6.7 square miles)... About three times the size of Takoma Park.

That's equivalent to 3,307 football fields!



Resources

Specific Project Information

http://www.montgomerycountymd.gov/DEP/Restoration /clearspring-manor.html

General Information

_www.montgomerycountymd.gov/DEP

• Living a Green Life: My Green Montgomery http://montgomerycountymd.mygreenmontgomery.org/

Project Selection

- Ponds constructed in early 1980s
- Located in a key watersheds (Great Seneca Creek) for pond retrofits
- Ponds are at or near the end of service life
- Meet current safety and design standards
- Opportunity for water quality treatment and ecological benefits



Project Location



Project Objectives - Stream

- Reconnect the stream channel to its floodplain
- Improve Water Quality
- Improve In-Stream & Floodplain Habitat
- Create new and Enhance Existing Wetlands



Project Location



Stream Length: 801 Linear Feet | Stream USE Class: I-P

Stream Drainage Area



Clearspring Stream Conditions

- Primarily a Rosgen G4 channel
- The upper reaches of the stream channel are actively downcutting
- At the pond, the channel is an unstable multithread channel
- Native soils are very loose and easily eroded





Causes of Instability

- Channel piping & loss of riparian buffers in the headwaters
- In-stream modifications (i.e. culverts)
- Increased runoff from development
- Increase in sediment load
- Deep unstable headcut
- No access to floodplain, highly entrenched
- Increased slope, higher velocity



Severely Eroded Bank with Vegetation Loss



Deep Headcut Moving Upstream

Floodplain Connectivity



Channel Realignment

- #1 priority is reconnecting the stream to its floodplain
- Create a stable C channel
- Reduce bank erosion and sediment supply



Glenora Tributary: Previous Condition



Channel Realignment: Glenora Tributary. City of Rockville. Construction 2014

In-Stream Structures

- Riffles and step pools reproduce natural stream conditions
- Riffles, pools and glides create a variety of habitats for fish and invertebrates
- Fish/invertebrates such as darters, cattisflies, midges, damsselflies, and dragonflies likely to return



Glenora Tributary: Constructed Riffle

Stream Bank Grading

- Allows floodplain access during storm events
- Allows vegetation to establish
- Higher storm flows to the floodplain slow water velocities and reduce stress on the banks



Grade Control

- In-stream grade control structures are implemented to reduce bank erosion
- Riffles increase oxygen and reduce water velocity
- Pools dissipate energy and material loads

Tree Stabilization & Riparian Planting

Stream bank vegetation increases floodplain and in-stream habitat, stabilizes banks and helps maintain stream temperatures by providing shade during hot summer months

Donnybrook Tributary: Riparian Planting 2014

Wilde Lake Reach D: Riparian Planting

Common Riparian Trees/Plants

Silky Dogwood

Images Source: http://plants.usda.gov

23

Clearspring Stormwater Pond

Project Objectives

- STORMWATER MANAGEMENT
 - Increase permanent pool for water quality
- STREAM PROTECTION
 - Modify outlet works to better regulate pond discharge and protect Magruder Branch and Seneca Creek streams
- MAINTENANCE
 - Replace existing riser with a water-tight structure
 - Replace dam embankment and install impervious core
 - Install internal drain in downstream embankment
- AESTHETICS/ENVIRONMENT
 - Landscape the pond to improve aquatic habitat and aesthetics
 - Augment existing environmental features such as forest and wetlands where possible

Stormwater Pond Drainage Area

• Clearspring Pond (Asset #11423)

- 66.14 Acres
- 23.5% Impervious

Pond 11423

- Stormwater Management Dry Pond
 - 16' High Earth Embankment Dam
 - Adjacent residential properties
 - Does not meet current SWM requirements to achieve any MS4 credit.
 - Heavily silted

Existing Metal Outlet Structure

Pond 11423

Project Objectives – Stormwater Management

- Increase permanent pool storage to provide maximum water quality treatment
- Modify outlet works to provide maximum channel protection treatment

Project Objectives - Streams

- Modify outlet works to better regulate pond discharge and protect Magruder Branch and Great Seneca Creek
- Achieve full water quality and channel protection treatment

Project Objectives - Maintenance

- Replace existing riser with water-tight structure
- Install impervious core in dam embankment
- Install internal drain in downstream embankment

Project Objectives - Aesthetics

 Sod and landscape facility with native vegetation to improve aesthetics

Project Objectives - Landscaping

- Trees:
 - Red Maple
 - American Hornbeam
 - Black Gum
 - White Oak
 - Swamp White Oak
- Shrubs:
 - Winterberry
 - Arrowhead
- Aquatic Emergents:
 - Blue Flag
 - Purple Stem Aster
 - Soft Rush

Red Maple

American Hornbeam

Winterberry

Project Costs

- **Financial** estimated cost of \$1,242,000 financed through MCDEP CIP Program using funds generated through the Water Quality Protection Charge
- Forest tree clearing to comply with state dam safety laws along the downstream toe of the dam.
- **Traffic** construction traffic enter and exit roadways Monday – Friday, 7AM to 4PM
- Neighborhood construction traffic and noise will typically occur Monday – Friday, 7AM to 4PM

Project Benefits

- Water improved water quality and stream water temperature through better management of runoff
- Environmental reduced downstream discharge allows for natural self-repair of stream channel. Increased aquatic and riparian habitat through landscaping and reforestation.
- **Recreational** increased aesthetic appeal of ponds
- **Maintenance** safer operating structure that will require minimal structural maintenance in future.

Estimated Design and Permitting Timeline

- Design November 2013 October 2015
- Approvals September/October 2015
- Permits November 2015
- Bidding –December 2015
- Construction (estimated) Jan. 2015– May 2015

What to Expect During

Construction

- Duration
 - Approximately 5 months
- Construction Hours
 - Monday through Friday, 7AM 4PM
- Safety
 - Open sides of site will be fenced with orange construction safety fence to separate construction from residents.
- Traffic
 - Minor impacts to traffic from entering and exiting construction traffic and contractor parking during the day.
- Noise
 - Contractor is required to comply with Montgomery County Noise Ordinance site elevation will help alleviate noise pollution.

Sediment

• Contractor will be required to comply with Montgomery County Sediment Control Permit and not track dirt onto roads

Questions?

For more information:

• Rebecca Winer-Skonovd 240-499-8531, rebecca.winer-skonovd@montgomerycountymd.gov