



MCDOT NEWS

News from the Montgomery County Department of Transportation, Division of Highway Services

Black Rock Road Chipseal Surface Treatment Project

Project to Continue in July; Includes Full-Depth Patching and Chipseal Resurfacing

PURPOSE

This newsletter is to update you on the upcoming roadway repairs and resurfacing of Black Rock Road, from Darnestown Road to Burdette Lane, and to describe the process. This pavement system preservation project employs long term strategies to preserve and enhance the physical and operating conditions of the roadway system as it exists and assures a system serviceable for many years. This project falls under the County's Rural/Rustic Roadway Resurfacing Program.

BACKGROUND

The Montgomery County Department of Transportation's (MCDOT) Division of Highway Services (DHS) maintains nearly 5,200 lane miles of streets and highways in the county's transportation system, including Rural/Rustic Roads such as Black Rock Road. These rustic/exceptional roads exemplify the rural and agricultural landscape of the county and have special characteristics which contribute significantly to the rural and historic features of Montgomery County.

As part of our pavement system preservation efforts, MCDOT initiated a new Pavement Management System in 2008. At that time, MCDOT concluded a complete condition inventory of all County roads, identifying and rating the condition of each. This new assessment system is updated every two years and has enabled the development of County-wide road resurfacing schedules based on a formula-based objective rating system coupled with budgetary parameters.

SCOPE OF PROJECT

Overall, pavement conditions of Black Rock Road were generally rated as fair, with some areas described as needing more attention. This rating, combined with the Rural/Rustic roadway design,

meets the criteria for Chipseal resurfacing. Often referred to as "Tar & Chip," Chipseal is a pavement surface treatment that combines an overlay of liquid asphalt binder and a layer of small gravel. The Chipseal application used on Rural/Rustic roads throughout the County will preserve the pavement structure as well as the natural, agricultural and historic characteristics of the surrounding area.

PROJECT WORK PLAN

Generally, the work will proceed as follows:

1. Roadway Base Repair - Field Inspectors have found several areas of the roadway in need of full-depth patching. The areas of distressed pavement marked by the MCDOT inspectors will be removed and replaced by new pavement. The final resurfacing of the road will cover these patched areas. **Patching will precede other construction activities by several weeks.**

2. Crack Sealing - It may be necessary to clean and seal large cracks in the roadway before resurfacing. A flexible filler material is injected into the cracks, filling voids and preventing water infiltration and damage.



Binder and Chipseal application.

3. Chipseal Resurfacing

Asphalt emulsion binder is first sprayed onto the pavement, immediately followed by an application of aggregate (stone). Chipseal is applied in an inch mat over the complete road sur-

face, usually in two separate applications (or "coats"), and provides the roadway with a uniform thickness and appearance. Following placement, rubber tired rollers complete the compaction effort until field testing indicates that all relevant specifications have been met.



Compacting the new material with rollers.

4. Sweeping of Residual aggregate - Following the initial application, the road will be swept within 7-14 days to help reduce the amount of surface dust and residual stone, which is evident for a period after the application.

5. Replace roadway lane markings - Permanent lane markings, if existing prior to the project, will be replaced shortly after resurfacing operations.

SCHEDULE

Full-depth patching is scheduled to continue in mid-July 2015. Resurfacing will occur several weeks after prep. work has been completed. Weather permitting, all construction should be completed by the end of August 2015. Working hours for this project will be between 9am and 3pm, Monday through Friday. However, construction will be permitted on Saturdays, if necessary, to expedite the completion of the project.

IMPACTS

Street resurfacing will necessitate temporary lane closures and temporary parking restrictions. Our goal is to maintain continuous traffic at all times utilizing alternating one-way traffic; however,

possible detours may be implemented to help minimize inconveniences to the traveling public. Signs will be posted identifying such restrictions. Access to residences will be available at all times; however, minor delays may be experienced as workers restrict traffic from freshly placed material.

Cyclists should proceed with extra caution when traveling on freshly applied material, as loose aggregate stone may cause slippage. The newly resurfaced roadway will be swept approximately two weeks after surface treatment has been completed to remove residual stone.



Loose aggregate may cause slippage.

Generally speaking, this work is best characterized as noisy and disruptive. However, MCDOT and its contractors will take all necessary steps to mitigate any inconveniences this work may cause. *If, for some reason, you have a medical condition that could be potentially impacted by construction activities, please alert the project manager listed on the opposite side of this newsletter or Josh Faust, Public Outreach Manager, at 240-777-7642.*

Quality control for the entire project will be managed by County inspection staff to ensure that the project meets County specifications.

Thank you for your cooperation and patience as we work to improve the county infrastructure for residents and users!



MONTGOMERY COUNTY, MARYLAND
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAY SERVICES
100 EDISON PARK DRIVE, 4th FLOOR, GAITHERSBURG, MD 20878
(240) 777-ROAD (7623) www.montgomerycountymd.gov/dot-highway/

KEEPING MONTGOMERY MOVING

MCDOT NEWS No. 2015.57

NOTICE OF BLACK ROCK ROAD CHIPSEAL RESURFACING PROJECT

SAFETY NOTICE

Please drive gently and safely through the work site and kindly remember that while repair work is underway personnel and construction vehicles will be moving around the site. Some materials may be stored in the area. Please use caution when walking or driving through the construction zone. Children may be attracted to the noise and machinery, so we ask that you please keep all children under close supervision at all times, even after the work is completed for the day. Also, please follow the direction of flaggers and temporary signs and traffic control devices. We appreciate your patience and cooperation while we make these much needed improvements to the infrastructure.

IMPORTANT MCDOT CONTACTS

Project Manager: Sean O'Connell 240-777-7692

Program Manager: Donald Noble 240-777-7601

Should your questions be of a more general nature, please contact the
MC311 Call Center by dialing 311 or 240-777-0311.

DHS Email: mcdot.highway@montgomerycountymd.gov

DHS Website: www.montgomerycountymd.gov/DOT-Highway/

On the county map, click on the **Poolesville** Service Area, where you will
find additional roadway maintenance projects scheduled in your area.

Follow us on Twitter and Facebook!



@MontCo_Highways



mocohighwayservices

