

CONTRACTOR MUST PROVIDE SHOP  
DRAWING DETAIL OF COVERED WALKWAY  
FOR REVIEW AND APPROVAL TO THE  
TRAFFIC OPERATIONS SECTION, IF  
ALTERNATE MATERIALS FOR WALKWAY  
ARE PROPOSED

1/2" MIN. THICK PLYWOOD  
2" THICK ROOF DECK

2" X 8" FULL LENGTH  
ONE ON EACH SIDE

SLOPE DOWN TOWARDS CURBLINE

ROLLED ROOFING 2" X 8" ON 4' O/C

WIRE MESH OR  
1/2" PLYWOOD

2" X 4" TYP.  
EACH STUD

40 WATT LIGHT  
W/ GUARD  
ON 16 FT O/C

BACK SIDE  
(WORK AREA)

FRONT SIDE  
(ROAD SIDE)

6" LAP

4" X 4" ON 2' O/C

1/2" PLYWOOD  
6' 0" HIGH MIN.

2" X 4"  
HANDRAIL

8' CLEAR

WIRE MESH, CONTINUOUS

5/8" PLYWOOD  
FLOOR

3'6"

5 FT MIN.

4" X 4" ON 2' O/C

PROVIDE TEMPORARY ASPHALT WEDGE  
FROM CURB TO EXISTING  
PAVING AS NECESSARY

DATE  
07-01-16

TRAFFIC OPERATIONS SECTION,  
MONTGOMERY COUNTY, MARYLAND

DES. BY

MCDPWT

DRAWN BY

TCLE

SCALE

NTS

APPROVED

CHIEF, TRAFFIC OPERATIONS SECTION

STANDARD TCP-107.03 OF SHEETS

REVISION BY	DATE	APPROVED