

CLARKSBURG TOWN CENTER

GROUNDWATER RECHARGE FACILITIES

SECTION 1B - PART 3

OK
RJS

Project # 29-100

Prepared by: JES
August 2001

CPJ Charles P. Johnson & Associates, Inc.
Associates
PLANNERS • ENGINEERS • LANDSCAPE ARCHITECTS • SURVEYORS
1751 ELTON ROAD SUITE 300 SILVER SPRING, MARYLAND 20910
(301) 434-7000 FAX (301) 434-5094 FREDERICK MD - PAI FAX, VA

CW # 7

Impervious Area to Facility = 19,602 SF (0.45 Ac.)

Storage Required = (19,602 SF) * (1'/12") = 1634 CF

In Stone Storage = 1634 / 0.4 (Void Ratio) = 4085 CF

Storage Provided = (846 SF) * (5' D) = 4230



CW # 8

Impervious Area to Facility = 19,602 SF (0.45 Ac)

Storage Required = (19,602 SF (1'/12")) = 1634 CF

In stone storage = 1634/0.4 (void ratio) = 4085 CF

Storage provided = (52' L) x (20' W) x (4.0' D) = 4160 CF





Charles P. Johnson & Associates, Inc.
 PLANNERS • ENGINEERS • LANDSCAPE ARCHITECTS • SURVEYORS
 1751 ELTON ROAD • SILVER SPRING, MARYLAND • 20903
 (301) 434-7000 FAIRFAX, VA

Prepared By: SJ
 Checked By: JES
 Date: 9/13/01

Engineer's Preliminary Cost Estimate
For
 CLEANWATER RECHARGE TRENCH 7 & 8
 SECTION 1B, PART 3

Job Number 29-100

Sheet 1 of 1

ITEM	UNIT	APPROXIMATE QUANTITY	APPROXIMATE UNIT PRICE	APPROXIMATE COST
SAND	CY	200	23.00	4,600.00
STONE	CY	320	14.00	4,480.00
8" PVC SCH-40	LF	303	17.00	5,151.00
CLEAN OUTS	EACH	2	50.00	100.00
EXCAVATION	CY	680	8.00	5,440.00
TOTAL:				\$19,771.00

NOTE

This estimate is prepared as a guide only, is based upon preliminary information, and is subject to possible change. Charles P. Johnson & Associates makes no warranty, either express or implied, that actual quantities and costs will not vary from the amounts indicated and assumes no liability for such variances.