Red Brick Courthouse Structural Repairs (P500727)

Category
Sub Category
Administering Agency
Planning Area

General Government

County Offices and Other Improvements

General Services (AAGE29)

Rockville

Date Last Modified
Required Adequate Public Facility

11/17/14 No

Relocation Impact

Status

None

Final Design Stage

	Total	Thru FY15	Est FY16	Total 6 Years	FY 17	FY 18	FY 19	FY 20	FY 21	FY 22	Beyond 6 Yrs
			EXPENDIT	URE SCHE	OULE (\$000	s)		•			
Planning, Design and Supervision	3,625	292	0	3,093	0	0	1,041	889	612	551	240
Land	0	0	0	0	0	0	0	0	0	0	0
Site Improvements and Utilities	227	0	0	127	0	0	0	0	80	47	100
Construction	15,606	295	0	14,424	0	0	0	0	8,983	5,441	887
Other	4	0	4	0	0	0	0	0	0	0	0
Total	19,462	587	4	17,644	0	0	1,041	889	9,675	6,039	1,227
			FUNDIN	G SCHEDU	LE (\$000s)						
G.O. Bonds	19,462	587	4	17,644	0	0	1,041	889	9,675	6,039	1,227
Total	19,462	587	4	17,644	0	0	1,041	889	9,675	6,039	1,227

APPROPRIATION AND EXPENDITURE DATA (000s)

Appropriation Request	FY 17	0
Appropriation Request Est.	FY 18	0
Supplemental Appropriation Request		0
Transfer		0
Cumulative Appropriation		591
Expenditure / Encumbrances		587
Unencumbered Balance		4

Date First Appropriation FY 07			
First Cost Estimate			
Current Scope	FY 15	19,462	
Last FY's Cost Estimate		19,462	

Description

Phase I of this project provided for the rehabilitation of the flooring system in the Red Brick Courthouse at 29 Courthouse Square in Rockville. The structural integrity of the flooring system was weakened by modifications made over the years to accommodate various electrical, mechanical, and plumbing systems. Phase II will provide for a historic rehabilitation of the Courthouse, to accommodate programmatic functions and requirements of current users and to preserve the building exterior and interior. Work will include the replacement of major building systems, modifications to make the facility compliant with the requirements for the Americans with Disabilities Act (ADA), repair for moisture infiltration issues, and repair and replacement of the building exterior, masonry, copper fittings, and roofing. All work will have to be performed in compliance with requirements and oversight of the Maryland Historical Society and per existing County regulation and easements.

Location

29 Courthouse Square Rockville, MD 20850

Estimated Schedule

Design is estimated to begin in FY19 and construction in FY21.

Justification

For Phase I, a structural engineer determined that some areas of the terra cotta arch and beam flooring system have been compromised by modifications that have been made for various electrical, mechanical, and plumbing systems. Access to certain areas on the first and second floors will be restricted until the problem is resolved. Phase II is the historic renovation of the building, which dates back to the 1800's. In 1995, the Courthouse had a small renovation to upgrade the HVAC and to provide an elevator. Currently, the slate roofing is deteriorating, as is the copper metal roofing on the steeple (both of which have reached the end of service life). The masonry joints need to be tuck-pointed on the exterior walls and parapets. This deterioration has allowed moisture infiltration, which has damaged the building, with repair efforts slowing but not stopping the problems. Along with accessibility issues, the HVAC, plumbing, and electrical systems are at the end of useful life. The fire prevention systems require redesign and installation to provide for better safeguards to prevent potential loss of the historic wood structure.

Other

This facility has been designated as a historic structure.

Fiscal Note

Project has been delayed due to fiscal affordability.

Disclosures

A pedestrian impact analysis has been completed for this project.

Coordination

Department of General Services, Circuit Court, Department of Technology Services, City of Rockville, Montgomery County Sheriff, Department of Human Resources, Peerless Rockville, Montgomery County Historical Society