



Gold Mine Road Bridge M-0096

(P501302)

Category	Transportation	Date Last Modified	12/23/22
SubCategory	Bridges	Administering Agency	Transportation
Planning Area	Olney and Vicinity	Status	Final Design Stage

EXPENDITURE SCHEDULE (\$000s)

Cost Elements	Total	Thru FY22	Rem FY22	Total 6 Years	FY 23	FY 24	FY 25	FY 26	FY 27	FY 28	Beyond 6 Years
Planning, Design and Supervision	1,004	1,004	-	-	-	-	-	-	-	-	-
Land	314	221	93	-	-	-	-	-	-	-	-
Site Improvements and Utilities	365	128	237	-	-	-	-	-	-	-	-
Construction	4,784	4,023	761	-	-	-	-	-	-	-	-
TOTAL EXPENDITURES	6,467	5,376	1,091	-	-	-	-	-	-	-	-

FUNDING SCHEDULE (\$000s)

Funding Source	Total	Thru FY22	Rem FY22	Total 6 Years	FY 23	FY 24	FY 25	FY 26	FY 27	FY 28	Beyond 6 Years
Federal Aid	3,500	3,500	-	-	-	-	-	-	-	-	-
G.O. Bonds	2,967	1,876	1,091	-	-	-	-	-	-	-	-
TOTAL FUNDING SOURCES	6,467	5,376	1,091	-	-	-	-	-	-	-	-

OPERATING BUDGET IMPACT (\$000s)

Impact Type	Total 6 Years	FY 23	FY 24	FY 25	FY 26	FY 27	FY 28
Maintenance	6	1	1	1	1	1	1
NET IMPACT	6	1	1	1	1	1	1

APPROPRIATION AND EXPENDITURE DATA (\$000s)

Appropriation FY 24 Request	-	Year First Appropriation	FY13
Cumulative Appropriation	6,467	Last FY's Cost Estimate	6,467
Expenditure / Encumbrances	6,000		
Unencumbered Balance	467		

PROJECT DESCRIPTION

This project provides for the replacement of the existing Gold Mine Road Bridge over Hawlings River and the construction of an 8'-0" bike path between James Creek Court and Chandlee Mill Road. The existing bridge, built in 1958, is a one span 30' steel beam with an asphalt filled corrugated metal deck structure carrying a 15'-8" clear roadway with W-beam guardrail on each side, for a total deck width of 16'-7". The proposed replacement bridge includes a one span 53' prestressed concrete slab beam structure with a 33'-0" clear

roadway width. The project includes 250' of approach roadway work at each end of the bridge that consists of widening and raising the roadway profile by 5' at the bridge. The new bridge will carry 2 lanes of traffic, improve sight distances at the bridge, raise the bridge elevation to reduce flooding at the roadway, carry all legal vehicles, and provide pedestrian facilities across the river.

LOCATION

The project site is located along Gold Mine Bridge Road over the Hawlings River. It includes a bike path between James Creek Court and Chandlee Mill Road.

ESTIMATED SCHEDULE

The design of the project finished in the fall of 2017. The construction is scheduled to start in 2018 and be completed in 2020.

PROJECT JUSTIFICATION

The proposed replacement work is necessary to provide a safe roadway condition for the traveling public. The 2009 bridge inspection revealed that the concrete abutments and wing walls are in fair condition and the bridge has a weight restriction which is controlled by the undersized steel beams. The bridge is currently on a 6-month inspection cycle to allow some school buses to exceed the inventory rating values of the beams. The bridge is functionally obsolete, carries two lanes of traffic on a single lane bridge with no sidewalks and has inadequate sight distance approaching the bridge. The bridge is closed two to three times a year due to flooding of the Hawlings River.

OTHER

This project also supports the County Executive's Vision Zero initiative which aims to reduce injuries and fatalities on all roads.

FISCAL NOTE

The costs of bridge construction and construction management for this project are eligible for up to 80 percent Federal Aid. The design costs for this project are covered in the Bridge Design project (CIP No. 509132). FY23 funding switch of \$446,000 from G.O. Bonds to Federal Aid to reflect FY22 actuals.

DISCLOSURES

A pedestrian impact analysis has been completed for this project.

COORDINATION

Federal Highway Administration - Federal Aid Bridge Replacement/Rehabilitation Program, Maryland State Highway Administration, Maryland Department of the Environment, Maryland-National Capital Park and Planning Commission, Montgomery County Department of Permitting Services, Utilities, and Bridge Design PDF (CIP 509132).

