



Brighton Dam Road Bridge No. M-0229

(P501907)

Category	Transportation	Date Last Modified	05/20/22
SubCategory	Bridges	Administering Agency	Transportation
Planning Area	Olney and Vicinity	Status	Preliminary Design Stage

EXPENDITURE SCHEDULE (\$000s)

Cost Elements	Total	Thru FY22	Rem FY22	Total 6 Years	FY 23	FY 24	FY 25	FY 26	FY 27	FY 28	Beyond 6 Years
Planning, Design and Supervision	890	232	440	218	30	188	-	-	-	-	-
Construction	1,360	-	-	1,360	272	1,088	-	-	-	-	-
TOTAL EXPENDITURES	2,250	232	440	1,578	302	1,276	-	-	-	-	-

FUNDING SCHEDULE (\$000s)

Funding Source	Total	Thru FY22	Rem FY22	Total 6 Years	FY 23	FY 24	FY 25	FY 26	FY 27	FY 28	Beyond 6 Years
G.O. Bonds	750	-	224	526	101	425	-	-	-	-	-
Intergovernmental	1,500	232	216	1,052	201	851	-	-	-	-	-
TOTAL FUNDING SOURCES	2,250	232	440	1,578	302	1,276	-	-	-	-	-

APPROPRIATION AND EXPENDITURE DATA (\$000s)

Appropriation FY 24 Request	-	Year First Appropriation	FY19
Cumulative Appropriation	2,250	Last FY's Cost Estimate	2,250
Expenditure / Encumbrances	411		
Unencumbered Balance	1,839		

PROJECT DESCRIPTION

This project provides for the rehabilitation of the existing Brighton Dam Road Bridge No. M-0229 over Brighton Dam of Triadelphia Reservoir. This 602-foot long 15-span bridge, which is supported by Brighton Dam, is in need of repairs to the parapets, bridge deck joints, prestressed concrete beams, abutment backwalls, street lights, and approach roadways and sidewalks to enhance the safety of the traveling public and the integrity of the dam. The existing storm inlets on the approach roadways at both ends of the bridge will be improved as needed.

LOCATION

The project site is located at the Montgomery/Howard County Line approximately 1.2 miles east of the intersection of Brighton Dam Road and New Hampshire Avenue (MD 650) in Brookeville.

CAPACITY

Upon completion, the Average Daily Traffic (ADT) on the Brighton Dam Road Bridge will remain approximately 6,000 vehicles per day.

ESTIMATED SCHEDULE

The design is expected to be completed in the summer of 2022. Construction is scheduled to start in the spring of 2023 and be completed in the end of the year.

PROJECT JUSTIFICATION

This bridge, reconstructed in 1999, requires repairs to the 1,002-foot long west parapets, 642-foot long east parapets, sixteen bridge deck joints, prestressed concrete beams, abutment backwalls, street lights, and approach roadways and sidewalks. The parapets have severe concrete spalling at many parapet joints. Prestressed concrete beams and abutment backwalls have spalling and cracking. The approach roadways and sidewalks have settlement at both ends of the bridge. The bridge deck joints have failed, allowing water and deicing chemicals to flow through the bridge deck which resulted in corrosion and deterioration to the mechanized equipment for the dam operations. Some street lights and pole supports are damaged. The improvement of storm inlets was requested by WSSC to minimize storm runoff entering into the bridge deck surface from the approach roadways.

OTHER

The 2005 Olney Master Plan designates Brighton Dam Road as Arterial Road (A-15) with a minimum right-of-way of 80 feet. The December 2018 Montgomery County Bicycle Master Plan recommends bikeable shoulders. The deterioration of the bridge was identified through the County's 2019 biennial inspection program. The bridge rehabilitation was requested by WSSC to protect the newly reconstructed dam operation equipment. Funding for this project will be shared equally between Montgomery County, Howard County and WSSC in accordance with the February 16, 2021 Design and Construction Agreement. The funding shown as "Intergovernmental" is from Howard County and WSSC for their share of the project cost.

DISCLOSURES

A pedestrian impact analysis has been completed for this project.

COORDINATION

Washington Suburban Sanitary Commission, Howard County, Maryland Department of the Environment, Maryland Department of Natural Resources, Maryland-National Capital Park and Planning Commission, Montgomery County Department of Permitting Services, and U.S. Army Corps of Engineers.

