

Montgomery County Department of Transportation

Win 255 / Backville Pike Grossing Project

Purpose of the Project

The purpose of the project is to:

- Enhance / improve access to mass transit facilities
- Improve the mobility and safety of pedestrians and bicyclists crossing MD 355 / Rockville
 Pike and improve traffic operations at the intersection of South Wood Road / South
 Drive / MD 355



Project Goals and Objectives

Primary Goals:

- Improve pedestrian mobility between NNMC, NIH, and Medical Center Metrorail Station facilities through improved crossing of MD 355
- Improve pedestrian safety within the project area by minimizing conflicts with vehicular traffic
- Improve traffic operations to and from NNMC and NIH / Medical Center Metrorail Station at the MD 355 / South Wood Road / South Drive intersection



Project Goals and Objectives

Secondary Goals:

- Promote alternative modes of transportation such as rail, bus, car / vanpool, pedestrian, and bicycle commuting
- Improve efficiency with which emergency and transit vehicles move between the NIH and NNMC campuses



Preliminary Alternatives

- Alternative 1 No-Build
- Alternative 2 TSM/TDM
- Alternative 3 Grade Separation of MD 355 Under South Wood Road / South Drive
- Alternative 4 Diamond Interchange
- Alternative 5 Double Left Turns with Pedestrian/Bicyclist Crossing Options
- Alternative 6 Southbound Jug Handle with Pedestrian/Bicyclist Crossing Options
- Alternative 7 Northbound Jug Handle with Pedestrian/Bicyclist Crossing
 Options



Alternatives Retained for Detailed Study

- Alternative 1 No-Build
- Alternative 2A Pedestrian / Bicycle Underpass with At-Grade TSM Improvements
- Alternative 2B Pedestrian / Bicycle Underpass and Deep Elevators with At-Grade TSM Improvements
- Alternative 3 Grade Separation of MD 355 Under South Wood Road / South Drive



Evaluation Criteria

Primary Goals

- Pedestrian / Bicyclist Efficiency
- Pedestrian / Bicyclist Safety
- Traffic Operations
- Bus Operations
- Emergency Vehicle Operations

Impacts and Costs

- Adjacent Projects
- NNMC Gate
- Construction Impacts
- Natural Environment
- Cultural Resources
- Cost

Secondary Goals

- Alternative modes of travel would be more attractive to travelers
- Emergency vehicle and bus travel between NIH and NNMC would be more efficient



Primary Goals



MD 355 / Rockville Pike Crossing Project

Efficiency of Pedestrian and Bicycle Movements Summary

Alternative 2A

- · Decreases travel time for underpass users (68% of 7,530 total users) by 34 seconds
- Total travel time saved = 48.4 hours per day compared to the No-Build (11% improvement)
- · Improves access to/from mass transit facility

Alternative 2B

- Improves travel time for underpass and deep elevator users
- Decreases travel time for Metrorail users (78% of 7,530) by over 2 minutes (139 seconds)
- Total travel time saved = 237.4 hours per day compared to the No-Build (52% improvement)
- Provides the shortest average travel time (deep elevator route)
- · Improves access to/from mass transit facility

- Decreases travel time for overpass (all) users (100% of 7,530) by 68 seconds
- Total travel time saved = 142.2 hours per day compared to the No-Build (31% improvement)
- · Improves access to/from mass transit facility
- Improves travel time for non-Metro pedestrians crossing MD 355



Pedestrian / Bicyclist Safety Summary

Alternatives 2A and 2B

- Decreases pedestrian crossing volumes for those using at-grade crosswalk
- Provides opportunity for 100% avoidance of pedestrian/vehicular conflicts
- Reduces number of conflicts between pedestrians and vehicles at the intersection
- Maintains some conflicts with vehicles and wait times for remaining at-grade crossing users (could be safer if at-grade crossing was eliminated)
- Increases safety for underpass and deep elevator users
- Includes additional safety measures such as lighting, video surveillance, and emergency call boxes in the underpass

- Provides opportunity for 100% avoidance of pedestrian/vehicular conflicts
- Completely eliminates conflict points for pedestrians crossing MD 355 at South Wood Road / South Drive
- Creates new crosswalks at each end of the proposed jug handle
- Increases safety for pedestrians crossing South Wood Road / South Drive over MD 355



Traffic Operations Summary

Alternatives 2A & 2B

- Minor capacity enhancements provide a slight improvement over No-Build delay conditions
- Reducing the number of pedestrians crossing MD 355 at-grade would reduce intersection delay during the AM peak
- At-grade pedestrian crossings would prevent the optimal signal timing enhancements needed to improve overall LOS
- Overall peak hour network delays will be slightly higher than the No-Build condition



Traffic Operations Summary

- LOS and delay for both AM and PM peak periods will improve compared to 2030 No-Build and Alternatives 2A and 2B
- Improving South Wood Road / South Drive traffic operations may impact the network and nearby cross streets.
- Congestion and associated operational issues would be "redistributed," providing relief for some movements, but potentially worsening others.
- Overall peak hour network delays are projected to increase approximately 10 percent due to the redistribution of traffic patterns.



Compatibility with Bus Operations Summary

Alternative 2A / 2B

- · Shuttle routes remain the same as the No-Build condition
- Trips from the north experience slightly higher travel times compared to No-Build
- · Trips from the south experience slightly lower travel times compared to No-Build
- East/west trips experience slightly lower travel times compared to No-Build except for the PM period

- Routes to and from Medical Center Metro Station are different from No-Build
- Reduction in travel time for buses is due to the removal of pedestrian and bicycle movements
- · Trips from the north experience shorter travel time compared to No-Build
- Trips from the south experience longer travel time compared to No-Build
- East/west trips experience significant decreases in travel times compared to No-Build except for PM congestion from the east



Emergency Vehicle Operations Summary

Alternatives 2A and 2B

Routes and travel times same as No-Build

- · Decreases travel time from the north
- · Increases travel time from the south





Impacts and Costs

Compatibility with Adjacent Projects Summary

Coordination with the following project teams will need to continue for the duration of the project:

State Highway Administration Intersection Improvement Projects:

- MD 355 (Rockville Pike) and Cedar Lane
 - All build alternatives are compatible with the proposed improvements at the intersection
- MD 355 (Rockville Pike) and Jones Bridge Road
 - o Alternative 2A/2B: Requires minor limited disruptions associated with MOT and temporary reconstruction of the MD 355 median
 - o Alternative 3: Requires a temporary reconstruction of the channelized right-turn lane proposed by SHA

Montgomery County Facilities Study:

- Pedestrian / Bicycle and Transit Stop Enhancements
 - All build alternatives require temporary relocation and reconstruction of pedestrian facilities along the east side of MD 355



Compatibility with NNMC Gate Operations Summary

- · Storage provided under existing conditions is insufficient to meet demand
- · Storage provided for processing with Alternatives 2A and 2B is insufficient
- Storage provided for processing with Alternative 3 is sufficient
- Alternatives 2A and 2B operate the same as the No-Build when the MD 355/South Wood Road/South Drive intersection is considered in isolation
- Alternative 3 performs better than the No-Bulld when the new intersections (MD 355/Jug handle and South Drive/Jug handle) are analyzed in isolation
- The network delay is increased with all alternatives compared to No-Build



Compatibility with NNMC Gate Operations – Results

Required Storage Analysis

- Current Gate Location (Existing)
 - Guard house is approximately 285 feet from the MD 355/South Wood Road intersection
 - Single lane approach to guard house in AM and PM peak period
 - Observed traffic queues from the gate to the MD 355/South Wood Road intersection
 - Observed southbound MD 355 left turning vehicles sometimes queuing into the southbound MD 355 through lanes during the AM peak period
- Proposed Gate Location (2030 No-Build)
 - Guard house will be approximately 125 feet from the MD 355/South Wood Road intersection
 - · Two lanes approaching guard house in AM peak period only
 - · Available queue storage would decrease below the already insufficient approach to the gate
 - Creating two service lanes approaching NNMC gate may present operational issues between southbound left turning and northbound right turning vehicles

Scenario	Gate Location	# of Lanes	Storage Provided (Feet per Lane)	Calculated Storage Required (Feet per Lane)		% of Required Storage Provided	
				All Traffic Using NNMC Gate	SB Lefts Using NNMC Gate	All Traffic Using NNMC Gate	SB Lefts Using NNMC Gate
2010	Existing	1	285	884	639	32	45
	Relocated	2	125	486	351	26	36
2030 No-Bulld	Relocated	2	125	510	371	25	34



MD 355 / Rockville Pike Crossing Project

Compatibility with NNNC Gate Operations – Results

Required Storage Analysis

- Proposed Gate Location (Alternatives 2A and 2B)
 - · Guard house will be approximately 125 feet from the MD 355/South Wood Road intersection
 - · Two lanes approaching guard house in AM peak period only
 - Available queue storage would decrease below the already insufficient approach to the gate
 - Creating two service lanes approaching NNMC gate may present operational issues between southbound left turning and northbound right turning vehicles
- Proposed Gate Location (Alternative 3)
 - Guard house will be approximately 675 feet from the proposed South Drive intersection with the jughandle
 - Two lanes approaching guard house in both AM and PM peak periods
 - Available queue storage approaching the gate would increase
 - Creating two dedicated service lanes approaching NNMC gate does not present additional operational issues

	Gate Location	# of Lanes	Storage Provided (Feet per Lane)	Calculated Storage Required (Feet per Lane)		% of Required Storage Provided	
Scenario				All Traffic Using NNMC Gate	SB Lefts Using NNMC Gate	All Traffic Using NVMC Gate	SB Lefts Using NNMC Gate
2030 No-Build	Relocated	2	125	510	371	25	34
2030 Alts. 2A/2B	Relocated	2	125	510	371	25	34
2030 Alt. 3	Relocated	2	450 *	510	N/A	110	N/A



* After 450 feet with two lanes, one lane is provided for an additional 225 feet

MD 355 / Rockville Pike Crossing Project

Construction Impacts Summary

Alternatives 2A, 2B, and 3

- All existing travel lanes will be maintained during weekday peak hours on MD 355 (some lane closures during off-peak hours would be necessary)
- Compliance with design requirements (including ADA) will be maintained throughout construction
- Efforts will be made to relocate existing bus stops disturbed during construction
- · No gate closures are proposed at any time during any construction phase
- Alternatives 2A and 2B require a smaller construction footprint than Alternative 3
- Alternative 3 will require a temporary bridge to be constructed
- MOT costs range from:
 - \$1-2M (Alternative 2A)
 - \$2-3M (Alternative 2B)
 - \$6-7M (Alternative 3)



Environmental Impacts Summary

- Natural environment
 - · No impacts to wetlands, streams, floodplains, or parks
 - All alternatives cause impacts to trees
- · Cultural resources
 - Alternatives 2A and 2B have 0.8 acres of historic property impacts (likely No Adverse Effect)
 - Alternative 3 has 1.3 acres of historic property impacts (could result in an Adverse Effect)



ROW Impacts and Cost Estimates - Summary

- No displacements, relocations, or impacts to residential or commercial properties anticipated
- Costs include property acquisition, damages, and contingencies to cover unforeseen future costs
- Costs include final design, roadway construction, right-of-way, maintenance of traffic, and utility relocation costs
- Costs do not include operations and maintenance costs
- Pedestrian underpass and elevator construction costs based on July 2009 WMATA Medical Center Metrorail Station Access
 Improvement Study

ROW Impacts and Cost Estimates - Results

Feature		Alternative 2A	Alternative 2B	Alternative 3
Right-of-Way Impacts				
NIH Right-of-Way (acre	s)	0.60	0.60	3.14
NNMC Right-of-Way (a	cres)	0.52	0.53	1.23
Total Right-of-Way (acr	es)	1.12	1.13	4.37
Cost (2010 dollars)				
Design Cost (millions)		\$4 – 6	\$8 - 10	\$8 - 10
	NIH	\$1 - 4	\$1-4	\$10 – 20
Right-of-Way Cost (millions)^	NNMC	\$1 - 4	\$1 - 4	\$3 – 7
(**************************************	Total	\$4 - 8	\$4 - 8	\$15 – 25
Construction Cost (million	ons)	\$16 - 20	\$38 – 42	\$36 - 40
Total Cost (millions)		\$25 - 31	\$48 - 58	\$58 - 70



MD 355 / Rockville Pike Crossing Project



Accommodating Alternative Modes of Transportation Summary

Alternative 2A

- Decreases travel time for Metrorail users, pedestrians, and bicyclists crossing MD 355
- · Improves access to/from mass transit facility
- Reducing the number of pedestrians crossing MD 355 at-grade would reduce intersection delay during the AM peak

Alternative 2B

- Significantly decreases travel time for Metrorall users crossing MD 355
- Decreases travel time for pedestrians and bicyclists
- Improves access to/from mass transit facility
- Reducing the number of pedestrians crossing MD 355 at-grade would reduce intersection delay during the AM peak

- · Decreases travel time for Metrorail users, pedestrians, and bicyclists crossing MD 355
- Improves access to/from mass transit facility
- Completely eliminating conflicts between pedestrians and vehicles would reduce intersection delay





MD 355 / Rockville Pike Crossing Project

Connectivity Summary

Alternatives 2A and 2B

· Proposed improvements are similar to the No-Build condition

Alternative 3

Proposed improvement creates a direct connection between NIH and NNMC



Next Steps

- Present Team Recommendation at the BIC meeting on December 21, 2010
- Finalize MHT/Section 106 Coordination
- Complete Environmental Document and submit to FHWA in February 2011
- Meeting to determine lead agency for design/build and development of a MOU for implementation

