



| Sligo Park Hills Phase 2 LID Site Summary (Preliminary) | | | | | | | | | |
|---|---------|--------------|----------------------|---------------------------|---------------------|-----------------------|---------------------|---------|---------------------------|
| LID # | DA (ac) | % Impervious | Impervious Area (ac) | Treatment Required by ESD | | | Proposed Treatment | | |
| | | | | WQ, (cf) | P _r (in) | ESD _v (cf) | Volume Treated (cf) | PE (in) | Type of Facility Proposed |
| 40 | 0.19 | 23.2% | 0.044 | 178 | 1.60 | 285 | 317 | 1.8 | Parking Pad |
| 41 | 0.95 | 29.5% | 0.28 | 1,087 | 1.60 | 1,739 | 307 | 0.3 | Parking Pad |
| 42 | 0.23 | 29.1% | 0.067 | 261 | 1.60 | 417 | 261 | 1.0 | 6' x 4' Filterra |
| 43 | 0.21 | 29.5% | 0.062 | 241 | 1.60 | 385 | 241 | 1.0 | 6' x 4' Filterra |
| 44 | 0.28 | 48.9% | 0.137 | 498.40 | 1.80 | 897 | 360 | 0.7 | Shallow Parking Pad |
| 45 | 0.48 | 41.7% | 0.200 | 740.52 | 1.80 | 1333 | 980 | 1.3 | Parking Pad |
| 46 | 0.47 | 35.3% | 0.166 | 627.63 | 1.80 | 1130 | 1407 | 2.2 | Bioswale |
| 47 | 0.55 | 44.7% | 0.246 | 903.51 | 1.80 | 1626 | 1404 | 1.6 | Bioswale |
| 48 | 0.27 | 35.2% | 0.095 | 359.37 | 1.80 | 647 | 300 | 0.8 | Bioswale |
| 49 | 0.27 | 40.4% | 0.109 | 405.11 | 1.80 | 729 | 334 | 0.8 | Bioswale |
| 50 | 0.23 | 34.3% | 0.079 | 299.84 | 1.80 | 540 | 269 | 0.9 | Parking Pad |
| 51 | 0.27 | 47.8% | 0.129 | 470.45 | 1.80 | 847 | 372 | 0.8 | RAINSTORE |
| 52 | 0.39 | 42.8% | 0.167 | 616.37 | 1.80 | 1109 | 637 | 1.0 | RAINSTORE |
| 53 | 0.44 | 41.8% | 0.184 | 680.99 | 1.80 | 1226 | 743 | 1.1 | RAINSTORE |
| 54 | 0.11 | 45.5% | 0.050 | 183.32 | 1.80 | 330 | 183 | 1.0 | 6' x 4' Filterra |
| 55 | 0.35 | 38.3% | 0.134 | 501.30 | 1.80 | 902 | 260 | 0.5 | Shallow Bioswale |
| 56 | 0.093 | 54.8% | 0.051 | 183.50 | 1.80 | 330 | 149 | 0.8 | Shallow Bioswale |
| 57 | 0.080 | 45.0% | 0.036 | 132.13 | 1.80 | 238 | 122 | 0.9 | Shallow Bioswale |
| 58 | 0.34 | 40.0% | 0.14 | 506.02 | 1.80 | 911 | 1093 | 2.2 | Bioswale |
| 59 | 0.96 | 25.9% | 0.249 | 987.72 | 1.60 | 1580 | 1211 | 1.2 | Bioswale |
| Total | 7.16 | 36.6% | 2.62 | 9863 | 1.74 | 17202 | 10949 | 1.1 | |

Sequence of Construction

Note:
Contractor to provide temporary staging areas near individual facility sites, stabilized with mulch. These staging areas are not to be considered part of the limits of disturbance and not counted against the maximum 5,000 SF disturbed area requirement of the permit. Staging areas are to be removed and restored to original condition upon completion of work at a facility unless they will be used as a staging area for another facility.

1. Prior to clearing of trees, installing sediment control measures, or grading, a pre-construction meeting must be conducted on-site with the owner's representative, the contractor, and the site engineer.
2. This project is a moving project involving multiple facilities. No more than 5,000 SF shall be disturbed at any one time. Construction of each LID facility will follow a basic sequence outlined below:
 - a. The limits of disturbance must be field-marked prior to clearing of trees, installation of sediment control measures, construction, or other land disturbing activities.
 - b. Review accommodations to keep a new SWM offline to the greatest extent practical until it is ready to receive storm flows.
 - c. Install maintenance of traffic measures.
 - d. Demolish and remove existing infrastructure as noted on the plan.
 - e. If facility requires new storm drain inlet structure to be installed or replaced:
 - i. Excavate and remove existing inlet structure. Take care not to damage existing storm drain pipe.
 - ii. Install new storm drain inlet structure and all appurtenances.
 - f. If facility requires that new curb and gutter be installed, install new curb and gutter. Provide sand bag diversions in any curb openings to facility to prevent gutter flows from entering the work area.
 - g. Complete excavation of the facilities and haul off excess material.
 - h. Install under drains (if required by plan) and facility media (if required by plan). Complete soil amendments (if required by plan).
 - i. Final grade facility.
 - j. Install plantings and other landscaping.
 - k. Permanently stabilize entire disturbed area.



PROFESSIONAL CERTIFICATION, I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 11007, EXPIRATION DATE: 07/09/2012.



| NO. | REVISION | DATE | BY |
|-----|----------|------|----|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

MONTGOMERY COUNTY
DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION
ROCKVILLE, MARYLAND

RECOMMENDED FOR APPROVAL

Chief, Design Section _____ Date _____
APPROVED

Chief, Division of Capital Development _____ Date _____

Designed by: ZK/MMR Drawn by: ZK/MMR Checked by: WRP

ROW LID RETROFIT PROJECT
SLIGO PARK HILLS
KEY MAP SHEET

SCALE: AS SHOWN

TIOI

Project No.: 2008037.00_Task III

1 of 8