

BASELINE OF STREAM - BATCHELLORS RUN

DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS
POB	0+00.00	527,697.70	1,300,983.20		CC		527,779.20	1,301,413.98	61.00	PC	14+24.72	527,555.59	1,302,134.25		PT	18+83.36	527,461.60	1,302,496.01	
PC	0+74.97	527,652.40	1,301,042.93		PT	6+21.05	527,840.19	1,301,414.95		PI	14+47.05	527,537.98	1,302,147.97		PC	19+23.45	527,440.73	1,302,530.24	
PI	1+05.92	527,633.70	1,301,067.59		PT	6+21.05	527,840.19	1,301,414.95		CC		527,578.33	1,302,163.44	37.00	PI	19+37.23	527,433.55	1,302,542.01	
CC		527,779.88	1,301,139.62	160.00	PI	7+55.48	527,838.05	1,301,549.36		PT	14+64.90	527,541.91	1,302,169.96		CC		527,488.54	1,302,559.40	56.00
PT	1+36.12	527,625.54	1,301,097.45		CC		527,698.79	1,301,501.83		PC	15+41.37	527,555.37	1,302,245.23		PT	19+50.47	527,432.66	1,302,555.76	
PC	1+65.99	527,617.66	1,301,126.26		PT	7+97.81	527,810.92	1,301,585.65		PI	15+55.09	527,557.79	1,302,258.74		PC	19+73.22	527,431.18	1,302,578.45	
PI	1+92.20	527,610.76	1,301,151.54		PC	8+66.91	527,769.55	1,301,641.00		CC		527,484.50	1,302,257.91	72.00	PI	19+89.52	527,430.12	1,302,594.72	
CC		527,633.10	1,301,130.48	16.00	PI	8+92.18	527,754.42	1,301,661.24		PT	15+68.49	527,555.07	1,302,272.18		CC		527,409.22	1,302,577.02	22.00
PT	1+98.72	527,636.40	1,301,146.14		CC		527,833.62	1,301,688.90	80.00	PC	15+86.97	527,551.40	1,302,290.30		PT	20+01.27	527,414.25	1,302,598.44	
PC	2+43.91	527,680.62	1,301,136.82		PRC	9+15.86	527,753.66	1,301,686.49		PI	15+94.02	527,550.01	1,302,297.21		PC	20+30.97	527,385.34	1,302,605.22	
PI	2+53.74	527,690.24	1,301,134.79		PI	9+53.30	527,752.54	1,301,723.92		CC		527,572.96	1,302,294.66	22.00	PI	20+41.59	527,375.00	1,302,607.65	
CC		527,684.74	1,301,156.39	20.00	CC		527,661.70	1,301,683.73	92.00	PT	16+00.60	527,552.88	1,302,303.64		CC		527,367.30	1,302,528.31	79.00
PT	2+62.19	527,697.73	1,301,141.17		PT	9+86.98	527,725.60	1,301,749.92		PC	16+25.33	527,562.96	1,302,326.21		PT	20+52.08	527,364.38	1,302,607.26	
PC	3+07.75	527,732.38	1,301,170.75		PC	10+81.92	527,657.29	1,301,815.86		PI	16+34.55	527,566.72	1,302,334.63		PC	20+60.17	527,356.31	1,302,606.96	
PI	3+40.96	527,757.64	1,301,192.31		PI	11+09.87	527,637.18	1,301,835.27		CC		527,519.13	1,302,345.78	48.00	PI	20+78.25	527,338.24	1,302,606.29	
CC		527,699.92	1,301,208.78	50.00	CC		527,714.24	1,301,874.86	82.00	PT	16+43.56	527,567.09	1,302,343.85		CC		527,354.24	1,302,662.92	56.00
PT	3+66.37	527,747.57	1,301,223.94		PT	11+35.80	527,633.12	1,301,862.93		PC	17+37.38	527,570.87	1,302,437.59		PT	20+95.14	527,323.19	1,302,616.32	
PC	4+28.43	527,728.75	1,301,283.09		PI	12+43.10	527,617.51	1,301,969.10		PI	18+08.03	527,573.71	1,302,508.19		PC	21+97.77	527,237.78	1,302,673.22	
PI	4+73.88	527,714.97	1,301,326.39		PI	13+29.35	527,594.60	1,302,052.25		CC		527,518.91	1,302,439.69	52.00	PI	22+20.69	527,218.71	1,302,685.93	
CC		527,773.53	1,301,297.34	47.00	PC	13+62.68	527,590.28	1,302,085.29		PT	18+34.75	527,505.46	1,302,489.92		CC		527,281.03	1,302,738.13	78.00
PT	5+00.68	527,757.78	1,301,341.62		PI	13+87.32	527,587.09	1,302,109.72		PC	18+52.52	527,488.30	1,302,485.32		PT	22+42.35	527,209.54	1,302,706.93	
PC	5+45.11	527,799.64	1,301,356.51		CC		527,530.79	1,302,077.52	60.00	PI	18+70.48	527,470.95	1,302,480.68		POE	22+49.83	527,206.55	1,302,713.79	
PI	5+88.89	527,840.89	1,301,371.18		PT	14+09.43	527,567.65	1,302,124.86		CC		527,482.09	1,302,508.51	24.00					

BASELINE OF STREAM - SHERWOOD

DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS
POB	76+50.00	513,443.28	1,306,927.15		PI	83+99.63	513,080.27	1,306,417.66		PT	88+08.57	512,782.28	1,306,167.25		CC		512,415.57	1,305,594.73	120.00
PC	77+17.46	513,413.84	1,306,866.46		CC		513,028.46	1,306,467.80	50.00	PC	88+66.99	512,728.16	1,306,145.27		PT	95+71.89	512,302.10	1,305,633.80	
PI	77+45.87	513,401.45	1,306,840.89		PT	84+28.13	513,028.33	1,306,417.80		PI	88+89.45	512,707.34	1,306,136.82		PC	95+80.41	512,299.33	1,305,625.75	
CC		513,341.86	1,306,901.36	80.00	PC	84+38.87	513,017.59	1,306,417.83		CC		512,743.21	1,306,108.21	40.00	PI	96+09.91	512,289.73	1,305,597.85	
PT	77+72.05	513,375.71	1,306,828.88		PI	84+87.41	512,969.05	1,306,417.97		PT	89+07.93	512,703.73	1,306,114.65		CC		512,166.96	1,305,671.32	140.00
PC	78+79.19	513,278.63	1,306,783.55		CC		513,017.46	1,306,367.83	50.00	PC	89+17.03	512,702.26	1,306,105.66		PT	96+38.56	512,269.68	1,305,576.20	
PI	79+19.59	513,242.02	1,306,766.46		PT	85+15.93	512,967.48	1,306,369.45		PI	89+41.25	512,698.36	1,306,081.76		PC	97+25.85	512,210.38	1,305,512.16	
CC		513,295.55	1,306,747.31	40.00	PC	85+32.10	512,966.96	1,306,353.28		CC		512,643.04	1,306,115.32	60.00	PI	97+42.29	512,199.21	1,305,500.10	
PT	79+42.42	513,259.47	1,306,730.03		PI	85+55.52	512,966.20	1,306,329.88		PT	89+63.07	512,678.97	1,306,067.26		CC		512,063.63	1,305,648.04	200.00
PC	79+97.22	513,283.15	1,306,680.60		CC		512,926.98	1,306,354.58	40.00	PC	90+92.62	512,575.20	1,305,989.70		PT	97+58.65	512,186.22	1,305,490.02	
PI	80+41.94	513,302.47	1,306,640.27		PT	85+74.47	512,945.43	1,306,319.08		PI	91+21.97	512,551.69	1,305,972.12		PC	97+64.51	512,181.59	1,305,486.43	
CC		513,251.59	1,306,665.48	35.00	PC	86+01.52	512,921.42	1,306,306.61		CC		512,694.93	1,305,829.50	200.00	PI	97+84.06	512,166.14	1,305,474.44	
PT	80+60.69	513,258.68	1,306,631.21		PI	86+15.80	512,908.76	1,306,300.03		PRC	91+50.91	512,534.22	1,305,948.54		CC		512,255.15	1,305,391.62	120.00
PC	80+69.41	513,250.15	1,306,629.44		CC		512,958.31	1,306,235.62	80.00	PI	91+64.67	512,526.02	1,305,937.48		PT	98+03.28	512,155.30	1,305,458.17	
PI	80+92.06	513,227.97	1,306,624.84		PT	86+29.77	512,899.15	1,306,289.47		CC		512,393.59	1,306,052.70	175.00	PC	98+27.26	512,142.00	1,305,438.22	
CC		513,258.26	1,306,590.27	40.00	PC	86+50.71	512,885.06	1,306,273.99		PT	91+78.38	512,516.20	1,305,927.83		PI	98+49.76	512,129.52	1,305,419.50	
PT	81+10.62	513,220.50	1,306,603.46		PI	86+74.21	512,869.23	1,306,256.61		PC	92+86.75	512,438.88	1,305,851.91		CC		512,058.79	1,305,493.68	100.00
PC	81+51.19	513,207.12	1,306,565.17		CC		512,811.10	1,306,341.30	100.00	PI	93+14.11	512,419.36	1,305,832.74		PT	98+71.52	512,110.22	1,305,407.92	
PI	81+94.72	513,192.76	1,306,524.07		PT	86+96.88	512,847.32	1,306,248.09		CC		512,473.91	1,305,816.23	50.00	PC	98+87.17	512,096.80	1,305,399.87	
CC		513,155.20	1,306,583.31	55.00	PC	87+12.19	512,833.05	1,306,242.55		PT	93+36.82	512,424.98	1,305,805.96		PI	99+14.06	512,073.74	1,305,386.04	
PT	82+24.84	513,149.46	1,306,528.61		PI	87+37.38	512,809.57	1,306,233.42		PC	93+61.10	512,429.97	1,305,782.20		CC		512,114.80	1,305,369.86	35.00
PC	82+64.11	513,110.40	1,306,532.71		CC		512,847.54	1,306,205.26	40.00	PI	94+13.96	512,440.82	1,305,730.47		PT	99+33.03	512,081.16	1,305,360.19	
PI	82+98.63	513,076.07	1,306,536.31		PT	87+57.15	512,807.66	1,306,208.30		CC		512,371.25	1,305,769.87	60.00	POE	99+74.50	512,092.62	1,305,320.34	
CC		513,107.27	1,306,502.87	30.00	PC	87+64.21	512,807.12	1,306,201.27		PT	94+47.76	512,390.88	1,305,713.17						
PT	83+15.43	513,077.29	1,306,501.81		PI	87+88.99	512,805.23	1,306,176.57		PC	94+63.20	512,376.30	1,305,708.12						
PC	83+47.69	513,078.43	1,306,469.57		CC		512,767.24	1,306,204.31	40.00	PI	95+21.59	512,321.12	1,305,689.01						


BASELINE OF STREAM - WOODLAWN

DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS	DESCRIPTION	STATION	NORTHING	EASTING	RADIUS
POB	40+00.00	533,407.63	1,306,681.06		PT	44+22.97	533,015.82	1,306,788.73		PI	49+09.15	532,571.44	1,306,788.62		PT	54+88.04	532,247.80	1,306,378.92	
PC	40+30.52	533,377.13	1,306,679.98		PC	44+87.86	532,950.96	1,306,790.68		CC		532,576.07	1,306,735.36	50.00	PC	54+96.85	532,242.50	1,306,371.88	
PI	40+45.36	533,362.30	1,306,679.45		PI	45+03.44	532,935.39	1,306,791.15		PT	49+26.41	532,554.38	1,306,780.41		PI	55+39.79	532,216.70	1,306,337.56	
CC		533,373.59	1,306,779.91	100.00	CC		532,952.46	1,306,840.65	50.00	PC	49+78.68	532,507.28	1,306,757.74		CC		532,206.54	1,306,398.93	



SEQUENCE OF CONSTRUCTION

1. NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION AT (410) 537-3510 FOR THE REQUIRED PRE-CONSTRUCTION MEETING AT LEAST SEVEN DAYS BEFORE COMMENCING LAND DISTURBING ACTIVITIES.
2. INSTALL TREE PROTECTION FENCING AS SHOWN ON THE PLAN.
3. COMPLETE TREE REMOVAL AND SELECTIVE TRIMMING AS SHOWN ON THE PLAN OR AS DIRECTED BY THE CONTRACTING OFFICER'S REPRESENTATIVE.
4. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED OVERNIGHT UNLESS RUNOFF IS DIRECTED TO AN APPROVED MDE SEDIMENT CONTROL DEVICE.
PHASE B-1 (UPSTREAM OF LAYHILL ROAD)
5. CLEAR AND GRUB ONLY THOSE AREAS NECESSARY TO INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.
6. INSTALL STABILIZED CONSTRUCTION ENTRANCES FROM CHAPEL HILL ROAD AND LAYHILL ROAD AND BUILD THE ASSOCIATED TEMPORARY ACCESS ROAD. STABILIZE AT THE END OF EACH WORK DAY. FOR THE ACCESS ROAD WITHIN A WETLAND, PLACE TIMBER MATS TO MINIMIZE IMPACTS.
7. INSTALL SILT FENCE AS DESIGNATED ON THE PLANS.
8. CLEAR AND GRUB REMAINING WORK AREA ABOVE LAYHILL ROAD. ANY DISTURBANCE CAUSED BY THIS PROCESS SHALL BE STABILIZED BY THE END OF THE DAY.
9. INSTALL PUMP-AROUND FLOW DIVERSION AND DEWATER THE CONSTRUCTION ZONE THROUGH THE APPROVED DEWATERING DEVICE. THE CONTRACTOR SHALL STAGE THE LIMITS OF THE PUMP-AROUND FLOW DIVERSION TO DEWATER ONLY THAT SECTION SCHEDULED FOR THAT DAY'S WORK. AT THE END OF EACH WORK DAY THE WORK AREA SHALL BE STABILIZED, THE PUMP-AROUND PRACTICE REMOVED, AND THE FLOW RESTORED TO THE CHANNEL. WORK SHALL BE COMPLETED ONLY DURING FORECASTED PERIODS OF DRY WEATHER.
10. CONSTRUCT STREAM IMPROVEMENTS ABOVE LAYHILL ROAD BEGINNING UPSTREAM TO DOWNSTREAM. THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO MINIMIZE UNNECESSARY DISTURBANCE. FOR THE STREAM IMPROVEMENTS, ONLY THAT AMOUNT OF WORK SHALL BE COMPLETED THAT CAN BE STABILIZED BY THE END OF THE DAY.
11. ONCE ALL STREAM WORK UPSTREAM OF LAYHILL ROAD HAS BEEN COMPLETED AND PERMANENTLY STABILIZED, REMOVE THE ASSOCIATED ACCESS ROAD, SILT FENCE AND STABILIZED CONSTRUCTION ENTRANCES. PERMANENTLY STABILIZE ALL AREAS DISTURBED BY THIS PROCESS IN ACCORDANCE WITH THE PLANS.
PHASE B-2 (DOWNSTREAM OF LAYHILL ROAD)
12. CLEAR AND GRUB ONLY THOSE AREAS NECESSARY TO INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.
13. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND ASSOCIATED ACCESS ROAD FOR WORK AREA DOWNSTREAM OF LAYHILL ROAD. STABILIZE AT THE END OF EACH WORK DAY.
14. CLEAR AND GRUB REMAINING WORK AREA ABOVE LAYHILL ROAD. ANY DISTURBANCE CAUSED BY THIS PROCESS SHALL BE STABILIZED BY THE END OF THE DAY.
15. INSTALL PUMP-AROUND FLOW DIVERSION AND DEWATER THE CONSTRUCTION ZONE THROUGH THE APPROVED DEWATERING DEVICE. THE CONTRACTOR SHALL STAGE THE LIMITS OF THE PUMP-AROUND FLOW DIVERSION TO DEWATER ONLY THAT SECTION SCHEDULED FOR THAT DAY'S WORK. AT THE END OF EACH WORK DAY THE WORK AREA SHALL BE STABILIZED, THE PUMP-AROUND PRACTICE REMOVED, AND THE FLOW RESTORED TO THE CHANNEL. WORK SHALL BE COMPLETED ONLY DURING FORECASTED PERIODS OF DRY WEATHER.
16. CONTINUE STREAM IMPROVEMENTS DOWNSTREAM OF LAYHILL ROAD WORKING FROM DOWNSTREAM TO UPSTREAM. UPON COMPLETION OF THE WORK, PERMANENTLY STABILIZE ALL DISTURBED AREAS WITHIN THE CHANNEL.
17. WITH APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING MAINTENANCE OF STREAMFLOW DEVICES, ACCESS ROAD, AND STABILIZED CONSTRUCTION ENTRANCE. STABILIZE ALL AREAS DISTURBED DURING THIS PROCESS.



VICINITY MAP
Copyright ADC The Map People
Permitted Use No. 21003214
Expiration: 04/01/12

SITE INFORMATION - BATCHELLORS	
A. TOTAL AREA OF FACILITY (Base, Campus, Park, Etc.)	27.3 Acres
B. TOTAL AREA OF PROJECT SITE	27.3 Acres
C. AREA DISTURBED	4.71 Acres
D. AREA TO BE ROOFED OR PAVED	0.00 Acres
E. TOTAL CUT	9,748 CY
F. TOTAL FILL	2,654 CY
G. OFF-SITE WASTE/BORROW AREA LOCATION	TBD

FOR COMBINED SITE INFORMATION REFER TO DRAWING GN-10

- NOTES:
1. STOCKPILE AREA SHALL BE LOCATED AT AN MDE APPROVED OFF-SITE LOCATION.
 2. MAINTENANCE OF TRAFFIC IS THE RESPONSIBILITY OF THE CONTRACTOR.

LEGEND			
— WUS —	WATERS OF THE U.S.	()	LIVE FASCINES
— B —	WETLAND BUFFER	()	ROCK J-HOOK VANE
()	WETLAND AREA	()	ROCK CROSS VANE
— 3.54 —	EXISTING CONTOURS	()	PROPOSED RIFFLE GRADE CONTROL
— 2.20 —	PROPOSED CONTOURS	()	PROP. BURIED LOG
()	EXIST. SAN. SEWER MANHOLE	()	LOG CROSS VANE
()	EXIST. STORMDRAIN MANHOLE	()	LOG J-HOOK VANE
()	EXISTING TREE >24" DBH	()	LOG MEANDER PROTECTION STRUCTURE
()	TREE TO BE REMOVED	()	



RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0228
(F) 703 246-0123

DATE	DESCRIPTION	MARK

Date	10/4/2011
Design file no.	
Dwg no.	BR-1
AS SHOWN	
Designed by	SPB
Drawn by	DEA
Checked by	REP
Reviewed by	TWH
Submitted by	CMK
U.S. ARMY ENGINEER DIVISION	
CORPS OF ENGINEERS	
BALTIMORE, MARYLAND	
W912DR-07-0-0008	
Task Order No. 19	

**BATCHELLORS RUN I & II
COVER SHEET**

Sheet Number:
5 OF 72



- NOTES:
1. ONLY TREES WITH A DBH >24" ARE SHOWN UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC AND THE GOLF COURSE.
 3. THE CONTRACTOR SHALL PROTECT ALL IRRIGATION LINES.




RK&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by: REP Dwn by: DEA	Chd by: SPB	Date: 10/4/2011
W912DR-07-D-0008 Task Order No. 19	Reviewed by: TMH Submitted by: CVK	Drawing code: BR-3	Design file no. Drawing scale: 1"=30'

**BATCHELLORES RUN I & II
SITE PLAN**




- NOTES:
1. ONLY TREES WITH A DBH >24" ARE SHOWN UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC AND THE GOLF COURSE.
 3. THE CONTRACTOR SHALL PROTECT ALL IRRIGATION LINES.




MARK	DESCRIPTION	DATE	APPR

Designed by: REP	Checked by: SPB	Date: 10/4/2011
Dwn by: DEA	Reviewed by: TMH	Design file no.
Submitted by: CVK	Drawing code: BR-4	Dwg scale: 1"=30'
U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND		Task Order No. 19

**BACHELLORS RUN I & II
SITE PLAN**



STREAM PROFILE - BATCHELLORS RUN
 SCALE: 1" = 10' (VERT.)
 1" = 30' (HORIZ.)



STREAM PROFILE - BATCHELLORS RUN
 SCALE: 1" = 10' (VERT.)
 1" = 30' (HORIZ.)

NOTE: VERTICAL STATIONING AND ADDITIONAL PROFILE DETAILS TO BE ADDED FOR NEXT SUBMISSION




RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0128
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by:	SBP	Date:	10/4/2011
	Dwn by:	DEA	Design file no.:	
W912DR-07-D-0008 Task Order No. 19	Reviewed by:	TWH	Drawing code:	BR-5
	Submitted by:	CVK	Dwg scale:	AS SHOWN

**BATCHELLORS RUN I & II
 PROFILE**

Sheet Number:
 9 OF 72



STREAM PROFILE - BATCHELLORS RUN
 SCALE: 1" = 10' (VERT.)
 1" = 30' (HORIZ.)

NOTE: VERTICAL STATIONING AND ADDITIONAL PROFILE DETAILS TO BE ADDED FOR NEXT SUBMISSION




MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	Date:
CORPS OF ENGINEERS	REP	10/4/2011
BALTIMORE, MARYLAND	Dwn by: DEB	Design file no.
	Crtd by: SPB	
	Reviewed by: TMH	Drawing code: BR-6
	Submitted by: CVK	Dwg status: AS SHOWN
		Task Order No. 19

BATCHELLORS RUN I & II
PROFILE

Sheet Number:
 10 OF 72



- NOTES:
1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELD UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.
 4. CONTOURS BEYOND SURVEY LIMITS WERE GENERATED FROM COUNTY LIDAR DATA USING A 2-FOOT CONTOUR INTRVAL.



RK&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0128
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by:	REP	Date:	10/4/2011
Drawn by:	DEA	Design file no.:	
Reviewed by:	TWH	Drawing code:	BR-9
Submitted by:	CVK	Dwg scale:	1"=30'
U.S. ARMY ENGINEER DIVISION	CORPS OF ENGINEERS	BALTIMORE, MARYLAND	Task Order No. 19

**BACHELLORS RUN I & II
 EROSION & SEDIMENT
 CONTROL PLAN**

Sheet
 Number:
 13 OF 72



US Army Corps
of Engineers
Baltimore District




9302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0028
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR


U.S. ARMY ENGINEER DIVISION	Designed by:	REP	Date:	10/4/2011
CORPS OF ENGINEERS	Dwn by:	DEA	Design file no.	
BALTIMORE, MARYLAND	Reviewed by:	TMH	Drawing code:	BR-10
W912DR-07-D-0008	Submitted by:	CVK	Dwg scale:	1"=30'
Task Order No. 19				

**BACHELLOORS RUN I & II
EROSION & SEDIMENT
CONTROL PLAN**

Sheet
Number:
14 OF 72



- NOTES:
1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.



- NOTES:
1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.
 4. 100-YR FLOODPLAIN LIMIT IS BEYOND THE NORTHERN LIMITS OF THE PROJECT.

HOSES FROM UPSTREAM PUMP-AROUND AND DEWATERING DEVICE SHALL OUTFALL ONTO A STABILIZED OUTFALL POINT BEYOND DOWNSTREAM FLOW BARRIER

REMOVE ASPHALT PAVEMENT UNDER STABILIZED CONSTRUCTION ENTRANCE PRIOR TO INSTALLATION



RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by: REP	Checked by: SPB	Date: 10/4/2011	Design file no.
Dwn by: DEA	Reviewed by: TWH	Drawing code: BR-11	Dwg scale: 1"=30'
Submitted by: CVK	Task Order No. 19	U.S. ARMY ENGINEER DIVISION	CORPS OF ENGINEERS
		BALTIMORE, MARYLAND	W912DR-07-0-0008
			Task Order No. 19


**BACHELORS RUN I & II
 EROSION AND SEDIMENT
 CONTROL PLAN**

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	DATE:	DESIGNED BY:	DATE:
CORPS OF ENGINEERS	10/4/2011	MMI	10/4/2011
BALTIMORE, MARYLAND		Dwn by: CKD	Design file no.
		DEA	REP
		Reviewed by: TMH	Drawing code: BR-15
		Submitted by: CVK	Dwg scales:

U.S. ARMY ENGINEER DIVISION	Task Order No. 19
CORPS OF ENGINEERS	W912DR-07-D-0008
BALTIMORE, MARYLAND	


**BACHELLORS RUN I & II
PLANTING PLAN**



LEGEND


NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN FOREST	
NATIVE FLOODPLAIN SHRUB	
SOD	
TREE PROTECTION FENCE	— TPF —
STUDY AREA	— — — — —
PROPERTY BOUNDARY	— — — — —
PROPOSED CONTOUR	— 120 —
EXISTING CONTOUR	— 120 —
LIMIT OF DISTURBANCE	— LOD —
WATERS OF THE US	— WUS —
WETLAND BUFFER	— B —
WETLANDS	
PROPOSED TREE LINE	— — — — —
EXISTING TREE LINE	— — — — —

- PLANTING NOTES**
- The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
 - The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
 - All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
 - See Sheet 22 for planting schedules.



E 1302250
N 527250

MATCH LINE SEE SHEET BR-16



LEGEND	
NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN SHRUB	
UPLAND WILDFLOWER	
SOD	
STUDY AREA	
PROPERTY BOUNDARY	
PROPOSED CONTOUR	
EXISTING CONTOUR	
LIMIT OF DISTURBANCE	
WATERS OF THE US	
WETLAND BUFFER	
WETLANDS	
PROPOSED TREE LINE	
EXISTING TREE LINE	

- PLANTING NOTES**
1. The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
 2. The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
 3. All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
 4. See Sheet 22 for planting schedules.

E 1302250
N 527250

30' 0 30' 60'
SCALE: 1" = 30'



RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0128
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by:	WMM	Checked by:	REP	Date:	10/4/2011
Dwn by:	DEA	Reviewed by:	TWH	Design file no.:	
Submitted by:	CVK	Drawing code:	BR-17	Dwg scale:	1"=30'
U.S. ARMY ENGINEER DIVISION	CORPS OF ENGINEERS	BALTIMORE, MARYLAND	W912DR-07-D-0008	Task Order No.:	19

**BACHELLOORS RUN I & II
PLANTING PLAN**

Sheet Number:
21 OF 72

NATIVE FLOODPLAIN FOREST

Size (acres): **0.05**

Overall Minimum Spacing-feet on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	TYPE	Placement
15	200	TREES							
		20	2	<i>Acer rubrum</i>	Red Maple	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		15	1	<i>Liriodendron tulipifera</i>	Tulip Poplar	FACU	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		10	1	<i>Nyssa sylvatica</i>	Black Gum	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		20	2	<i>Platanus occidentalis</i>	American Sycamore	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		15	2	<i>Quercus palustris</i>	Pin Oak	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		20	2	<i>Betula nigra</i>	River Birch	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		100.0	10	=total					
7	300	SHRUBS							
		25	4	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24" ht.	Cont.	Clustered @ 7' OC
		25	4	<i>Lindera benzoin</i>	Spice Bush	FACW	18-24" ht.	Cont.	Clustered @ 7' OC
		30	5	<i>Viburnum prunifolium</i>	Blackhaw	FACU	18-24" ht.	Cont.	Clustered @ 7' OC
		20	2	<i>Viburnum dentatum</i>	Southern Arrowwood	FAC	18-24" ht.	Cont.	Clustered @ 7' OC
		100.0	15	=total					
NA	20	NATIVE PERMANENT SEED							
		34	0.34	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%
		33	0.33	<i>Elymus canadensis</i>	Canada Wild Rye	FAC	Seed	NA	Lb. of P.L.S. 76%
		33	0.33	<i>Panicum clandestinum</i>	Deer Tongue	FAC	Seed	NA	Lb. of P.L.S. 76%
		100.0	1.00	=total					

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES

NATIVE UPLAND FOREST


Size (acres): **1.39**

Overall Minimum Spacing-feet on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	TYPE	Placement
15	200	TREES							
		20	56	<i>Acer rubrum</i>	Red Maple	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		15	41	<i>Liriodendron tulipifera</i>	Tulip Poplar	FACU	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		10	28	<i>Nyssa sylvatica</i>	Black Gum	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		20	56	<i>Platanus occidentalis</i>	American Sycamore	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		15	41	<i>Quercus palustris</i>	Pin Oak	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		20	56	<i>Quercus rubra</i>	Northern Red Oak	FACU	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC
		100.0	278	=total					
10	300	SHRUBS							
		25	104	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24" ht.	Cont.	Clustered @ 7' OC
		25	104	<i>Lindera benzoin</i>	Spicebush	FACW-	18-24" ht.	Cont.	Clustered @ 7' OC
		20	84	<i>Viburnum acerifolium</i>	Mapleleaf viburnum	UPL	18-24" ht.	Cont.	Clustered @ 7' OC
		30	125	<i>Viburnum dentatum</i>	Southern Arrowwood	FAC	18-24" ht.	Cont.	Clustered @ 7' OC
		100.0	417	=total					
NA	20	NATIVE PERMANENT SEED							
		33.3	9.3	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%
		33.3	9.3	<i>Elymus canadensis</i>	Canada Wild Rye	FAC	Seed	NA	Lb. of P.L.S. 76%
		33.4	9.3	<i>Panicum clandestinum</i>	Deer Tongue	FAC	Seed	NA	Lb. of P.L.S. 76%
		100.0	27.9	=total					

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES

GENERAL NOTES


- The landscaping shown on sheets 19-21 must be planted in accordance with the latest edition of Landscape Specification Guidelines, developed by the MD-DC-VA Chapter of the Landscape Contractors Association.
- All plants must meet the standards of the latest edition of American Standard for Nursery Stock sponsored by the Association of American Nurserymen.
- Plant type substitutions are permitted with verbal or written approval from the Planning and Code Administration.
- All trees are to be located a minimum distance of 5 feet from all utility boxes, 5 feet from a storm drain inlet or manhole, 10 feet from a fire hydrant, 15 feet from public street lights, 5 feet from driveway aprons, 20 feet from any traffic control sign and at least 30 feet from any intersection.
- Shrubs to be planted in groups of 7-10 plants.
- Soil conditions must be tested, verified and adjusted by the landscape contractor to ensure that appropriate soil composition and PH levels are suitable for plant materials specified for that specific location.
- Any planting within a forest retention area, as designated on the Forest conservation plan and shown on this plan, must be carried out in such a way as to avoid any adverse impact to the roots of existing trees.
- All plant material will be reinspected for survival by the Planning and Code Administration one year following installation. A 10 percent maintenance bond will be retained during this time period.
- Plant installation shall include a 2 year maintenance period.



- NOTES:
- If surrounding soil is compacted as determined by the engineer, an area up to 5 times the diameter of the root mass shall be excavated or retortified to a depth.
 - Do not damage or cut leader.

TREE PLANTING - CONTAINER GROWN

N.T.S.



SHRUB PLANTING - CONTAINER

N.T.S.

NATIVE FLOODPLAIN SHRUB

Size (acres): **0.28**

Overall Minimum Spacing-feet on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	TYPE	Placement
	436	TREES							
		33	41	<i>Clethra alnifolia</i>	Sweet Pepperbush	FAC+	18-24" ht.	Cont.	Clustered @ 6' OC
		33	41	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24" ht.	Cont.	Clustered @ 8' OC
		34	40	<i>Ilex verticillata</i>	Winterberry	FACW+	18-24" ht.	Cont.	Clustered @ 8' OC
		100.0	122	=total					
NA	40	NATIVE SEED							
		30	3.3	<i>Andropogon gerardii</i>	Big Bluestem	FAC	SEED	NA	Lb. of P.L.S. 76%
		40	4.5	<i>Elymus virginicus</i>	Virginia Wild Rye	FACW	SEED	NA	Lb. of P.L.S. 76%
		30	3.4	<i>Panicum clandestinum</i>	Deer Tongue	FACW	SEED	NA	Lb. of P.L.S. 76%
		100.0	11.2	=total					

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES


UPLAND WILDFLOWER SEED

Size (acres): **0.18**

Overall Minimum Spacing-feet on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	ECOTYPE	Placement
NA	30	SEED							
		2	0.11	<i>Asclepias tuberosa</i>	Butterfly Milkweed	NI	SEED	NA	Lb. of P.L.S. 76%
		10	0.54	<i>Chamaecrista fasciculata</i>	Partridge Pea	FACU	SEED	PA	Lb. of P.L.S. 76%
		15	0.81	<i>Elymus riparius</i>	Riverbank Wild Rye	FACW	SEED	PA	Lb. of P.L.S. 76%
		3	0.16	<i>Monarda fistulosa</i>	Wild Bergamot	UPL	SEED	NA	Lb. of P.L.S. 76%
		6	0.32	<i>Rudbeckia hirta</i>	Black Eyed Susan	FACU-	SEED	CP NC	Lb. of P.L.S. 76%
		25	1.35	<i>Schizachyrium scoparium</i>	Little Bluestem	FACU-	SEED	E. U.S.	Lb. of P.L.S. 76%
		6	0.32	<i>Senna hebecarpa</i>	Wild Senna	FAC	SEED	VA & WV	Lb. of P.L.S. 76%
		5	0.28	<i>Senna marilandica</i>	Maryland Senna	FAC+	SEED	NA	Lb. of P.L.S. 76%
		10	0.54	<i>Sorghastrum nutans</i>	Indiangrass	UPL	SEED	PA	Lb. of P.L.S. 76%
		3	0.16	<i>Tradescantia virginiana</i>	Virginia Spiderwort	FACU	SEED	SE PA/N VA	Lb. of P.L.S. 76%
		15	0.81	<i>Tridens flavus</i>	Purple Top	FACU	SEED	SE VA	Lb. of P.L.S. 76%
		100.0	5.40	=total					

Seed Mix equivalent to ERNMX-172


SOD SIZE (ACRES): 0.24 SIZE (SF): 10,565



- Make cut with sharp knife through Coir Fiber Matting - Solid line in diagram
- Pin back Coir Fiber with 4 staples - dashed line in diagram
- Install plant through pinned back Coir Fiber. Install plant at proper grade to ground plane
- Remove 4 staples
- For tree installations, install tree stakes through Coir Matting to ground
- Install deer protection
- Place 4 staples in each of four cut sections. Re-anchor Coir Matting to ground


TREE & SHRUB INSTALLATION THROUGH COIR FIBER MATTING

N.T.S.



NATURALIZED PLANT SPACING

N.T.S.



TREE SHELTER DETAIL

N.T.S.


- NOTES:
- UP TO 2\"/>



DATE	DESCRIPTION	MARK	APPR


Designed by: WMM	Date: 10/4/2011	Design File no.:
Dwn by: DEB	REP	
Reviewed by: TMH	Drawing code: BR-18	Dwg scales: N.T.S.
Submitted by: CVK		
U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND		
w912DR-07-0008 Task Order No. 19		

BACHELORS RUN I& II PLANTING SCHEDULES & PLANTING DETAILS



SEQUENCE OF CONSTRUCTION

1. NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION AT (410) 537-3510 FOR THE REQUIRED PRE-CONSTRUCTION MEETING AT LEAST SEVEN DAYS BEFORE COMMENCING LAND DISTURBING ACTIVITIES.
2. INSTALL TREE PROTECTION FENCING AS SHOWN ON THE PLAN.
3. COMPLETE TREE REMOVAL AND SELECTIVE TRIMMING AS SHOWN ON THE PLAN OR AS DIRECTED BY THE CONTRACTING OFFICER'S REPRESENTATIVE.
4. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED OVERNIGHT UNLESS RUNOFF IS DIRECTED TO AN APPROVED MDE SEDIMENT CONTROL DEVICE.
5. CLEAR AND GRUB ONLY THOSE AREAS NECESSARY TO INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.
6. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND BUILD THE ASSOCIATED TEMPORARY ACCESS ROAD. STABILIZE AT THE END OF EACH WORK DAY. FOR THE ACCESS ROAD WITHIN A WETLAND, PLACE TIMBER MATS TO MINIMIZE IMPACTS.
7. INSTALL SILT FENCE AS DESIGNATED ON THE PLANS.
8. CLEAR AND GRUB REMAINING WORK AREA. ANY DISTURBANCE CAUSED BY THIS PROCESS SHALL BE STABILIZED BY THE END OF THE DAY.
9. INSTALL PUMP-AROUND FLOW DIVERSION AND DEWATER THE CONSTRUCTION ZONE THROUGH THE APPROVED DEWATERING DEVICE. THE CONTRACTOR SHALL STAGE THE LIMITS OF THE PUMP-AROUND FLOW DIVERSION TO DEWATER ONLY THAT SECTION SCHEDULED FOR THAT DAY'S WORK. AT THE END OF EACH WORK DAY, THE WORK AREA SHALL BE STABILIZED, THE PUMP-AROUND PRACTICE REMOVED, AND THE FLOW RESTORED TO THE CHANNEL. WORK SHALL BE COMPLETED ONLY DURING FORECASTED PERIODS OF DRY WEATHER.
10. CONSTRUCT STREAM IMPROVEMENTS BEGINNING UPSTREAM TO DOWNSTREAM. THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO MINIMIZE UNNECESSARY DISTURBANCE. FOR THE STREAM IMPROVEMENTS, ONLY THAT AMOUNT OF WORK SHALL BE COMPLETED THAT CAN BE STABILIZED BY THE END OF THE DAY.
11. ONCE ALL STREAM WORK HAS BEEN COMPLETED AND PERMANENTLY STABILIZED, AND WITH APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING MAINTENANCE OF STREAMFLOW DEVICES, ACCESS ROAD, AND EROSION AND SEDIMENT CONTROL DEVICES. STABILIZE ALL AREAS DISTURBED DURING THIS PROCESS.



VICINITY MAP

Copyright ADC The Map People
Permitted Use No. 21003214
Expiration: 04/01/12


SITE INFORMATION - SHERWOOD

A. TOTAL AREA OF FACILITY (Base, Campus, Park, Etc.)	10.55 Acres
B. TOTAL AREA OF PROJECT SITE	10.55 Acres
C. AREA DISTURBED	3.75 Acres
D. AREA TO BE ROOFED OR PAVED	0.00 Acres
E. TOTAL CUT	1,678 CY
F. TOTAL FILL	1,203 CY
G. OFF-SITE WASTE/BORROW AREA LOCATION	TBD

FOR COMBINED SITE INFORMATION REFER TO DRAWING GN-10

NOTES:

1. STOCKPILE AREA SHALL BE LOCATED AT AN MDE APPROVED OFF-SITE LOCATION.
2. MAINTENANCE OF TRAFFIC IS THE RESPONSIBILITY OF THE CONTRACTOR.




RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 546-0028
(F) 703 546-0123

DATE	DESCRIPTION	MARK

Designed by: REP	Date: 10/4/2011
Dwn by: DEA	Design file no.
Reviewed by: TMH	Drawing code: SH-1
Submitted by: CMK	Dwg scale: AS SHOWN
U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	
W912DR-07-D-0008 Task Order No. 19	

**SHERWOOD
COVER SHEET**

Sheet
Number:
23 OF 72



MATCH LINE, SEE DRAWING SH-3


- NOTES:
1. ONLY TREES WITH A DBH >24" ARE SHOWN UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC



MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by: REP	Date: 10/4/2011
CORPS OF ENGINEERS	Drawn by: DEB	Design file no.
BALTIMORE, MARYLAND	Reviewed by: TMH	Drawing code: SH-2
W912DR-07-D-0008	Submitted by: CVK	Dwg scale: 1"=30'
Task Order No. 19		

**SHERWOOD
SITE PLAN**



- NOTES:
1. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPCC




RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by: REP Dwn by: DEA	Chd by: SPB	Date: 10/4/2011
W912DR-07-0-0008 Task Order No. 19	Reviewed by: TMH Submitted by: CVK	Drawing code: SH-4	Design file no. Drawing scale: 1"=30'


**SHERWOOD
SITE PLAN**

Sheet
Number:
26 OF 72



STREAM PROFILE - SHERWOOD

SCALE: 1" = 10' (VERT.)
1" = 30' (HORIZ.)



STREAM PROFILE - SHERWOOD

SCALE: 1" = 10' (VERT.)
1" = 30' (HORIZ.)

NOTE: VERTICAL STATIONING AND ADDITIONAL PROFILE DETAILS TO BE ADDED FOR NEXT SUBMISSION




MARK	DESCRIPTION	DATE	APPR


U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by: REP Dwn by: DEA	Crtd by: SPB Rvw by: TMH	Date: 10/4/2011 Design file no. Drawing code: SH-5 Dwg scale: AS SHOWN
W912DR-07-D-0008 Task Order No. 19	Submitted by: CVK	Reviewed by: TMH	

**SHERWOOD
PROFILE**


Sheet Number:
27 OF 72




Sherwood Typical Section - Riffle



Sherwood Stabilization Detail - Riffle



Sherwood Typical Section - Pool



Sherwood Stabilization Detail - Pool

- NOTES:
1. IN CASES WHERE AREA BEYOND THE BANKFULL CHANNEL ARE IN FILL, THE FILL SHALL BE PLACED AT 10:1 SLOPE.
 2. SEE DETAIL SHEETS FOR ADDITIONAL CHANNEL STABILIZATION MEASURES.
 3. SEE SPECIFICATIONS FOR DESCRIPTION OF MODIFIED COMMON BORROW.




MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by: REP	Date: 10/4/2011
CORPS OF ENGINEERS	Drawn by: DEA	Design file no.
BALTIMORE, MARYLAND	Reviewed by: TMH	Drawing code: SH-7
W912DR-07-D-0008	Submitted by: CVK	Dwg scale: 1"=30'
Task Order No. 19		

**SHERWOOD
TYPICAL SECTION**

Sheet
Number:
29 OF 72



MATCH LINE, SEE DRAWING SH-10

- NOTES:
1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.




RK&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Date: 10/4/2011 Design file no. Drawing code: SH-09 Dwg scale: 1"=30' Task Order No. 19
Designed by: REP Dwn by: DEA Chd by: SPB Reviewed by: TMW Submitted by: CMK	Date: 10/4/2011 Design file no. Drawing code: SH-09 Dwg scale: 1"=30'

**SHERWOOD
EROSION & SEDIMENT
CONTROL PLAN**

Sheet Number:
31 OF 72



MATCH LINE, SEE DRAWING SH-11

MATCH LINE, SEE DRAWING SH-9


- NOTES:**
1. PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.



MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	REP	Date:	10/4/2011
CORPS OF ENGINEERS	Dwn by:	DEA	Design file no.:	
BALTIMORE, MARYLAND	Reviewed by:	SPB	Drawing code:	SH-10
Task Order No. 19	Submitted by:	TMH	Dwg scale:	1"=30'
		CVK		

**SHERWOOD
EROSION & SEDIMENT
CONTROL PLAN**



HOSES FROM UPTREAM PUMP-AROUND AND DEWATERING DEVICE SHALL OFFFALL ONTO A STABILIZED OFFFALL POINT BEYOND DOWNSTREAM FLOW BARRIER

MATCH LINE, SEE DRAWING SH-10

NOTES:

1. ENTIRE MAIN CHANNEL PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
2. TRIBUTARY PUMP-AROUND TO BE INSTALLED WHEN CONFLUENCE IS WITHIN THE LIMITS OF THE ACTIVE WORK ZONE. THE ALIGNMENT OF THE DISCHARGE HOSE IS INCLUDED FOR GRAPHICAL PURPOSES ONLY AND IS TO OUTLET DOWNSTREAM OF THE ACTIVE WORK AREA FLOW BARRIER. THE TRIBUTARY PUMP-AROUND SHALL BE REMOVED AT THE END OF EACH DAY AND FLOW TO THE MAIN CHANNEL RESTORED.
3. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
4. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.
5. ENTIRE AREA SHOWN IS WITHIN THE 100-YR FLOODPLAIN LIMIT.



RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by: REP	Date: 10/4/2011
CORPS OF ENGINEERS	Chd by: SPB	Design file no.
BALTIMORE, MARYLAND	Dwn by: DEA	Reviewed by: TWH
W912DR-07-0-0008	Submitted by: CVK	Dwg scale: 1"=30'
Task Order No. 19		Drawing code: SH-11

**SHERWOOD
 EROSION & SEDIMENT
 CONTROL PLAN**

Sheet
 Number:
33 OF 72

PLANTING NOTES



1. The Contractor shall place 3' x 1' x 1' stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
2. The Contractor shall layout plants at all tree locations in the native upland forest and floodplain shrub areas and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
3. All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
4. See Sheet 39 for planting schedules.

LEGEND

- NATIVE UPLAND FOREST [Symbol]
- NATIVE FLOODPLAIN SHRUB [Symbol]
- TREE PROTECTION FENCE — TPF —
- STUDY AREA [Symbol]
- PROPERTY BOUNDARY [Symbol]
- PROPOSED CONTOUR [Symbol]
- EXISTING CONTOUR [Symbol]
- LIMIT OF DISTURBANCE [Symbol]
- WATERS OF THE US [Symbol]
- WETLAND BUFFER [Symbol]
- WETLANDS [Symbol]
- SIGNIFICANT TREE TO BE REMOVED [Symbol]
- PROPOSED TREE LINE [Symbol]
- EXISTING TREE LINE [Symbol]


30' 0 30' 60'
SCALE: 1" = 30'

MATCH LINE, SEE SHEET SH-14




- NOTES:**
1. If surrounding soil is compacted as determined by the engineer, an area up to 5 times the diameter of the root mass shall be excavated or rototilled to a 1' depth.
 2. Do not damage or cut leader.

TREE PLANTING - CONTAINER GROWN
N.T.S.




- NOTES:**
1. UP TO 2" OF SOIL CAN BE MOUNTED AROUND THE OUTSIDE OF TREE SHELTER.
 2. REFER TO TREE SHELTER SPECIFICATION FOR ADDITIONAL INFORMATION.


SHRUB PLANTING - CONTAINER
N.T.S.



TREE SHELTER DETAIL
N.T.S.



NATURALIZED PLANT SPACING
N.T.S.



TREE & SHRUB INSTALLATION THROUGH COIR FIBER MATTING
N.T.S.



RK&K
9302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0028
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by: WMM	Date: 10/14/2011
Dwn by: DEB	Design file no.:
Reviewed by: TMH	Drawing code: SH-16
Submitted by: CVK	Dwg scales: 1"=30'
U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	
W912DR-07-D-0008 Task Order No. 19	

SHERWOOD PLANTING PLAN & PLANTING DETAILS

Sheet Number:
37 OF 72

NATIVE FLOODPLAIN SHRUB

Size (acres): 0.33

Overall Minimum Spacing (feet center)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	Type	Placement
10	436			SHRUBS					
		33	48	<i>Clethra alnifolia</i>	Sweet Pepperbush	FAC+	24-36' ht.	Cont.	Clustered @ 8' OC
		33	48	<i>Cornus amomum</i>	Silky Dogwood	FACW	24-36' ht.	Cont.	Clustered @ 8' OC
		34	48	<i>Ilex verticillata</i>	Winterberry	FACW+	24-36' ht.	Cont.	Clustered @ 8' OC
		100.0	84	=total					
NA	40		lbs.	NATIVE PERMANENT SEED*					
		34	4.4	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%
		33	4.4	<i>Panicum clandestinum</i>	Deer Tongue	FACW	Seed	NA	Lb. of P.L.S. 76%
		33	4.4	<i>Elymus virginicus</i>	Virginia Wild Rye	FACW-	Seed	NA	Lb. of P.L.S. 76%
		100.0	13.2	=total					


* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL GENERAL NOTES

NATIVE UPLAND FOREST

Size (acres): 6.95

Overall Minimum Spacing (feet center)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/ Species Name	Common Name	Wetland Indicator Status	Size	Type	Placement
15	200			TREES					
			56	<i>Acer rubrum</i>	Red Maple	FAC	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
			42	<i>Liriodendron tulipifera</i>	Tulip Poplar	FACU	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
			28	<i>Nyssa sylvatica</i>	Black Gum	FAC	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
			56	<i>Platanus occidentalis</i>	American Sycamore	FACW	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
			42	<i>Quercus palustris</i>	Pin Oak	FACW	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
			56	<i>Quercus rubra</i>	Northern Red Oak	FACU	1 - 1/2' cal.	B & B	Naturalized @ 15' OC
		100.0	280.0	=total					
7	300			SHRUBS					
		25	105	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24' ht.	Cont.	Clustered @ 7' OC
		25	105	<i>Lindera benzoin</i>	Spice Bush	FACW	18-24' ht.	Cont.	Clustered @ 7' OC
		30	126	<i>Viburnum acerifolium</i>	Mapleleaf Viburnum	UPL	18-24' ht.	Cont.	Clustered @ 7' OC
		20	84	<i>Viburnum dentatum</i>	Southern Arrowwood	FAC	18-24' ht.	Cont.	Clustered @ 7' OC
		100.0	420	=total					
NA	20			NATIVE PERMANENT SEED*					
		34	9.52	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%
		33	9.24	<i>Panicum clandestinum</i>	Deer Tongue	FACW	Seed	NA	Lb. of P.L.S. 76%
		33	9.24	<i>Elymus virginicus</i>	Virginia Wild Rye	FACW-	Seed	na	Lb. of P.L.S. 76%
		100.0	28	=total					

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL GENERAL NOTES



MATCH LINE, SEE SHEET SH-16

LEGEND


NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN SHRUB	
TREE PROTECTION FENCE	— TPF —
STUDY AREA	— — — —
PROPERTY BOUNDARY	— — — —
PROPOSED CONTOUR	— I20 —
EXISTING CONTOUR	— I20 —
LIMIT OF DISTURBANCE	— LOD —
WATERS OF THE US	— WUS —
WETLAND BUFFER	— B —
WETLANDS	
PROPOSED TREE LINE	
EXISTING TREE LINE	

PLANTING NOTES

- The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the floodplain shrub and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
- The Contractor shall layout plants at all tree locations in the native upland forest and floodplain shrub areas and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
- All trees shall be installed with proper deer protection tree shelters as per plans and specifications.

GENERAL NOTES

- The landscaping shown on Sheets 37-39 must be planted in accordance with the latest edition of Landscape Specification Guidelines, developed by the MD-DC-VA Chapter of the Landscape Contractors Association.
- All plants must meet the standards of the latest edition of American Standard for Nursery Stock sponsored by the Association of American Nurserymen.
- Plant type substitutions are permitted with verbal or written approval from the Planning and Code Administration.
- All trees are to be located a minimum distance of 5 feet from all utility boxes, 5 feet from a storm drain inlet or manhole, 10 feet from a fire hydrant, 15 feet from public street lights, 5 feet from driveway aprons, 20 feet from any traffic control sign and at least 30 feet from any intersection.
- Shrubs to be planted in groups of 7-10 plants.
- Soil conditions must be tested, verified and adjusted by the landscape contractor to ensure that appropriate soil composition and PH levels are suitable for plant materials specified for that specific location.
- Any planting within a forest retention area, as designated on the forest conservation plan and shown on this plan, must be carried out in such a way as to avoid any adverse impact to the roots of existing trees.
- All plant material will be reinspected for survival by the Planning and Code Administration one year following installation. A 10 percent maintenance bond will be retained during this time period.
- Planting installation shall include a 2 year maintenance period.




MARK	DESCRIPTION	DATE	APPR

Designed by: WMM	Date: 10/4/2011
Dwn by: DEA	Design file no.:
Reviewed by: TMH	Drawing code: SH-18
Submitted by: CVK	Dwg scales: 1"=30'
U.S. ARMY ENGINEER DIVISION	
CORPS OF ENGINEERS	
BALTIMORE, MARYLAND	
W912DR-07-0-0008	
Task Order No. 19	


SHERWOOD PLANTING PLAN & PLANTING SCHEDULES

Sheet Number:
39 OF 72



SEQUENCE OF CONSTRUCTION

1. NOTIFY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION AT (410) 537-3510 FOR THE REQUIRED PRE-CONSTRUCTION MEETING AT LEAST SEVEN DAYS BEFORE COMMENCING LAND DISTURBING ACTIVITIES.
2. INSTALL TREE PROTECTION FENCING AS SHOWN ON THE PLAN.
3. COMPLETE TREE REMOVAL AND SELECTIVE TRIMMING AS SHOWN ON THE PLAN OR AS DIRECTED BY THE CONTRACTING OFFICER'S REPRESENTATIVE.
4. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED OVERNIGHT UNLESS RUNOFF IS DIRECTED TO AN APPROVED MDE SEDIMENT CONTROL DEVICE.
 PHASE W-1 (STA. 40+00 TO STA. 49+00)
5. CLEAR AND GRUB ONLY THOSE AREAS NECESSARY TO INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.
6. INSTALL STABILIZED CONSTRUCTION ENTRANCE OFF ALEXANDER MANOR DRIVE AND BUILD THE ASSOCIATED TEMPORARY ACCESS ROAD. STABILIZE AT THE END OF EACH WORK DAY. FOR THE ACCESS ROAD WITHIN A WETLAND, PLACE TIMBER MATS TO MINIMIZE IMPACTS.
7. INSTALL SILT FENCE AS DESIGNATED ON THE PLANS.
8. CLEAR AND GRUB REMAINING WORK AREA ABOVE STA. 49+00. ANY DISTURBANCE CAUSED BY THIS PROCESS SHALL BE STABILIZED BY THE END OF THE DAY.
9. INSTALL PUMP-AROUND FLOW DIVERSION AND DEWATER THE CONSTRUCTION ZONE THROUGH THE APPROVED DEWATERING DEVICE. THE CONTRACTOR SHALL STAGE THE LIMITS OF THE PUMP-AROUND FLOW DIVERSION TO DEWATER ONLY THAT SECTION SCHEDULED FOR THAT DAY'S WORK. AT THE END OF EACH WORK DAY THE WORK AREA SHALL BE STABILIZED, THE PUMP-AROUND PRACTICE REMOVED, AND THE FLOW RESTORED TO THE CHANNEL. WORK SHALL BE COMPLETED ONLY DURING FORECASTED PERIODS OF DRY WEATHER.
10. CONSTRUCT PHASE W-1 STREAM IMPROVEMENTS BEGINNING UPSTREAM TO DOWNSTREAM. THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO MINIMIZE UNNECESSARY DISTURBANCE. FOR THE STREAM IMPROVEMENTS, ONLY THAT AMOUNT OF WORK SHALL BE COMPLETED THAT CAN BE STABILIZED BY THE END OF THE DAY.
11. ONCE ALL PHASE W-1 STREAM WORK HAS BEEN COMPLETED AND PERMANENTLY STABILIZED, REMOVE THE ASSOCIATED ACCESS ROAD, SILT FENCE AND STABILIZED CONSTRUCTION ENTRANCES. PERMANENTLY STABILIZE ALL AREAS DISTURBED BY THIS PROCESS IN ACCORDANCE WITH THE PLANS.
 PHASE W-2 (STA. 49+00 TO STA. 59+83)
12. CLEAR AND GRUB ONLY THOSE AREAS NECESSARY TO INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.
13. INSTALL EDNOR ROAD STABILIZED CONSTRUCTION ENTRANCE AND ASSOCIATED ACCESS ROAD FOR WORK AREA DOWNSTREAM OF STA 49+00. STABILIZE AT THE END OF EACH WORK DAY.
14. CLEAR AND GRUB REMAINING WORK AREA BELOW STA. 49+00. ANY DISTURBANCE CAUSED BY THIS PROCESS SHALL BE STABILIZED BY THE END OF THE DAY.
15. INSTALL PUMP-AROUND FLOW DIVERSION AND DEWATER THE CONSTRUCTION ZONE THROUGH THE APPROVED DEWATERING DEVICE. THE CONTRACTOR SHALL STAGE THE LIMITS OF THE PUMP-AROUND FLOW DIVERSION TO DEWATER ONLY THAT SECTION SCHEDULED FOR THAT DAY'S WORK. AT THE END OF EACH WORK DAY, THE WORK AREA SHALL BE STABILIZED, THE PUMP-AROUND PRACTICE REMOVED, AND THE FLOW RESTORED TO THE CHANNEL. WORK SHALL BE COMPLETED ONLY DURING FORECASTED PERIODS OF DRY WEATHER.
16. CONTINUE STREAM IMPROVEMENTS DOWNSTREAM OF STA. 49+00 WORKING FROM DOWNSTREAM TO UPSTREAM. UPON COMPLETION OF THE WORK, PERMANENTLY STABILIZE ALL DISTURBED AREAS WITHIN THE CHANNEL.
17. WITH APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR, REMOVE ALL REMAINING MAINTENANCE OF STREAMFLOW DEVICES, ACCESS ROAD, AND EROSION AND SEDIMENT CONTROL DEVICES. STABILIZE ALL AREAS DISTURBED DURING THIS PROCESS.



VICINITY MAP


Copyright ADC The Map People
 Permitted Use No. 21003214
 Expiration: 04/01/12

SITE INFORMATION - WOODLAWN	
A. TOTAL AREA OF FACILITY (Base, Campus, Park, Etc.)	18.24 Acres
B. TOTAL AREA OF PROJECT SITE	18.24 Acres
C. AREA DISTURBED	2.97 Acres
D. AREA TO BE ROOFED OR PAVED	0.00 Acres
E. TOTAL CUT	917 CY
F. TOTAL FILL	1,237 CY
G. OFF-SITE WASTE/BORROW AREA LOCATION	TBD

FOR COMBINED SITE INFORMATION REFER TO DRAWING GN-10

NOTES:

1. STOCKPILE AREA SHALL BE LOCATED AT AN MDE APPROVED OFF-SITE LOCATION.
2. MAINTENANCE OF TRAFFIC IS THE RESPONSIBILITY OF THE CONTRACTOR.




RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0228
 (F) 703 246-0123

DATE	DESCRIPTION	MARK

Designed by: REP	Date: 10/4/2011
Dwn by: SPB	Design file no.
Reviewed by: TWH	Drawing code: WL-1
Submitted by: CVK	Dwg status: AS SHOWN
U.S. ARMY ENGINEER DIVISION	
CORPS OF ENGINEERS	
BALTIMORE, MARYLAND	
W912DR-07-D-0008	
Task Order No. 19	

WOODLAWN COVER SHEET

Sheet Number:
 40 OF 72



- NOTES:
1. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC




RK&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR


U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by: REP Dwn by: DEA	Chd by: SPB	Reviewed by: TMH Submitted by: CVK	Date: 10/4/2011 Design file no. Drawing code: WL-4 Dwg scale: 1"=30'
W912DR-07-D-0008 Task Order No. 19				

WOODLAWN SITE PLAN

Sheet
Number:
43 OF 72



STREAM PROFILE - WOODLAWN
 SCALE: 1" = 10' (VERT.)
 1" = 30' (HORIZ.)



STREAM PROFILE - WOODLAWN
 SCALE: 1" = 10' (VERT.)
 1" = 30' (HORIZ.)

NOTE: VERTICAL STATIONING AND ADDITIONAL PROFILE DETAILS TO BE ADDED FOR NEXT SUBMISSION



RK&K
 8302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0728
 (F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	Date:	10/4/2011
CORPS OF ENGINEERS	REP:	Design file no.:	
BALTIMORE, MARYLAND	Dwn by: DEB	Crtd by: SPB	
	Reviewed by: TMH	Dwg scale:	WL-6
	Submitted by: CVK	AS SHOWN	
		Task Order No. 19	
		W912DR-07-D-0008	

**WOODLAWN
 PROFILE**

Sheet
 Number:
 45 OF 72



US Army Corps
of Engineers
Baltimore District




8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0228
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by:	REP	Date:	10/4/2011
	Dwn by:	DEA	Design file no.:	
W912DR-07-D-0008 Task Order No. 19	Reviewed by:	TWH	Drawing code:	WL-7
	Submitted by:	CVK	Dwg status:	AS SHOWN


**WOODLAWN
PROFILE**

Sheet
Number:
46 OF 72




STREAM PROFILE - WOODLAWN
SCALE: 1" = 10' (VERT.)
1" = 30' (HORIZ.)


NOTE: VERTICAL STATIONING AND ADDITIONAL PROFILE
DETAILS TO BE ADDED FOR NEXT SUBMISSION




Woodlawn Typical Section - Riffle



Woodlawn Stabilization Detail - Riffle



Woodlawn Typical Section - Pool



Woodlawn Stabilization Detail - Pool

- NOTES:
1. IN CASES WHERE AREA BEYOND THE BANKFULL CHANNEL ARE IN FILL, THE FILL SHALL BE PLACED AT 10:1 SLOPE.
 2. SEE DETAIL SHEETS FOR ADDITIONAL CHANNEL STABILIZATION MEASURES.
 3. SEE SPECIFICATIONS FOR DESCRIPTION OF MODIFIED COMMON BORROW.




RK&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0028
 (F) 703 246-0123

DATE	DESCRIPTION	MARK	APPR

U.S. ARMY ENGINEER DIVISION	Designed by: REP	Date: 10/4/2011
CORPS OF ENGINEERS	Drawn by: DEA	Design file no.
BALTIMORE, MARYLAND	Checked by: SPB	Drawing code: WL-8
W912DR-07-D-0008	Reviewed by: TMH	Draw scale: 1"=30'
Task Order No. 19	Submitted by: CVK	

**WOODLAWN
 TYPICAL SECTIONS**

Sheet Number:
47 OF 72



- NOTES:
1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 3. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.




MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	Date:
CORPS OF ENGINEERS	REP	10/4/2011
BALTIMORE, MARYLAND	Chd by:	Design file no.
	DEA	SPB
	Reviewed by:	Drawing code:
	TWH	WL-10
	Submitted by:	Dwg scale:
	CVK	1"=30'
Task Order No. 19		

**WOODLAWN
EROSION & SEDIMENT
CONTROL PLAN**

Sheet
Number:
49 OF 72



- NOTES:
1. MAIN CHANNEL PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
 2. TRIBUTARY PUMP-AROUND TO BE INSTALLED WHEN CONFLUENCE IS WITHIN THE LIMITS OF THE ACTIVE WORK ZONE. THE TRIBUTARY PUMP-AROUND SHALL BE REMOVED AT THE END OF EACH DAY AND FLOW TO THE MAIN CHANNEL RESTORED.
 3. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 4. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.




MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by: WBRM	Date: 10/4/2011
CORPS OF ENGINEERS	Chd by: BEB	Design file no.
BALTIMORE, MARYLAND	Dwn by: DEA	Drawing code: WL-11
Task Order No. 19	Reviewed by: TMH	Dwg scale: 1"=30'
	Submitted by: CVK	

**WOODLAWN
EROSION & SEDIMENT
CONTROL PLAN**

Sheet
Number:
50 OF 72



NOTES:

1. ENTIRE PUMP-AROUND AND DEWATERING SYSTEMS NOT SHOWN, BUT SHALL BE INSTALLED IN ACCORDANCE WITH THE SEQUENCE OF CONSTRUCTION AND STANDARD DETAILS.
2. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
3. LIMITS OF ACCESS ROADS AND STAGING/STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.
4. 100-YR FLOODPLAIN LIMIT EXTENDS BEYOND THE EASTERN LIMITS OF THE PROJECT.



MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	REP	Date:	10/4/2011
CORPS OF ENGINEERS	Checked by:	SPB	Design file no.	
BALTIMORE, MARYLAND	Drawn by:	DEA	Drawing code:	WL-12
W912DR-07-D-0008	Reviewed by:	TWH	Dwg scale:	1"=30'
Task Order No. 19	Submitted by:	CVK		

**WOODLAWN
EROSION & SEDIMENT
CONTROL PLAN**

Sheet
Number:
51 OF 72




MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Designed by:	Date:
CORPS OF ENGINEERS	REP	10/4/2011
BALTIMORE, MARYLAND	Dwn by: DEB	Design file no.
	Chd by: SPB	
	Reviewed by: TMH	Drawing code: WL-13
	Submitted by: CVK	Dwg scale: 1"=30'
		Task Order No. 19

**WOODLAWN
EROSION & SEDIMENT
CONTROL PLAN**

Sheet
Number:
44 OF 72



- NOTES:
1. ONLY TREES WITH A DBH >24" ARE LABELED UNLESS OTHERWISE SPECIFIED.
 2. LIMITS OF ACCESS ROADS AND STAGING STORAGE AREA ARE APPROXIMATE AND SHALL BE COORDINATED WITH M-NCPPC.
 3. TOPOGRAPHY FROM COUNTY 200' SCALE MAPPING WITH 2-FOOT CONTOUR INTERVAL

MATCH LINE, SEE DRAWING WL-11


BY: bpehner

MARK	DESCRIPTION	DATE	APPR

Designed by:	WMM	Date:	10/4/2011
Dwn by:	CKD	Design file no.:	
Reviewed by:	DEA	Drawing code:	WL-19
Submitted by:	TMH	Dwg scales:	1"=30'

U.S. ARMY ENGINEER DIVISION	W912DR-07-D-0008
CORPS OF ENGINEERS	Task Order No. 19
BALTIMORE, MARYLAND	

WOODLAWN PLANTING PLAN



- PLANTING NOTES**
- The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
 - The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
 - All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
 - See Sheet 60 for planting schedules.





LEGEND	
NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN FOREST	
NATIVE FLOODPLAIN SHRUB	
NATIVE PERMANENT SEED	
TREE PROTECTION FENCE	
STUDY AREA	
PROPERTY BOUNDARY	
PROPOSED CONTOUR	
EXISTING CONTOUR	
LIMIT OF DISTURBANCE	
WATERS OF THE US	
WETLAND BUFFER	
WETLANDS	
PROPOSED TREE LINE	
EXISTING TREE LINE	

LEGEND


NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN FOREST	
NATIVE FLOODPLAIN SHRUB	
TREE PROTECTION FENCE	— TPF —
STUDY AREA	— — — — —
PROPERTY BOUNDARY	— — — — —
PROPOSED CONTOUR	— I20 —
EXISTING CONTOUR	— I20 —
LIMIT OF DISTURBANCE	— LOD —
WATERS OF THE US	— WUS —
WETLAND BUFFER	— B —
WETLANDS	
PROPOSED TREE LINE	— — — — —
EXISTING TREE LINE	— — — — —

PLANTING NOTES

- The Contractor shall place 3' x 1' x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
- The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
- All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
- See Sheet 60 for planting schedules.




MONTGOMERY COUNTY
5010/842
22.44 Ac.
N300
PARCEL '5'




TREE SHELTER DETAIL
N.T.S.


- NOTES:
- UP TO 2" OF SOIL CAN BE MOUNTED AROUND THE OUTSIDE OF TREE SHELTER.
 - REFER TO TREE SHELTER SPECIFICATION FOR ADDITIONAL INFORMATION.




TREE PLANTING - CONTAINER GROWN
N.T.S.



SHRUB PLANTING - CONTAINER
N.T.S.



NATURALIZED PLANT SPACING
N.T.S.



- Make cut with sharp knife through Coir Fiber Matting. Solid line in diagram.
- Pin back Coir Fiber with 4 staples - dashed line in diagram.
- Install plant through pinned back Coir Fiber. Install plant at proper grade to ground plane.
- Remove 4 staples.
- For tree installations, install tree stakes through Coir Fiber.
- Install deer protection.
- Place 4 staples in each of four cut sections. Re-anchor Coir Matting to ground.

TREE & SHRUB INSTALLATION THROUGH COIR FIBER MATTING
N.T.S.



RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0028
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by:	WMM	Date:	10/4/2011
Dwn by:	DEA	Chk by:	REP
Reviewed by:	TMH	Design file no.:	
Submitted by:	CVK	Drawing code:	WL-20
		Dwg scales:	1"=30'
U.S. ARMY ENGINEER DIVISION		CORPS OF ENGINEERS	
BALTIMORE, MARYLAND		W912DR-07-D-0008	
		Task Order No. 19	


**WOODLAWN
PLANTING PLAN &
PLANTING DETAILS**

MARK	DESCRIPTION	DATE	APPR

Designed by:	WMM	Date:	10/4/2011
Dwn by:	CKD	Design file no.:	
Reviewed by:	REP	Drawing codes:	WL-21
Submitted by:	TMH	Dwg scales:	1"=30'


U.S. ARMY ENGINEER DIVISION	Task Order No. 19
CORPS OF ENGINEERS	
BALTIMORE, MARYLAND	


WOODLAWN PLANTING PLAN



LEGEND	
NATIVE UPLAND FOREST	
NATIVE FLOODPLAIN FOREST	
NATIVE FLOODPLAIN SHRUB	
NATIVE PERMANENT SEED	
TREE PROTECTION FENCE	— TPF —
STUDY AREA	— — — — —
PROPERTY BOUNDARY	— — — — —
PROPOSED CONTOUR	— 120 —
EXISTING CONTOUR	— 120 —
LIMIT OF DISTURBANCE	— LOD —
WATERS OF THE US	— WUS —
WETLAND BUFFER	— B —
WETLANDS	
PROPOSED TREE LINE	— — — — —
EXISTING TREE LINE	— — — — —

- PLANTING NOTES**
- The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
 - The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
 - All trees shall be installed with proper deer protection tree shelters as per plans and specifications.
 - See Sheet 60 for planting schedules.





LEGEND	
NATIVE UPLAND FOREST	[Hatched pattern]
NATIVE FLOODPLAIN FOREST	[Cross-hatched pattern]
SOD	[Hexagonal pattern]
NATIVE PERMANENT SEED	[Diagonal line pattern]
TREE PROTECTION FENCE	— TPF —
STUDY AREA	— — — — —
PROPERTY BOUNDARY	— — — — —
PROPOSED CONTOUR	—120—
EXISTING CONTOUR	—120—
LIMIT OF DISTURBANCE	— LOD —
WATERS OF THE US	— WUS —
WETLAND BUFFER	— B —
WETLANDS	[Wetland symbol]
PROPOSED TREE LINE	[Wavy line symbol]
EXISTING TREE LINE	[Dashed wavy line symbol]

- PLANTING NOTES**
- The Contractor shall place 3' x 1" x 1" stakes to identify planting areas along the entire boundary between the upland forest and the floodplain forest. Stakes shall be placed at 25' increments. The Contractor shall request that an Owner's representative review these locations and gain final approval before planting commences.
 - The Contractor shall layout plants at all tree locations in the upland forest and floodplain forest and gain approval from an Owner's representative that all locations are satisfactory before plants are installed.
 - All trees shall be installed with proper deer protection tree shelters as per plans and specifications.

- GENERAL NOTES**
- The landscaping shown on sheets 57-59 must be planted in accordance with the latest edition of Landscape Specification Guidelines, developed by the MD-DC-VA Chapter of the Landscape Contractors Association.
 - All plants must meet the standards of the latest edition of American Standard for Nursery Stock sponsored by the Association of American Nurserymen.
 - Plant type substitutions are permitted with verbal or written approval from the Planning and Code Administration.
 - All trees are to be located a minimum distance of 5 feet from all utility boxes, 5 feet from a storm drain inlet or manhole, 10 feet from a fire hydrant, 15 feet from public street lights, 5 feet from driveway aprons, 20 feet from any traffic control sign and at least 30 feet from any intersection.
 - Shrubs to be planted in groups of 7-10 plants.
 - Soil conditions must be tested, verified and adjusted by the landscape contractor to ensure that appropriate soil composition and pH levels are suitable for plant materials specified for that specific location.
 - Any planting within a forest retention area, as designated on the landscape conservation plan and shown on this plan, must be carried out in such a way as to avoid any adverse impact to the roots of existing trees.
 - All plant material will be reinspected for survival by the Planning and Code Administration one year following installation. A 10 percent maintenance bond will be retained during this time period.
 - Plant installation shall include a 2 year maintenance period.

NATIVE FLOODPLAIN FOREST											Size (acres): 0.28	
Overall Minimum Spacing-foot on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/Species Name	Common Name	Wetland Indicator Status	Size	TYPE	Placement			
TREES												
15	200	15	8	<i>Acer rubrum</i>	Red Maple	FAC	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		20	11	<i>Betula nigra</i>	River Birch	FAC	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		10	6	<i>Nyssa sylvatica</i>	Black Gum	FAC	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		20	11	<i>Platanus occidentalis</i>	American Sycamore	FACW	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		20	11	<i>Quercus palustris</i>	Pin Oak	FACW	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		15	9	<i>Quercus phellos</i>	Willow Oak	FAC	1 - 1 1/2" cal.	Cont.	Naturalized @ 15' OC			
		100.0	56	=total								
10	300	SHRUBS										
		20	17	<i>Alnus serrulata</i>	Smooth alder	OBL	18-24"	Cont.	Clustered @ 7' OC			
		20	17	<i>Cephalanthus occidentalis</i>	Buttonbush	OBL	18-24"	Cont.	Clustered @ 7' OC			
		20	17	<i>Clethra alnifolia</i>	Sweet Pepperbush	FAC	18-24"	Cont.	Clustered @ 7' OC			
		10	8	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24"	Cont.	Clustered @ 7' OC			
		10	8	<i>Ilex verticillata</i>	Winterberry	FACW	18-24"	Cont.	Clustered @ 7' OC			
		20	17	<i>Salix sericea</i>	Silky willow	OBL	18-24"	Cont.	Clustered @ 7' OC			
		100.0	84	=total								
NA	20	NATIVE SEED										
		35	1.96	<i>Andropogon gerardii</i>	Big Bluestem	FAC	SEED	NA	LB. of P.L.S. 76%			
		20	1.12	<i>Elymus riparius</i>	Riverbank Wild Rye	FACW	SEED	NA	LB. of P.L.S. 76%			
		4	0.22	<i>Eupatorium fistulosum</i>	Joe-Pye Weed	FACW	SEED	NA	LB. of P.L.S. 76%			
		15	0.84	<i>Panicum virgatum</i>	Switchgrass	FAC	SEED	NA	LB. of P.L.S. 76%			
		10	0.56	<i>Scirpus cyperinus</i>	Wool Grass	FACW	SEED	NA	LB. of P.L.S. 76%			
		12	0.68	<i>Tripsacum dactyloides</i>	Eastern Gama Grass	FACW	SEED	NA	LB. of P.L.S. 76%			
		4	0.22	<i>Vernonia noveboracensis</i>	New York Ironweed	FACW	SEED	NA	LB. of P.L.S. 76%			
		100.0	5.60	=total								

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES

NATIVE UPLAND FOREST											Size (acres): 6.95	
Overall Minimum Spacing-foot on center (OC)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/Species Name	Common Name	Wetland Indicator Status	Size	TYPE	Placement			
TREES												
15	200	20	278	<i>Acer rubrum</i>	Red Maple	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		15	208	<i>Liriodendron tulipifera</i>	Tulip Poplar	FACU	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		10	139	<i>Nyssa sylvatica</i>	Black Gum	FAC	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		20	278	<i>Platanus occidentalis</i>	American Sycamore	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		15	209	<i>Quercus palustris</i>	Pin Oak	FACW	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		20	278	<i>Quercus rubra</i>	Northern Red Oak	FACU	1 - 1 1/2" cal.	B&B	Naturalized @ 15' OC			
		100.0	1390	=total								
10	300	SHRUBS										
		25	521	<i>Cornus amomum</i>	Silky Dogwood	FACW	18-24"	Cont.	Clustered @ 7' OC			
		25	522	<i>Lindera benzoin</i>	Spicebush	FACW	18-24"	Cont.	Clustered @ 7' OC			
		30	625	<i>Viburnum acerifolium</i>	Mapleleaf viburnum	UPL	18-24"	Cont.	Clustered @ 7' OC			
		20	417	<i>Viburnum dentatum</i>	Southern Arrowwood	FAC	18-24"	Cont.	Clustered @ 7' OC			
		100.0	2085	=total								
NA	20	NATIVE PERMANENT SEED										
		33.3	46.33	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%			
		33.3	46.33	<i>Elymus canadensis</i>	Canada Wild Rye	FACW	Seed	NA	Lb. of P.L.S. 76%			
		33.4	46.34	<i>Panicum clandestinum</i>	Deer Tongue	FACW	Seed	NA	Lb. of P.L.S. 76%			
		100.0	139.00	=total								


* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES

NATIVE FLOODPLAIN SHRUB											Size (acres): 0.20	
Overall Minimum Spacing (feet center)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/Species Name	Common Name	Wetland Indicator Status	Size	Type	Placement			
SHRUBS												
10	436	33	29	<i>Clethra alnifolia</i>	Sweet Pepperbush	FAC+	24-36" ht.	Cont.	Clustered @ 8' OC			
		33	29	<i>Cornus amomum</i>	Silky Dogwood	FACW	24-36" ht.	Cont.	Clustered @ 8' OC			
		34	30	<i>Ilex verticillata</i>	Winterberry	FACW+	24-36" ht.	Cont.	Clustered @ 8' OC			
		100.0	88	=total								
NA	40	NATIVE PERMANENT SEED*										
		34	1.33	<i>Andropogon gerardii</i>	Big Bluestem	FAC	Seed	NA	Lb. of P.L.S. 76%			
		33	1.33	<i>Panicum clandestinum</i>	Deer Tongue	FACW	Seed	NA	Lb. of P.L.S. 76%			
		33	1.34	<i>Elymus virginicus</i>	Virginia Wild Rye	FACW-	Seed	NA	Lb. of P.L.S. 76%			
		100.0	4.00	=total								

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES

NATIVE PERMANENT SEED											Size (acres): 0.38	
Overall Minimum Spacing (feet center)	Quantity per acre	Frequency (%)	Species Quantity	Vegetation Strata/Species Name	Common Name	Wetland Indicator Status	Size	Type	Placement			
NATIVE PERMANENT SEED*												
NA	20	50	3.8	<i>Elymus canadensis</i>	Canada Wild Rye	FACW	Seed	NA	Lb. of P.L.S. 76%			
		50	3.8	<i>Panicum clandestinum</i>	Deer Tongue	FACW	Seed	NA	Lb. of P.L.S. 76%			
		100.0	7.6	=total								

* FOR TEMPORARY SEED, REFER TO TEMPORARY SEED TABLE IN EROSION & SEDIMENT CONTROL NOTES



R&K
 9302 LEE HIGHWAY, SUITE 425
 HUNTERS BRANCH 2
 FAIRFAX, VA
 (P) 703 246-0128
 (F) 703 246-0123


DATE	DESCRIPTION	MARK	APPR

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Task Order No. 19
--	--	-------------------


**WOODLAWN
 PLANTING PLAN &
 PLANTING SCHEDULES**

Sheet Number:
60 OF 72

CROSS VANE STRUCTURE



J-HOOK VANE






- NOTES:
1. ALL ROCKS ARE SUBJECT TO VISUAL INSPECTION BY THE DESIGNATED SPECIALIST
 2. ROCKS SHOWN ARE NOT TO SCALE

BUILDING INSTRUCTIONS FOR INSTREAM STONE STRUCTURES

1. CUT A TRENCH FOR ONE OF THE ARMS OF THE STRUCTURE, FROM OUTWARD LIMIT OF THE STRUCTURE, EXTENDING INTO THE STREAM AT THE ANGLE SPECIFIED IN THE INSTREAM STRUCTURE TABLE OR AS DETERMINED BY THE DESIGNATED SPECIALIST IN THE FIELD (REFER TO THE DETAIL). THE DIMENSIONS OF THE TRENCH (WIDTH AND DEPTH) SHALL ACCOMMODATE THE DIMENSIONS OF THE STONES. EXCAVATION OF THE TRENCH SHALL BE CONDUCTED IN CONJUNCTION WITH THE PLACEMENT OF THE FOOTER AND THE ARM STONES (STONES WHICH ARE PLACED ON TOP OF THE FOOTERS STONES IN THE ARM AND WEIR PORTION OF THE STRUCTURE.)
2. FOOTER STONES SHALL BE PLACED IN THE EXCAVATED TRENCH SUCH THAT THEY ARE SPACED ONE THIRD (1/3) THE DIAMETER OF THE STONES, WHICH WILL ALLOW THE ARM STONES TO INTERLOCK WITH THE FOOTER STONE. ADDITIONAL FOOTER STONES MAY BE REQUIRED FOR PLACEMENT OF THE ARM STONE AT THE REQUIRED ELEVATION.
3. EXCAVATION OF THE TRENCH TO ACCOMMODATE THE DIMENSIONS OF THE STONES TO ALLOW FOR THE PLACEMENT OF THE NEXT SERIES OF ARM STONES, UNTIL THE REQUIRED LENGTH OF THE STRUCTURE IS ACHIEVED.
4. ARM STONES SHALL BE PLACED ON TOP OF THE FOOTER STONES SUCH THAT THEY ARE CONTIGUOUS, STAGGERED OVER THE ADJACENT FOOTER STONES, AND PLACED SKEWED UPSTREAM OF THE FOOTER STONES. THE ARM STONES SHALL BE POSITIONED SUCH THAT THEY SLOPE FIVE (5) TO TEN (10) PERCENT TOWARDS THE STREAM CHANNEL.
5. REPEAT STEPS FIVE (3) AND (4) UNTIL THE STRUCTURE ARM EXTENDS TO THE ELEVATION SPECIFIED. UPON ACHIEVING THE REQUIRED ARM LENGTH, PROCEED WITH THE FOLLOWING INSTRUCTIONS.
6. TO CONSTRUCT THE WEIR PORTION OF THE STRUCTURE, A TRENCH PERPENDICULAR TO THE STREAM CHANNEL SHALL BE EXCAVATED FROM THE END OF THE EXISTING ARM CHANNEL WARD TOWARD THE OPPOSITE CHANNEL BANK, EXTENDING APPROXIMATELY ONE THIRD (1/3) OF THE PROPOSED CHANNEL WIDTH (REFER TO DETAIL), THE EXACT LENGTH TO BE DETERMINED BY THE DESIGNATED SPECIALIST IN THE FIELD. THE TRENCH SHALL BE EXCAVATED TO A DEPTH WHICH WILL ACCOMMODATE THE FOOTER STONES. CONTINUOUS EXCAVATION OF THE TRENCH PROGRESSIVELY STREAM WARD, IN THE CONJUNCTION WITH THE PLACEMENT OF THE FOOTER AND THE WEIR STONES (STONES WHICH PLACED ON TOP OF THE FOOTERS IN THE WEIR PORTION OF THE STRUCTURE).
7. WEIR STONES SHALL BE PLACED ON TOP OF THE FOOTER STONES SUCH THAT THEY ARE CONTIGUOUS, STAGGERED OVER THE FOOTER STONES, PLACED SKEWED UPSTREAM OF THE FOOTER STONES, AND PLACED FLUSH WITH THE PROPOSED STREAM CHANNEL. THE TOP OF THE WEIR STONES SHALL BE PLACED FLUSH WITH THE PROPOSED STREAM INVERT.
8. UPON COMPLETING THE WEIR PORTION OF THE STRUCTURE A J-HOOK IS COMPLETE, REPEAT STEPS ONE (1) THROUGH EIGHT (8) TO COMPLETE A CROSS-VANE STRUCTURE.
9. EXCAVATE A SCOUR POOL DOWNSTREAM OF THE STRUCTURE AS DIRECTED BY THE DESIGNATED SPECIALIST.
10. THE DESIGNATED SPECIALIST RESERVES THE RIGHT TO ADJUST THE LOCATION / ANGLE, OR ELEVATION OF THE PROPOSED STRUCTURE.

EXTEND TO SPECIFIED ELEVATION AS PER PLAN OR AS DIRECTED BY DESIGNATED SPECIALIST.



NOTE: FOR TYPICAL SIZE OF FOOTER STONES USE 200 LB. TO 400 LB. STONES

CONSTRUCTION NOTES:

1. NOTIFY THE DESIGNATED SPECIALIST ONE WEEK PRIOR TO STARTING THE INSTREAM GRADING AND STONE STRUCTURES WORK. AN ACCURATE SCHEDULE SHALL BE SUBMITTED TO THE DESIGNATED SPECIALIST INDICATING THE DAYS TO BE DEDICATED BY THE CONTRACTOR TO PERFORM THE INSTREAM GRADING AND STONE STRUCTURE WORK. THE DESIGNATED SPECIALIST WILL BE AVAILABLE AT THE SITE DURING THESE DAYS.
2. SEE PROFILE FOR DEPTH OF SCOUR HOLE FOR ALL STRUCTURES.
3. FOOTER STONES SHALL EXTEND TO 2' BELOW THE SCOUR DEPTH SPECIFIED AT THE WEIR OF THE STRUCTURE.
4. ALL DIMENSIONS SHOWN HERE ARE APPROXIMATE AND SHALL BE INSTALLED AS DIRECTED BY DESIGNATED SPECIALIST.

STRUCTURE TYPE/I.D.	STATION	ANGLE X	ANGLE Y	K	L	WEIR LENGTH	SCOUR HOLE DEPTH	WEIR ROCK ELEVATION	TOP ROCK ELEV ARM K	TOP ROCK ELEV ARM L
RJ-S1										
RJ-S2										
CV-S1										
CV-S2										
CV-S3										
RJ-W1										
RV-W1										

- NOTES:
1. ALL DIMENSIONS ARE APPROXIMATE AND MAY BE ADJUSTED BY THE DESIGNATED SPECIALIST
 2. STATIONING POINT IS UPSTREAM EDGE OF WEIR STONE USING BASELINE OF CONSTRUCTION



DATE	DESCRIPTION	MARK

U.S. ARMY ENGINEER DIVISION	Date: 10/4/2011
CORPS OF ENGINEERS	Design file no.
BALTIMORE, MARYLAND	Drawn by: SBP
	Checked by: REP
	Reviewed by: TMH
	Submitted by: CMK
	Dwg scale: AS SHOWN
	Drawing code: GN-6
	Task Order No. 19

CONSTRUCTION DETAIL SHEET

Sheet Number:
62 OF 72



Maryland's Guidelines To Waterway Construction DETAIL 2.5: LIVE FASCINES




Preliminary Step – prepare fascine bundles as follows: cigar-shaped bundles of live, rootable brush and branches with butts alternating, 4 to 10-inch (10 to 25-cm) diameters, tied 12 to 18 inches (30 to 45 cm) on center

Construction Note: installation begins at the bottom of the slope and proceeds from Step 1 through Step 5
Adapted from Leiser (1983)


Step 1 – insert stakes on contour




Step 2 – dig trench (1/2 bundle diameter in depth) above the stakes



Step 3 – place bundles in trench



Step 4 – add additional stakes through and below bundles



Step 5 – tamp soil into and along sides of bundle leaving the top 2 inches (5 cm) exposed to promote growth


SLOPE PROTECTION AND STABILIZATION TECHNIQUES

PAGE 2.5 - 3

MARYLAND DEPARTMENT OF THE ENVIRONMENT
WATER MANAGEMENT ADMINISTRATION


LIVE FASCINES TABLE

UNIT	STATION	LENGTH	ROWS
FS-S1			
FS-S2			
FS-S3			
FS-S4			
FS-S5			



IN ORDER TO SET PIPE AT PROPOSED INVERT ELEVATION, FOOTER ROCK(S) MAY BE REQUIRED TO BE PLACED LOWER THAN ADJACENT STONES

STORM DRAIN OUTFALL THROUGH IMBRICATED WALL
NOT TO SCALE




IMBRICATED RIPRAP WALL SECTION
NOT TO SCALE

IMBRICATED RIPRAP WALL DETAILS
NOT TO SCALE

LIVE STAKES FOR IMBRICATED WALLS NOTES:

- IMBRICATED WALL LIVE STAKES TO CONSIST OF 20 SILKY DOGWOOD AND 20 SILKY WILLOW CUTTINGS. LIVE STAKES TO BE 3' MIN. LENGTH AND ARE TO BE PLACED 10' ON-CENTER IN ALL LOCATIONS OF TWO-TIER IMBRICATED WALLS.
- REFER TO SHEET 17 OF 17 LIVE STAKE DETAIL FOR SIZE REQUIREMENTS AND REQUIRED CUTS.
- REFER TO SHEET 16 OF 17 FOR LIVE STAKE - IMBRICATED WALL SCHEDULE.
- PLACE LIVE STAKES INTO SPACES BETWEEN THE ROCKS. USE A STEEL ROD OR PROBE TO PREPARE PILOT HOLES.
- PROVIDE PLANTING SOIL AND FIRM SOIL SO THAT LIVE STAKE CANNOT BE EASILY MOVED OR PULLED OUT.
- KEEP CUTTINGS MOIST AND COOL UNTIL PLANTED.
- LIVE STAKE CUTTINGS SHALL HAVE 80% OF LENGTH WITHIN PLANTING SOIL AND 20% EXPOSED.
- PLANT CUTTINGS WHILE DORMANT.
- PLANTING SOIL TO CONSIST OF SALVAGED TOPSOIL.



RIFFLE GRADE CONTROL STRUCTURE
N.T.S.

RIFFLE GRADE CONTROL STRUCTURE TABLE

STRUCTURE I.D.	STATION	CHANNEL SLOPE	DIMENSIONS (FT)		
			X	Y	Z
RGC-S1					
RGC-S2					
RGC-S3					
RGC-W1					
RGC-W2					
RGC-W3					



RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0028
(F) 703 246-0123

MARK	DESCRIPTION	DATE	APPR

Designed by: REP	Date: 10/4/2011
Drawn by: DEA	Design file no.
Checked by: SPB	Drawn by: GN-7
Reviewed by: TMH	Drawn scale: AS SHOWN
Submitted by: CMK	Task Order No. 19

U.S. ARMY ENGINEER DIVISION
CORPS OF ENGINEERS
BALTIMORE, MARYLAND
w912DR-07-0-0008
Task Order No. 19

Sheet Number:
63 OF 72

STANDARD EROSION AND SEDIMENT CONTROL NOTES

1. THE CONTRACTOR SHALL NOTIFY THE ADMINISTRATION (WMA) 537-3510 SEVEN (7) DAYS BEFORE COMMENCING ANY LAND DISTURBING ACTIVITY AND, UNLESS WAIVED BY THE ADMINISTRATION, SHALL BE REQUIRED TO HOLD A PRECONSTRUCTION MEETING BETWEEN PROJECT REPRESENTATIVES AND A REPRESENTATIVE OF WMA.
2. THE CONTRACTOR MUST NOTIFY WMA IN WRITING AND BY TELEPHONE AT THE FOLLOWING POINTS:
 - A. THE REQUIRED PRE-CONSTRUCTION MEETING.
 - B. FOLLOWING INSTALLATION OF SEDIMENT CONTROL MEASURES.
 - C. DURING THE INSTALLATION OF SEDIMENT BASINS (TO BE CONVERTED INTO PERMANENT STORMWATER MANAGEMENT STRUCTURES) AT THE REQUIRED INSPECTION POINTS (SEE INSPECTION CHECKLIST ON PLAN). NOTIFICATION PRIOR TO COMMENCING CONSTRUCTION OF EACH STEP IS MANDATORY.
 - D. PRIOR TO REMOVAL OR MODIFICATION OF ANY SEDIMENT CONTROL STRUCTURE(S).
 - E. PRIOR TO REMOVAL OF ALL SEDIMENT CONTROL DEVICES.
 - F. PRIOR TO FINAL ACCEPTANCE.

3. THE CONTRACTOR SHALL CONSTRUCT ALL EROSION AND SEDIMENT CONTROL MEASURES PER THE APPROVED PLAN AND CONSTRUCTION SEQUENCE AND SHALL HAVE THEM INSPECTED AND APPROVED BY THE AGENCY INSPECTOR OR WMA INSPECTOR PRIOR TO BEGINNING ANY OTHER LAND DISTURBANCES. MINOR SEDIMENT CONTROL DEVICE LOCATION ADJUSTMENTS MAY BE MADE IN THE FIELD WITH THE APPROVAL OF THE FROM WMA INSPECTOR. THE CONTRACTOR SHALL ENSURE THAT ALL RUNOFF FROM DISTURBED AREAS IS DIRECTED TO THE SEDIMENT CONTROL DEVICES AND SHALL NOT REMOVE ANY EROSION OR SEDIMENT CONTROL MEASURE WITHOUT PRIOR PERMISSION FROM WMA INSPECTOR AND AGENCY INSPECTOR. THE CONTRACTOR MUST OBTAIN PRIOR AGENCY AND WMA APPROVAL FOR CHANGES TO THE SEDIMENT CONTROL PLAN AND/OR SEQUENCE OF CONSTRUCTION. .

4. THE CONTRACTOR SHALL PROTECT ALL POINTS OF CONSTRUCTION INGRESS AND EGRESS TO PREVENT DEPOSITION OF MATERIALS ONTO PUBLIC ROADS. ALL MATERIALS DEPOSITED ONTO PUBLIC ROADS SHALL BE REMOVED IMMEDIATELY.

5. THE CONTRACTOR SHALL INSPECT DAILY AND MAINTAIN CONTINUOUSLY IN AN EFFECTIVE OPERATING CONDITION ALL EROSION AND SEDIMENT CONTROL MEASURES UNTIL SUCH TIMES AS THEY ARE REMOVED WITH PRIOR PERMISSION FROM WMA INSPECTOR AND AGENCY INSPECTOR.

6. ALL SEDIMENT BASINS, TRAP EMBANKMENTS AND SLOPE, PERMITTED DIKES, SWALES AND ALL DISTURBED SLOPES STEEPER OR EQUAL TO 3:1 SHALL BE STABILIZED WITH SOD OR SEED AND ANCHORED STRAY MULCH, OR OTHER APPROVED STABILIZATION MEASURES, AS SOON AS POSSIBLE BUT NO LATER THAN SEVEN (7) CALENDAR DAYS AFTER ESTABLISHMENT. ALL AREAS DISTURBED OUTSIDE OF THE PERIMETER SEDIMENT CONTROL SYSTEM MUST BE MINIMIZED. MAINTENANCE MUST BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION. (REQUIREMENT FOR STABILIZATION MAY BE REDUCED TO THREE (3) DAYS FOR SENSITIVE AREAS.)

7. THE CONTRACTOR SHALL APPLY SOD OR SEED AND ANCHORED STRAW MULCH, OR OTHER APPROVED STABILIZATION MEASURES TO ALL DISTURBED AREAS AND STOCKPILES WITHIN FOURTEEN (14) CALENDAR DAYS AFTER STRIPPING AND GRADING ACTIVITIES HAVE CEASED IN THE AREA. MAINTENANCE SHALL BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION. (REQUIREMENT MAY BE REDUCED TO SEVEN (7) DAYS FOR SENSITIVE AREAS.)

8. PRIOR TO REMOVAL OF SEDIMENT CONTROL MEASURES, THE CONTRACTOR SHALL STABILIZE AND HAVE PERMANENT STABILIZATION FOR ALL CONTRIBUTORY DISTURBED AREAS USING SOD OR AN APPROVED PERMANENT SEED MIXTURE WITH REQUIRED SOIL AMENDMENTS AND AN APPROVED ANCHORED MULCH. WOOD FIBER MULCH MAY PROMOTE SHEET FLOW DRAINAGE. AREAS BROUGHT TO FINISHED GRADE DURING THE SEEDING SEASON SHALL BE PERMANENTLY STABILIZED AS SOON AS POSSIBLE, BUT NOT LATER THAN FOURTEEN (14) CALENDAR DAYS AFTER ESTABLISHMENT. WHEN PROPERTY IS BROUGHT TO FINISHED GRADE DURING THE MONTHS OF NOVEMBER THROUGH FEBRUARY, AND PERMANENT STABILIZATION IS FOUND TO BE IMPRACTICAL, TEMPORARY SEED AND ANCHORED STRAW MULCH SHALL BE APPLIED TO DISTURBED AREAS. THE FINAL PERMANENT STABILIZATION OF SUCH PROPERTY SHALL BE APPLIED BY MARCH 15 OR EARLIER IF GROUND AND WEATHER CONDITIONS ALLOW.

9. THE SITE'S APPROVAL LETTER, APPROVED EROSION AND SEDIMENT CONTROL PLANS, DAILY LOG BOOKS, AND TEST REPORTS SHALL BE AVAILABLE AT THE SITE FOR INSPECTION BY DULY AUTHORIZED OFFICIALS OF WMA AND THE AGENCY RESPONSIBLE FOR PROJECT.

10. SURFACE DRAINAGE FLOWS OVER UNSTABILIZED CUT AND FILL SLOPES SHALL BE CONTROLLED BY EITHER PREVENTING DRAINAGE FLOWS FROM TRAVERSING THE SLOPES OR BY INSTALLING PROTECTIVE DEVICES TO LOWER THE WATER DOWNSLOPE WITHOUT CAUSING EROSION. DIKES SHALL BE INSTALLED AND MAINTAINED AT THE TOP OF A CUT OR FILL SLOPE UNTIL THE SLOPE AND DRAINAGE AREA TO IT ARE FULLY STABILIZED. AT WHICH TIME THEY MUST BE REMOVED AND FINAL GRADING DONE TO PROMOTE SHEET FLOW DRAINAGE. PROTECTIVE METHODS MUST BE PROVIDED AT POINTS OF CONCENTRATED FLOW WHERE EROSION IS LIKELY TO OCCUR.

11. PERMANENT SWALES OR OTHER POINTS OF CONCENTRATED WATER FLOW SHALL BE STABILIZED WITH SOD OR SEED WITH APPROVED EROSION CONTROL MATTING, RIP-RAP, OR BY OTHER APPROVED STABILIZATION MEASURES.

12. TEMPORARY SEDIMENT CONTROL DEVICES MAY BE REMOVED, WITH PERMISSION OF WMA INSPECTOR AND AGENCY INSPECTORS, WITHIN THIRTY (30) CALENDAR DAYS FOLLOWING ESTABLISHMENT OF PERMANENT STABILIZATION IN ALL CONTRIBUTORY DRAINAGE AREAS. STORMWATER MANAGEMENT STRUCTURES USED TEMPORARILY FOR SEDIMENT CONTROL SHALL BE CONVERTED TO THE PERMANENT CONFIGURATION WITHIN THIS TIME PERIOD AS WELL.

13. NO PERMANENT CUT OR FILL SLOPE WITH A GRADIENT STEEPER THAN 3:1 WILL BE PERMITTED IN LAWN MAINTENANCE AREAS. A SLOPE GRADIENT OF UP TO 2:1 WILL BE PERMITTED IN NON-MAINTENANCE AREAS PROVIDED THAT THOSE AREAS ARE INDICATED ON THE EROSION AND SEDIMENT CONTROL PLAN WITH A LOW-MAINTENANCE GROUND COVER SPECIFIED FOR PERMANENT STABILIZATION. SLOPE GRADIENT STEEPER THAN 2:1 WILL NOT BE PERMITTED WITH VEGETATIVE STABILIZATION.

14. FOR FINISHED GRADING, THE CONTRACTOR SHALL PROVIDE ADEQUATE GRADIENTS TO PREVENT WATER FROM PONDING FOR MORE THAN TWENTY FOUR (24) HOURS AFTER THE END OF A RAINFALL EVENT. DRAINAGE COURSES AND SWALE FLOW AREAS MAY TAKE AS LONG AS FORTY-EIGHT (48) HOURS AFTER THE END OF A RAINFALL EVENT TO DRAIN. AREAS DESIGNED TO HAVE STANDING WATER SHALL NOT BE REQUIRED TO MEET THIS REQUIREMENT.

15. SEDIMENT TRAPS OR BASINS ARE NOT PERMITTED WITHIN 20 FEET OF A FOUNDATION THAT EXISTS OR IS UNDER CONSTRUCTION. NO STRUCTURE MAY BE CONSTRUCTED WITHIN 20 FEET OF AN ACTIVE SEDIMENT TRAP OR BASIN.

16. THE WMA INSPECTOR HAS THE OPTION OF REQUIRING ADDITIONAL SAFETY OR SEDIMENT CONTROL MEASURES, IF DEEMED NECESSARY.

17. ALL TRAP DEPTH DIMENSIONS ARE RELATIVE TO THE OUTLET ELEVATION. ALL TRAPS MUST HAVE A STABLE OUTFALL. ALL TRAPS AND BASINS SHALL HAVE STABLE INFLOW POINTS.

18. VEGETATIVE STABILIZATION SHALL BE PERFORMED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL. REFER TO APPROPRIATE SPECIFICATIONS FOR TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING SODDING, AND GROUND COVERS.

19. SEDIMENT SHALL BE REMOVED AND THE TRAP OR BASIN RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ONE QUARTER OF THE TOTAL DEPTH OF THE TRAP OR BASIN. TOTAL DEPTH SHALL BE MEASURED FROM THE TRAP OR BASIN BOTTOM TO THE CREST OF THE OUTLET.

20. SEDIMENT REMOVED FROM TRAPS (AND BASINS) SHALL BE PLACED AND STABILIZED IN APPROVED AREAS, BUT NOT WITHIN A FLOODPLAIN, WETLAND OR TREE-SAVE AREA. WHEN PUMPING SEDIMENT LADEN WATER, THE DISCHARGE MUST BE DIRECTED TO A SEDIMENT TRAPPING DEVICE PRIOR TO RELEASE FROM THE SITE. A SUMP PIT MAY BE USED IF SEDIMENT TRAPS THEMSELVES ARE BEING PUMPED OUT.

21. ALL WATER REMOVED FROM EXCAVATED AREAS (E.G. UTILITY TRENCHES) SHALL BE PASSED THROUGH AN APPROVED DEWATERING PRACTICE OR PUMPED TO A SEDIMENT TRAP OR BASIN PRIOR TO DISCHARGE FROM THE SITE (I.E. VIA FUNCTIONAL STORM DRAIN SYSTEM OR TO STABLE GROUND SURFACE).

22. SEDIMENT CONTROL FOR UTILITY CONSTRUCTION FOR AREAS OUTSIDE OF DESIGNED CONTROLS OR AS DIRECTED BY ENGINEER OR WMA INSPECTOR:

A. CALL "MISS UTILITY" AT 1-800-257-7777 48 HOURS PRIOR TO THE START OF WORK.

B. EXCAVATED TRENCH MATERIAL SHALL BE PLACED ON THE HIGH SIDE OF THE TRENCH.

C. TRENCHES FOR UTILITY INSTALLATION SHALL BE BACKFILLED, COMPACTED, AND STABILIZED AT THE END OF EACH WORKING DAY. NO MORE TRENCH SHALL BE OPENED THAN CAN BE COMPLETED THE SAME DAY. UNLESS:

D. TEMPORARILY SILT FENCE SHALL BE PLACED IMMEDIATELY DOWNSTREAM OF ANY DISTURBED AREA INTENDED TO REMAIN DISTURBED FOR MORE THAN ONE DAY.

23. WHERE DEEMED APPROPRIATE BY THE ENGINEER OR INSPECTOR, SEDIMENT BASINS AND TRAPS MAY NEED TO BE SURROUNDED WITH AN APPROVED SAFETY FENCE. THE FENCE MUST CONFORM TO LOCAL ORDINANCES AND REGULATIONS. THE DEVELOPER OR OWNER SHALL CHECK WITH LOCAL BUILDING OFFICIALS ON APPLICABLE IS SAFETY REQUIREMENTS. WHERE SAFETY FENCE DEEMED APPROPRIATE AND LOCAL ORDINANCES DO NOT SPECIFY FENCING SIZES AND TYPES, THE FOLLOWING SHALL BE USED AS A MINIMUM STANDARD: THE SAFETY FENCE MUST BE MADE OF WELDED WIRE AND AT LEAST 42 INCHES HIGH, HAVE POSTS SPACED NO FARTHER APART THAN 8 FEET, HAVE MESH OPENINGS NO GREATER THAN 2 INCHES IN WIDTH AND 4 INCHES IN HEIGHT WITH A MINIMUM OF 14 GAUGE WIRE. SAFETY FENCE MUST BE MAINTAINED AND IN GOOD CONDITION AT ALL TIMES.

24. OFF-SITE SPOIL OR BORROW AREAS ON STATE OR FEDERAL PROPERTY MUST HAVE PRIOR APPROVAL BY WMA AND OTHER APPLICABLE STATE, FEDERAL, AND LOCAL AGENCIES. OTHERWISE APPROVAL MUST BE GRANTED BY THE LOCAL AUTHORITIES. ALL WASTE AND BORROW AREAS OFF-SITE MUST BE PROTECTED BY SEDIMENT CONTROL MEASURES AND STABILIZED.

25. SITES WHERE INFILTRATION DEVICES ARE USED FOR THE CONTROL OF STORMWATER, EXTREME CARE MUST BE TAKEN TO PREVENT RUNOFF FROM UNSTABILIZED AREAS FROM ENTERING THE STRUCTURE DURING CONSTRUCTION. SEDIMENT CONTROL DEVICES PLACED IN INFILTRATION AREAS MUST HAVE BOTTOM ELEVATIONS AT LEAST TWO (2) FEET HIGHER THAN THE FINISH GRADE BOTTOM ELEVATION OF THE INFILTRATION PRACTICE. WHEN CONVERTING A SEDIMENT TRAP TO AN INFILTRATION DEVICE, ALL ACCUMULATED SEDIMENT MUST BE REMOVED AND DISPOSED OF PRIOR TO FINAL GRADING OF INFILTRATION DEVICE.

26. WHEN A STORM DRAIN SYSTEM OUTFALL IS DIRECTED TO A SEDIMENT TRAP OR SEDIMENT BASIN AND THE SYSTEM IS TO BE USED FOR TEMPORARILY CONVEYING SEDIMENT LADEN WATER, ALL STORM DRAIN INLETS IN NON-SUMP AREAS SHALL HAVE TEMPORARY ASPHALT BERMS CONSTRUCTED AT THE TIME OF BASE PAVING TO DIRECT GUTTER FLOW INTO THE INLETS TO AVOID SURCHARGING AND OVERFLOW OF INLETS IN SUMP AREAS.

27. SITE INFORMATION:
- A. TOTAL AREA OF FACILITY (BASE, CAMPUS, PARK, ETC.) - 53.3 ACRES
 - B. TOTAL AREA OF PROJECT SITE - 53.3 ACRES
 - C. AREA DISTURBED - 11.43 ACRES
 - D. AREA TO BE ROOFED OR PAVED - 0.0 ACRES
 - E. TOTAL CUT - 12,343 CUBIC YARDS
 - F. TOTAL FILL - 5,094 CUBIC YARDS
 - G. OFF-SITE WASTE/BORROW AREA LOCATION --TO BE DETERMINED

STANDARD STABILIZATION NOTE:

FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY STABILIZATION SHALL BE COMPLETED WITHIN SEVEN (7) CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER CONTROLS, DIKES, SWALES, DITCHES, PERIMETER SLOPES, AND ALL SLOPES GREATER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) AND FOURTEEN (14) DAYS AS TO ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT SITE.

OWNER'S / DEVELOPER'S CERTIFICATION:

"I/WE HEREBY CERTIFY THAT ALL CLEARING, GRADING, CONSTRUCTION, AND OR DEVELOPMENT WILL BE DONE PURSUANT TO THIS PLAN AND THAT ANY RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF NATURAL RESOURCES APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT."

OWNER/DEVELOPER SIGNATURE DATE

PRINTED NAME AND TITLE

CARD NO.

DESIGN CERTIFICATION

I HEREBY CERTIFY THAT THIS PLAN HAS BEEN DESIGNED IN ACCORDANCE WITH THE MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, THE 2000 MARYLAND STORMWATER DESIGN MANUAL, VOLUMES I & II INCLUDING SUPPLEMENTS, THE ENVIRONMENT ARTICLE SECTIONS 4-101 THROUGH 116 AND SECTIONS 4-201 AND 215, AND THE CODE OF MARYLAND REGULATIONS (COMAR) 26.17.01 AND COMAR 26.17.02 FOR EROSION AND SEDIMENT CONTROL AND STORMWATER MANAGEMENT, RESPECTIVELY.

DATE DESIGNER'S SIGNATURE

MD. REGISTRATION NO. _____
P.E., R.L.S., OR R.A. (CIRCLE ONE) PRINTED NAME

"PROFESSIONAL CERTIFICATION. I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 16493, EXPIRATION DATE: 5/13/2013"

SUPPLEMENTAL EROSION AND SEDIMENT CONTROL NOTES

1. STAGING AND STOCKPILING:
THE CONTRACTOR SHALL ESTABLISH STAGING AND STOCKPILE AREAS AT LOCATIONS APPROVED BY THE ENGINEER AND WMA INSPECTOR. THESE AREAS SHALL BE ESTABLISHED SUCH THAT WETLAND, WETLAND BUFFERS, FORESTED AREAS, AND OTHER ENVIRONMENTALLY SENSITIVE AREAS ARE NOT IMPACTED. EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILT FENCE SHALL BE INSTALLED DOWNGRADE OF THE STAGING AND STOCKPILING AREAS AS DIRECTED BY THE ENGINEER AND WITH THE APPROVAL OF THE MDE INSPECTOR.
2. STABILIZED CONSTRUCTION ENTRANCE LOCATIONS:
THE LOCATIONS OF STABILIZED CONSTRUCTION ENTRANCES ON THE PLANS ARE RECOMMENDED AND HAVE BEEN APPROVED BY MDE. THE CONTRACTOR MAY DETERMINE OTHER LOCATIONS FOR INGRESS/EGRESS TO THE CONSTRUCTION SITE WITH THE APPROVAL OF THE ENGINEER AND WMA INSPECTOR.
3. STORM DRAIN AND DITCH CONSTRUCTION:
STORM DRAIN SYSTEMS AND PERMANENT DITCHES/SWALES SHALL BE CONSTRUCTED FROM DOWNSTREAM TO UPSTREAM UNLESS OTHERWISE NOTED ON THE PLANS OR APPROVED BY THE ENGINEER.
4. COORDINATION WITH MAINTENANCE OF TRAFFIC PLAN:
THE SEDIMENT AND EROSION CONTROL SEQUENCES SHALL BE COORDINATED WITH THE MAINTENANCE OF TRAFFIC PLANS TO MAINTAIN CONTINUITY OF THE PRACTICES DURING ALL PHASES OF THE PROPOSED WORK. CONCURRENT CONSTRUCTION WITHIN THE VARIOUS PHASES MAY BE UNDERTAKEN IN ACCORDANCE WITH THE MAINTENANCE OF TRAFFIC PLAN. APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE PRIOR TO BEGINNING CONCURRENT WORK. SEDIMENT AND EROSION CONTROL MEASURES SHALL BE REMOVED UPON COMPLETION OF THEIR INTENDED FUNCTION. PERMANENT STABILIZATION OF CONTRIBUTORY DRAINAGE AREA AND PRIOR APPROVAL FROM THE SEDIMENT CONTROL INSPECTOR. SEDIMENT AND EROSION CONTROL MEASURES NECESSARY FOR SUBSEQUENT PHASE OF THE WORK SHALL BE MAINTAINED AS REQUIRED BY THE STANDARDS AND SPECIFICATIONS.
5. DEWATERING:
ANY EFFLUENT FROM DEWATERING FOUNDATIONS, TRENCHES AND OTHER DISTURBED AREAS MUST BE TREATED BY AN APPROVED SEDIMENT CONTROL DEVICE BEFORE BEING DISCHARGED.
6. SEQUENCE OF CONSTRUCTION:
THE SEQUENCE OF CONSTRUCTION INCLUDED IN THESE PLANS IS APPROVED BY THE MDE. THIS SEQUENCE OF CONSTRUCTION MAY BE MODIFIED BY THE CONTRACTOR. HOWEVER, THE CONTRACTOR MUST OBTAIN MDE APPROVAL FOR ANY MODIFICATIONS PRIOR TO IMPLEMENTING A REVISED SEQUENCE OF CONSTRUCTION IN THE FIELD.
7. END OF DAY STABILIZATION:
ONLY THAT AMOUNT OF WORK SHALL BE COMPLETED THAT CAN BE STABILIZED BY THE END OF THE DAY. THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO MINIMIZE UNNECESSARY DISTURBANCE. USE TEMPORARY STABILIZATION MEASURES, AS NEEDED, TO ENSURE END OF THE DAY STABILIZATION. TEMPORARY MEASURES TO PREVENT SEDIMENT-LADEN RUNOFF FROM ENTERING THE CHANNEL MAY INCLUDE, BUT NOT LIMITED TO, STRAW MULCH, SILT FENCE, IMPERVIOUS SHEETING, ETC., AND SHALL BE APPROVED BY THE CONTRACTING OFFICER'S REPRESENTATIVE AND MDE INSPECTOR. IF TEMPORARY STABILIZATION MEASURES ARE WASHED AWAY OR OTHERWISE RENDERED INEFFECTIVE, THEY ARE TO BE REPLACED OR REPAIRED THE NEXT DAY.
8. STABILIZATION DURING CHANNEL FORMATION:
THE CONSTRUCTION OF THE IN-STREAM STRUCTURES AND BANKFULL BENCH IS AN INTEGRAL PART OF STABILIZING THE CHANNEL DURING EXCAVATION AND FILL OPERATIONS WITHIN THE CHANNEL. ACCORDINGLY, THE IN-STREAM STRUCTURES AND PLACEMENT OF BENCH MATERIAL SHOULD OCCUR AT THE SAME TIME AS CHANNEL EXCAVATION. BENCHES IN FILL SHOULD BE BUILT FROM COURSE MATERIALS HARVESTED FROM THE CHANNEL.

SEQUENCE OF CONSTRUCTION

FOR SEQUENCE OF CONSTRUCTION SEE SITE SPECIFIC SEQUENCE ON DRAWINGS




DATE	APPR	DESCRIPTION	MARK

Designed by: EBB	Date: 10/4/2011
Drawn by: DEA	Design file no.:
Reviewed by: TWH	Drawing code: GN-10
Submitted by: CVK	Dwg scale: N.T.S.
U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	
W912DR-07-0-0008 Task Order No. 19	

EROSION & SEDIMENT CONTROL GENERAL NOTES

Sheet Number:
66 OF 72

DETAIL 22 - SILT FENCE



- Construction Specifications**
- Fence posts shall be a minimum of 36" long driven 16" minimum into the ground. Wood posts shall be 1 1/2" x 1 1/2" square (minimum) cut, or 1 3/4" diameter (minimum) round and shall be of sound quality hardwood. Steel posts will be standard T or U section weighting not less than 1.00 pound per linear foot.
 - Geotextile shall be fastened securely to each fence post with wire ties or staples at top and mid-section and shall meet the following requirements for Geotextile Class F:

Tensile Strength	50 lbs/in (min.)	Test: MSMT 509
Tensile Modulus	20 lbs/in (min.)	Test: MSMT 509
Flow Rate	0.3 gal ft ² /minute (max.)	Test: MSMT 322
Filtering Efficiency	75% (min.)	Test: MSMT 322
 - Where ends of geotextile fabric come together, they shall be overlapped, folded and stapled to prevent sediment bypass.
 - Silt Fence shall be inspected after each rainfall event and maintained when bulges occur or when sediment accumulation reached 50% of the fabric height.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE E - 15 - 3 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

SILT FENCE


Silt Fence Design Criteria

Slope Steepness	(Maximum) Slope Length	(Maximum) Silt Fence Length
Flatter than 50:1	unlimited	unlimited
50:1 to 10:1	125 feet	1,000 feet
10:1 to 5:1	100 feet	750 feet
5:1 to 3:1	60 feet	500 feet
3:1 to 2:1	40 feet	250 feet
2:1 and steeper	20 feet	125 feet

Note: In areas of less than 2% slope and sandy soils (USDA general classification system, soil Class A) maximum slope length and silt fence length will be unlimited. In these areas a silt fence may be the only perimeter control required.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE E - 15 - 3A MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION


DETAIL 21 - PORTABLE SEDIMENT TANK



- Construction Specifications**
- The following formula should be used in determining the storage volume of the sediment tank: 1 cubic foot of storage for each gallon per minute of pump discharge capacity.
 - An example of a typical sediment tank is shown above. Other container designs can be used if the storage volume is adequate and approval is obtained from the local approving agency.
 - Tanks may be connected in series.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE D - 14 - 2 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION


DETAIL 24 - STABILIZED CONSTRUCTION ENTRANCE



- Construction Specification**
- Length - minimum of 50' (*30' for single residence lot).
 - Width - 10' minimum, should be flared at the existing road to provide a turning radius.
 - Geotextile fabric (filter cloth) shall be placed over the existing ground prior to placing stone. **The plan approval authority may not require single family residences to use geotextile.
 - Stone - crushed aggregate (2" to 3") or reclaimed or recycled concrete equivalent shall be placed at least 6" deep over the length and width of the entrance.
 - Surface Water - all surface water flowing to or diverted toward construction entrances shall be piped through the entrance, maintaining positive drainage. Pipe installed through the stabilized construction entrance shall be protected with a mountable berm with 5:1 slopes and a minimum of 6" of stone over the pipe. Pipe has to be sized according to the drainage. When the SCE is located at a high spot and has no drainage to convey a pipe will not be necessary. Pipe should be sized according to the amount of runoff to be conveyed. A 6" minimum will be required.
 - Location - A stabilized construction entrance shall be located at every point where construction traffic enters or leaves a construction site. Vehicles leaving the site must travel over the entire length of the stabilized construction entrance.

U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE PAGE F - 17 - 3 MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

**Maryland's Guidelines To Waterway Construction
DETAIL 1.5: SANDBAG/STONE DIVERSION**



SANDBAG /STONE DIVERSION REVISED NOVEMBER 2000 PAGE 1.5 - 3 MARYLAND DEPARTMENT OF THE ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

LOCATION	MIN. BARRIER HEIGHT (FT.)	2-YR DISCHARGE (CFS)
BACHELLORS	3.5	586
SHERWOOD	3.5	310
WOODLAWN	3.0	685



RK&K
8302 LEE HIGHWAY, SUITE 425
HUNTERS BRANCH 2
FAIRFAX, VA
(P) 703 246-0128
(F) 703 246-0123


MARK	DESCRIPTION	DATE	APPR

U.S. ARMY ENGINEER DIVISION	Date: 10/4/2011
CORPS OF ENGINEERS	REP
BALTIMORE, MARYLAND	Design file no.
	Chd by: SPB
	Dwn by: DEB
	Reviewed by: TMH
	Submitted by: CMK
	Dwg scale: N.T.S.
	Dwg sheet: GN-14
	Task Order No. 19
	W912DR-07-0-0008

EROSION & SEDIMENT CONTROL DETAILS

Sheet Number:
70 OF 72

Maryland's Guidelines To Waterway Construction
DETAIL 4.8: TEMPORARY ACCESS BRIDGE



Maryland's Guidelines To Waterway Construction
DETAIL 4.8: TEMPORARY ACCESS BRIDGE

DESCRIPTION
A temporary access bridge is a stream crossing made of wood, metal, or other materials designed to limit the amount of disturbance to the stream banks and bed.

EFFECTIVE USES & LIMITATIONS
Temporary access bridges are the preferred method of waterway crossing since they typically cause the least disturbance to the waterway bed and banks, pose the least chance for interference with fish migration, and can be quickly removed and reused.

MATERIAL SPECIFICATIONS


- Stringers: Stringers should either be logs, sawn timber, prestressed concrete beams, metal beams, or other approved materials.
- Deck Materials: Deck materials should be of sufficient strength to support the anticipated load.

CONSTRUCTION SEQUENCE

All erosion and sediment control devices, including stream diversions, should be implemented as the first order of business according to a plan approved by the WMA or local authority. Dewatering basins should be built as needed and swales or ditches should be used to prevent surface drainage from entering the stream via the bridge crossing. (See the 1994 Maryland Standards and Specifications for Soil Erosion and Sediment Control.) The proposed construction, maintenance, and removal sequence is as follows:

1. Abutments should be placed parallel to, and on, stable banks such that the structure is at or above bankfull depth to prevent the entrapment of floating materials and debris.
2. Temporary access bridges should be constructed to span the entire channel. If the bankfull channel width exceeds 8 feet (2.5 meters), then a footing, pier, or other bridge support may be constructed within the waterway. No support will be permitted within the channel for waterways less than 8 feet wide. One additional bridge support will be permitted for each additional 8-foot width of the channel.
3. All decking members should be placed perpendicularly to the stringers, butted tightly, and securely fastened to the stringers. Decking materials must be butted tightly to prevent any soil material tracked onto the bridge from falling into the waterway.
4. Although run planks are optional, they may be necessary to properly distribute loads. One run plank should be provided for each track of the equipment wheels and should be securely fastened to the length of the span.
5. Curbs or fenders may be installed along the outer sides of the deck to provide additional safety.
6. Bridges should be securely anchored at one end using steel cable or chain to prevent the bridge from floating downstream and possibly causing an obstruction to the flow. Anchoring at only one end will prevent channel obstruction in the event that flood waters float the bridge. Acceptable anchors are large trees, boulders, or driven steel anchors. Temporary stream crossing intended for minimum corridor disturbance.
7. All areas disturbed during installation should be stabilized within 14 calendar days in accordance with a revegetation plan approved by the WMA.
8. Periodic inspection should be performed by the user to ensure that the bridge, streambed, and stream banks are maintained and not damaged.
9. Maintenance should be performed as needed to ensure that the structure complies with all standards and specifications. This should include the removal of trapped sediment and debris which should then be disposed of and stabilized outside the floodplain.
10. When the temporary bridge is no longer needed, all structures including abutments and other bridging materials should be removed within 14 calendar days. In all cases, the bridge materials should be removed within 1 year of installation. Removal of the bridge and cleanup of the area, including protection and stabilization of disturbed stream banks, should be accomplished without the use of construction equipment in the waterway.

Maryland's Guidelines To Waterway Construction
DETAIL 1.2: PUMP-AROUND PRACTICE



Maryland's Guide to Waterway Construction
DETAIL 1.2: PUMP-AROUND PRACTICE

The work should consist of installing a temporary pump around and supporting measures to divert flow around instream construction sites.

IMPLEMENTATION SEQUENCE
Sediment control measures, pump-around practices, and associated channel and bank construction should be completed in the following sequence (refer to Detail 1.2):

1. Construction activities including the installation of erosion and sediment control measures should not begin until all necessary easements and/or right-of-ways have been acquired. All existing utilities should be marked in the field prior to construction. The contractor is responsible for any damage to existing utilities that may result from construction and should repair the damage at his/her own expense to the county's or utility company's satisfaction.
2. The contractor should notify the Maryland Department of the Environment or WMA sediment control inspector at least 5 days before beginning construction. Additionally, the contractor should inform the local environmental protection and resource management inspection and enforcement division and the provider of local utilities a minimum of 48 hours before starting construction.
3. The contractor should conduct a pre-construction meeting on site with the WMA sediment control inspector, the county project manager, and the engineer to review limits of disturbance, erosion and sediment control requirements, and the sequence of construction. The contractor should stake out all limits of disturbance prior to the pre-construction meeting so they may be reviewed. The participants will also designate the contractor's staging areas and flag all trees within the limit of Disturbance which will be removed for construction access. Trees should not be removed within the limit of disturbance without approval from the WMA or local authority.
4. Construction should not begin until all sediment and erosion control measures have been installed and approved by the engineer and the sediment control inspector. The contractor should stay within the limits of the disturbance as shown on the plans and minimize disturbance within the work area whenever possible.
5. Upon installation of all sediment control measures and approval by the sediment control inspector and the local environmental protection and resource management inspection and enforcement division, the contractor should begin work at the upstream section and proceed downstream beginning with the establishment of stabilized construction entrances. In some cases, work may begin downstream if appropriate. The sequence of construction must be followed unless the contractor gets written approval for deviations from the WMA or local authority. The contractor should only begin work in an area which can be completed by the end of the day including grading adjacent to the channel. At the end of each work day, the work area must be stabilized and the pump around removed from the channel. Work should not be conducted in the channel during rain events.
6. Sandbag dikes should be situated at the upstream and downstream ends of the work area as shown on the plans, and stream flow should be pumped around the work area. The pump should discharge onto a stable velocity dissipater made of riprap or sandbags.
7. Water from the work area should be pumped to a sediment filtering measure such as a dewatering basin, sediment bag, or other approved source. The measure should be located such that the water drains back into the channel below the downstream sandbag dike.
8. Traversing a channel reach with equipment within the work area where no work is proposed should be avoided. If equipment has to traverse such a reach for access to another area, then timber mats or similar measures should be used to minimize disturbance to the channel. Temporary stream crossings should be used only when necessary and only where noted on the plans or specified. (See Section 4, Stream Crossings, Maryland Guidelines to Waterway Construction).
9. All stream restoration measures should be installed as indicated by the plans and all banks graded in accordance with the grading plans and typical cross-sections. All grading must be stabilized at the end of each day with seed and mulch or seed and matting as specified on the plans.
10. After an area is completed and stabilized, the clean water dike should be removed. After the first sediment flush, a new clean water dike should be established upstream from the old sediment dike. Finally, upon establishment of a new sediment dike below the old one, the old sediment dike should be removed.
11. A pump around must be installed on any tributary or storm drain outfall which contributes baseflow to the work area. This should be accomplished by locating a sandbag dike at the downstream end of the tributary or storm drain outfall and pumping the stream flow around the work area. This water should discharge onto the same velocity dissipater used for the main stem pump around.
12. If a tributary is to be restored, construction should take place on the tributary before work on the main stem reaches the tributary confluence. Construction in the tributary, including pump around practices, should follow the same sequence as for the main stem of the river or stream. When construction on the tributary is completed, work on the main stem should resume. Water from the tributary should continue to be pumped around the work area in the main stem.
13. The contractor is responsible for providing access to and maintaining all erosion and sediment control devices until the sediment control inspector approves their removal.
14. After construction, all disturbed areas should be regraded and revegetated as per the planting plan.



DATE	APPR	DESCRIPTION	MARK

U.S. ARMY ENGINEER DIVISION CORPS OF ENGINEERS BALTIMORE, MARYLAND	Designed by: REP Dwn by: DEA	Checked by: SPB	Date: 10/4/2011
W912DR-07-0-0008 Task Order No. 19	Reviewed by: TWH	Submitted by: CVK	Design file no. Drawing code: GN-15 Dwg scale: N.T.S.

EROSION & SEDIMENT CONTROL DETAILS

Sheet Number:
71 OF 72