

MARC ELRICH - Montgomery County Executive

CHRISTOPHER CONKLIN - Director, MCDOT

# **Turkey Foot Road Overlay**

## Project to Begin Soon Includes Patching, Milling, and Resurfacing

#### **PURPOSE**

This newsletter is to inform you of the upcoming road overlay of Turkey Foot Road. Please see Project Map located on the reverse side of this newsletter for the locations. This pavement system preservation project employs long-term strategies to preserve and enhance the physical and operating conditions of the roadway system.

#### **BACKGROUND**

The Montgomery County Department of Transportation's (MCDOT) Division of Highway Services (DHS) maintains nearly 5,200 lane miles of streets and highways in the county's transportation system.

MCDOT concluded a complete condition inventory of all County roads, identifying and rating the condition of each. This new assessment survey, updated every two years, has enabled the development of County-wide roadway repair strategies based on a formula-based objective rating system



SCOPE OF PROJECT

This project will consist of repairing Base Repairs, Milling, Adjusting Utilities, and Resurfacing the streets. We will do our best to keep the impact of traffic to a minimum. There will be lane shifts, lane closures, and temporary detours.

#### **SCHEDULE**

This project is scheduled to start in late October and end in early December, weather and other operational requirements permitting. If the weather gets worse before project completion, early spring of 2023 is the target completion date. Work hours will be between 8am and 4pm, Monday through Friday.

#### PROJECT WORK PLAN

Generally, the work will proceed as follows:

- **1. Conduct survey -** MCDOT inspectors will identify areas of pavement that, prior to resurfacing, may require full depth patching or other repairs. These areas are marked by white paint.
- 2. Isolated Concrete Repairs ADA curb ramps will be brought up to current standards, and trip hazards on sidewalks will be removed within the project work limits Some additional curb repairs may also be made.
- **3. Full-Depth Patching** Full-depth patching restores the pavement's structural integrity and capacity to support vehicle loads. The areas of distressed pavement marked by the MCDOT inspectors is removed and replaced by new asphalt pavement. The final paving of the road will cover these patched areas.
- **4. Pavement milling** Milling/grinding off the edges of the existing pavement allows the new



pavement to match the level of the existing curbs, etc., and restores the proper highway cross-section to improve ride-ability and drainage. The new pavement will provide a smoother ride and assure positive drainage.



**5. Paving with hot mix asphalt** - Asphalt is delivered to the site in dump trucks. The hot material is transferred into the hopper of an asphalt paving machine such as the one depicted



New asphalt is compacted with steel wheeled roller

in the photo. The paving machine places the hot asphalt in a uniform thickness and compaction.

#### 6. Replace roadway lane markings -

Permanent lane markings, if existing prior to paving, will be remarked shortly after all paving operations have been completed.

#### **IMPACTS**



We will do our best to keep the impact of traffic to a minimum. There will be Lane Shifts and Lane Closures. There will also be Parking Restrictions during the work hours of 8am to 4pm. We will be in contact with Traffic Marking and TMC daily.

# SHOULD THE POLICE TOW YOUR VEHICLE, CONTACT THE POLICE NON-EMERGENCY NUMBER (301-279-8000.)

Access to residences will be available, however minor delays may be experienced as workers restrict traffic from freshly placed hot mix asphalt. Generally speaking, this work is best characterized as noisy and disruptive. MCDOT will take steps to mitigate any inconveniences.

Please walk or drive carefully through the work zone and obey all posted signage.

We thank you for your cooperation and patience as we work to improve the County infrastructure for residents and users.



#### MONTGOMERY COUNTY, MARYLAND

DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAY SERVICES
100 EDISON PARK DRIVE, 4TH FLOOR, GAITHERSBURG, MD 20878

240-777-ROAD (7623) www.montgomerycountymd.gov/DOT-Highway/

### KEEPING MONTGOMERY MOVING

MCDOT NEWS No. 2022.10.5

# NOTICE OF TURKEY FOOT ROAD OVERLAY

## **SAFETY NOTICE**

Please drive gently and safely through the work site and kindly remember that while repair work is underway, personnel and construction vehicles will be moving around the site. Some materials may be stored in the area. Please use caution when walking or driving through the construction zone. Children may be attracted to the noise and machinery, so we ask that you please keep all children under close supervision at all times, even after the work is completed for the day. Also, please follow the direction of flaggers and temporary signs and traffic control devices. We appreciate your patience and cooperation while we make these much needed improvements to the infrastructure. If you have questions relating to your health or safety, please email Degan Bartels, Public Relations & Outreach Manager, at degan.bartels@montgomerycountymd.gov

#### **DIVISION OF HIGHWAY SERVICES**

Richard C. Dorsey Frank Kingsley
Division Chief Pavement Management Section Chief

**Project Manager:** James Kisner 240-777-7631 **Program Manager:** Donald Noble 240-777-7601

Should your questions be of a more general nature, please contact the MC311 Call Center by dialing 311 or 240-777-0311

DHS Email: mcdot.highway@montgomerycountymd.gov

DHS Website: dot.dhs@montgomerycountymd.gov



