Public Right-of-Way Construction Impacts

Side: North

Limits: Avenel to Stateside Ct

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

ADDRESS	CONSTRUCTION IMPACTS
All Addresses	Construct a 5' wide concrete sidewalk with a 2-3' green space.
	All driveway aprons will be replaced with concrete.
	All lead walks will be replaced with concrete.
	For all tree removals, new trees may be planted.
	Remove 1400 LF of curb and replace with barrier curb.
1510 Stateside	Construct a 5-ft wide concrete sidewalk with a 0 to 3-ft wide
	variable greenspace.
	Reconstruct 1 ADA ramp.
	Relocate 4 signs.
	Transition sidewalk behind two poles #805428-550660.
	Transition sidewalk behind pole #805428-510670.
	Adjust storm drain top.
	Reconstruct concrete apron.
1504 Stateside	Move 2 signs.
	Remove concrete apron.
	Place sidewalk behind pole #805428-320800.
	Relocate 2 PVC property drain pipes.
1500 Stateside	Remove concrete apron.
	Remove brick lead walk.
	Place sidewalk behind pole #805428-220860.
	Adjust gas meter, if needed.
1418 Stateside	Remove HMA apron.
	Remove 3 trees with 6", 8", and 26" diameters.
	Remove bushes.
	Place sidewalk behind pole #805428-130920.
1412 Stateside	Remove HMA apron.
	Remove bushes.
	Remove 3 trees with 12", 21", and 27" diameters.
	Place sidewalk behind pole #804429-030990.
	Adjust gas meter, if needed.
1408 Stateside	Remove HMA apron.
	Remove tree with 30" diameter.
	Place sidewalk behind pole #804429-940050.
	Adjust sewer cleanout.

Public Right-of-Way Construction Impacts

Side: North

Limits: Avenel to Stateside Ct

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

ADDRESS	CONSTRUCTION IMPACTS
1404 Stateside	Construct a retaining wall.
	Remove concrete apron.
	Place sidewalk behind fire hydrant.
	Remove 2 trees with 24" and 26" diameters.
	Place sidewalk behind pole #805429-840110.
	Remove metal fence.
1400 Stateside	Remove concrete apron.
	Remove metal fence.
	Place sidewalk behind pole #804429-740180.
	Construct block retaining wall along front of property, if needed.
1324 Stateside	Remove tree with 29" diameter.
	Remove concrete apron.
	Remove concrete lead walk.
	Place sidewalk behind pole #805429-650240.
	Remove PVC property drain pipe within the County's public
	right of way, if needed.
	Remove shrubs within the County's public right of way, if
	needed.
1320 Stateside	Remove concrete apron.
	Remove 2 trees with 7" and 20" diameters.
	Remove bushes.
	Place sidewalk behind pole #805429-570290.
1318 Stateside	Remove HMA apron.
1316 Stateside	Remove concrete apron.
	Place sidewalk behind pole #805429-430380. Move anchors.
	Meet existing sidewalk.

The above impacts are based on a preliminary investigation and are subject to change at anytime as field conditions warrant.

Public Right-of-Way Construction Impacts

Side: South

Limits: Stateside Ct to Avenel

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

ADDRESS	CONSTRUCTION IMPACTS
All Addresses	Construct a 5' wide concrete sidewalk with a 2-3' green space.
	All driveway aprons will be replaced with concrete.
	All lead walks will be replaced with concrete.
	For all tree removals, new trees may be planted.
	Remove 1350 LF of curb and replace with barrier curb.
1303 Stateside	Construct an ADA ramp.
	Place sidewalk behind fire hydrant.
	Move sign.
	Remove tree with 5" diameter.
	Remove concrete lead walk.
	Adjust gas valve.
1319 Stateside	Remove paver lead walk.
	Remove HMA apron.
1323 Stateside	Remove 2 trees with 6" and 15" diameters.
	Remove landscaping.
	Remove stumps.
	Remove concrete apron.
	Place sidewalk behind pole #804429-690170.
	Adjust 2 water meters, if needed.
1325 Stateside	Remove 2 trees with 19" and 21" diameters.
	Remove tree stump.
	Remove concrete apron.
	Adjust manhole.
1403 Stateside	Remove tree with 3" diameter.
	Remove bushes.
	Remove concrete apron.
1405 Stateside	Remove bushes.
	Remove 2 trees with 3" and 28" diameters.
	Remove concrete apron.
	Adjust water meter, if needed.

Public Right-of-Way Construction Impacts

Side: South

Limits: Stateside Ct to Avenel

Sidewalk Width: 5-Ft

Sidewalk Material: Concrete

ADDRESS	CONSTRUCTION IMPACTS
1409 Stateside	Remove HMA apron.
	Remove rocks.
	Remove 2 trees with 21" and 33" diameters.
	Adjust water meter, if needed.
1415 Stateside	Remove concrete apron.
	Adjust manhole.
1419 Stateside	Remove bushes.
	Remove 2 trees with 24" and 28" diameters.
	Remove concrete apron.
	Remove slate lead walk.
	Adjust water meter, if needed.
1501 Stateside	Remove tree with 34" diameter.
	Move 2 signs.
	Remove concrete apron.
	Place sidewalk behind fire hydrant.
	Adjust water meter.
1509 Stateside	Move sign.
	Remove concrete apron.
	Construct a retaining wall.
	Remove bushes.
9408 Avenel	Move 3 signs.
	Construct a retaining wall.
	Remove tree with 30" diameter.
	Update ADA ramp.
	Adjust storm drain top.

The above impacts are based on a preliminary investigation and are subject to change at anytime as field conditions warrant.