

Oakview Drive

Public Right-of-Way Construction Impacts

Side: North (even-numbered homes)
Limits: New Hampshire to Dilston
Sidewalk Width: 5-feet
Sidewalk Material: Concrete
Road Width: 34-feet

ADDRESS	CONSTRUCTION IMPACTS
Oakview Drive at New Hampshire Avenue (MD-650)	Construct one A.D.A. ramp.
1626 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove 1,950 linear feet of curb and replace with barrier curb. Remove bushes. Transition sidewalk behind pole #806430-120420. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Relocate sign. Remove four trees due to poor condition, a 14 and 8.5-inch Leyland Cypress, a 17-inch Pin Oak and a 5-inch Red Cedar tree. Remove three trees, an 8-inch in diameter Redbud and two 12-inch in diameter Leyland Cypress trees; replacement trees may be planted.
1624 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove bush within County's public right of way to make way for sidewalk. Remove one 7-inch in diameter Redbud tree due to poor condition; replacement trees may be planted Relocate Neighborhood Watch sign. Sidewalk will transition behind pole #805430-980440.
1622 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove one 12-inch in diameter Redbud tree; replacement trees may be planted. Relocate sign.
1620 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove one 7.5-inch in diameter Redbud tree; replacement trees may be planted. Sidewalk will transition behind pole #805430-860460.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1618 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove one 8-inch in diameter Redbud tree; replacement trees may be planted.</p>
1616 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Sidewalk will transition behind pole #805430-750470.</p>
1614 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Construct an A.D.A ramp. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove one 8.5-inch in diameter Redbud tree; replacement trees may be planted.</p>
1612 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Construct an A.D.A ramp. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Remove one 9-inch in diameter Redbud tree; replacement trees may be planted. Sidewalk will transition behind pole #805430-640490.</p>
1610 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Sidewalk will transition behind fire hydrant.</p>
1608 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove two trees, a 2-inch in diameter Goldenrain tree and a 42-inch in diameter Willow Oak tree; replacement trees may be planted. Sidewalk will transition behind pole #805430-510510.</p>
1606 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk.</p>
1604 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Remove landscaping within County's public right of way to make way for sidewalk. Construct an A.D.A ramp. Sidewalk will transition behind pole #805430-380530.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1602 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove one 8-inch in diameter Redbud tree; replacement trees may be planted. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Remove bush within County's public right of way to make way for sidewalk.</p>
1600 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Remove one 10-inch in diameter Kwanzan Cherry tree; replacement trees may be planted.</p>
Oakview Drive @ Braddock Road	<p>Construct two A.D.A. ramps.</p>
1516 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Sidewalk will transition behind pole #805430-040500.</p>
1514 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove one 3-inch in diameter Serviceberry tree; replacement trees may be planted. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Sidewalk will transition behind fire hydrant.</p>
1512 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove stump. Remove and replace concrete driveway apron. Sidewalk will transition behind pole #804430-970490.</p>
1510 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove bush within County's public right of way to make way for sidewalk. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron.</p>
1508 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove one 35-inch in diameter Pin Oak tree due to poor condition; replacement trees may be planted. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk.</p>
1506 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Sidewalk will transition behind pole #804430-10480. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron.</p>
1504 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1502 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Sidewalk will transition behind pole #804430-690470.</p>
1500 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove one 37.5-inch in diameter Pin Oak tree due to poor condition; replacement trees may be planted. Remove and replace concrete leadwalk.</p>
Oakview Drive at Cottrell Terrace	<p>Construct two A.D.A. ramps</p>
9800 Cottrell Terrace	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Relocate sign. Sidewalk will transition behind pole #804430-480450. Remove bush and landscaping from County's public right of way to make way for sidewalk. Sidewalk will transition behind fire hydrant. Remove brick leadwalk within County's public right of way and replace with concrete.</p>
1404 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove brick leadwalk within County's public right of way and replace with concrete. Remove and replace concrete driveway apron. Construct a retaining wall. Sidewalk will transition behind pole #804430-390460.</p>
1402 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk. Remove and replace handrail. Construct a retaining wall.</p>
9601 Dilston Road	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Sidewalk will transition behind pole #804430-230470. Remove one 35-inch in diameter Tulip Poplar tree; replacement trees may be planted.</p>
Oakview Drive @ Dilston Road	<p>Construct an A.D.A. ramp.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

Oakview Drive

Public Right-of-Way Construction Impacts

Side: South (odd-numbered homes)
Limits: New Hampshire to Dilston
Sidewalk Width: 5-feet
Sidewalk Material: Concrete
Road Width: 34-feet

ADDRESS	CONSTRUCTION IMPACTS
Oakview Drive @ Dilston Road	Construct an A.D.A. ramp.
1401 Oakview Drive	Remove 1,975 linear feet of curb and replace with barrier curb. Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove two trees, one 43-inch in diameter Pin Oak and one 24.5-inch in diameter Tulip Poplar; replacement trees may be planted. Remove landscaping within County's public right of way to make way for sidewalk. Construct a retaining wall. Sidewalk will transition behind pole #804430-220440.
1403 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Construct a retaining wall. Remove and replace concrete leadwalk. Remove and replace concrete driveway apron. Remove bushes within County's public right of way to make way for sidewalk.
1405 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Remove and replace concrete leadwalk. Construct a retaining wall. Sidewalk will transition behind pole #804430-340240. Relocate anchors.
1407 Oakview Drive	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace. Construct a retaining wall. Remove one 41.5-inch in diameter Pin Oak tree that was previously marked for removal due to poor health; replacement trees may be planted. Remove landscaping within County's public right of way to make way for sidewalk. Remove and replace concrete driveway apron. Remove and replace concrete leadwalk.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1409 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Construct a retaining wall.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove one Crape Myrtle tree with 24 multi-stems; replacement trees may be planted.</p> <p>Remove bushes from County's public right of way to make way for sidewalk.</p>
Oakview Drive @ Cottrell Terrace	<p>Construct two A.D.A. ramps.</p>
1501 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove rock and bushes from County's public right of way to make way for sidewalk.</p> <p>Remove and replace concrete leadwalk.</p> <p>Construct a retaining wall.</p>
1503 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove on 58-inch in diameter Pin Oak tree; replacement trees may be planted.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove bricks from County's public right of way to make way for sidewalk.</p> <p>Construct a retaining wall.</p>
1505 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove one 42-inch in diameter Pin Oak tree; replacement trees may be planted.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove and replace concrete leadwalk.</p> <p>Construct a retaining wall.</p>
1507 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove bush from County's public right of way to make way for sidewalk.</p> <p>Remove one Crape Myrtle with 16 multi-stems; replacement trees may be planted.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove and replace concrete driveway apron.</p> <p>Construct a retaining wall.</p>
1509 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove stump.</p> <p>Remove and replace concrete driveway apron.</p> <p>Construct a retaining wall.</p>
1511 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove two trees, one 5-inch in diameter Magnolia and one 50.5-inch in diameter Pin Oak; replacement trees may be planted.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove and replace concrete driveway apron.</p> <p>Construct a retaining wall.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

ADDRESS	CONSTRUCTION IMPACTS
1513 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove fence.</p> <p>Construct a retaining wall.</p> <p>Remove two trees, one 20-inch in diameter Japanese Maple tree and one 15-inch in diameter Overcup Oak tree; replacement trees may be planted.</p>
1515 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Construct a retaining wall.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove two 2.5-inch in diameter Chinkapin Oak trees; replacement trees may be planted.</p>
Oakview Drive @ Braddock Road	<p>Construct two A.D.A. ramps.</p>
1601 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove one 23.5-inch in diameter Pin Oak tree; replacement trees may be planted.</p> <p>Remove and replace concrete driveway apron.</p> <p>Remove bushes from County's public right of way to make way for sidewalk.</p>
1603 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove one 13-inch in diameter Linden tree to make way for sidewalk; replacement trees may be planted.</p> <p>Remove one private property Yoshino Cherry tree as a courtesy due to poor condition.</p>
Oakview Drive @ Parham Road	<p>Construct two A.D.A. ramps.</p>
1605 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove one 36-inch in diameter Pin Oak tree due to poor condition; replacement trees may be planted.</p>
1607 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove and replace concrete leadwalk.</p> <p>Remove and replace concrete driveway apron.</p>
1609 Oakview Drive	<p>Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide variable greenspace.</p> <p>Remove two trees, one 11-inch Boxelder tree due to poor condition and one 22-inch in diameter Red Oak tree; replacement trees may be planted.</p> <p>Remove and replace concrete leadwalk.</p>
Oakview Drive @ Parham Place	<p>Construct one A.D.A. ramp.</p>

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.