

CONTRACTOR MUST PROVIDE SHOP DRAWING DETAIL OF COVERED WALKWAY FOR REVIEW AND APPROVAL TO THE TRAFFIC OPERATIONS SECTION, IF ALTERNATE MATERIALS FOR WALKWAY ARE PROPOSED

1/2" MIN. THICK PLYWOOD
2" THICK ROOF DECK

2" X 8" FULL LENGTH
ONE ON EACH SIDE

WIRE MESH OR
1/2" PLYWOOD

SLOPE DOWN TOWARDS CURBLINE

ROLLED ROOFING

2" X 8" ON 4' O/C

2" X 4" TYP.
EACH STUD

40 WATT LIGHT
W/ GUARD
ON 16 FT O/C

BACK SIDE
(WORK AREA)

FRONT SIDE
(ROAD SIDE)

1/2" PLYWOOD
6' 0" HIGH MIN.

6" LAP

4" X 4" ON 2' O/C

2" X 4" HANDRAIL

8' CLEAR

WIRE MESH, CONTINUOUS

3'6"

5/8" PLYWOOD FLOOR

5 FT MIN.

4" X 4" ON 2' O/C

PROVIDE TEMPORARY ASPHALT WEDGE FROM CURB TO EXISTING PAVING AS NECESSARY

REVISION BY	DATE	APPROVED

DATE 07-01-12	TRAFFIC OPERATIONS SECTION MONTGOMERY COUNTY, MARYLAND
DES. BY MCDPWT	
DRAWN BY TCLE	COVERED WALKWAY
SCALE NTS	APPROVED _____ CHIEF, TRAFFIC OPERATIONS SECTION
STANDARD TCP-107.03 _____ OF _____ SHEETS	