



2425 Reedie Drive, 7th Floor Wheaton, MD 20902 240-777-0311 montgomerycountymd.gov/dps

Retaining Wall Inspections

Inspection Sequence		Prior to Inspection Request		Performed by		Inspection approval required prior to
Туре	Code	Work to be Completed	Approved Inspections	DPS	Others	
Footings	401	 Excavation for retaining wall footing (sometimes), Grade stakes, reinforcing steel installed Sediment control measures installed per the approved sediment control plans, if any 	Before you dig call MISS UTILITY 800- 257-7777 (2-day notice required)	Yes	 Licensed Design Professional⁽¹⁾ 	Placing concrete
Rebar, deadman, geogrid placement	402	 Excavation retaining wall Grade stakes, reinforcing steel Sediment control measures installed per the approved sediment control plans, if required Drainage system installed, if required 	• 401	Yes	 Licensed Design Professional⁽¹⁾ 	• Backfilling
Final	251	Construction complete	• 402	Yes	 Licensed Design Professional⁽¹⁾ 	Using structure

(1) Maryland registered professional engineers & architects