A. Identification and Coding Information				2. Da	2. Date: October 1, 2008			7. Pre PDF Pg.No.: 8. Req. Adeq				
1. Project Number Agency Number		Update Code										
083807 S-89,22 Change		Revis	Revised: January 21, 2009									
3, Project Name: Anacostia Storage Facility				-				- W	WSSC			
4. Program: S	Sanitation 6	. Planning	Area:									
В.			E	xpenditu	ire Sched	ule (000'	s)					
Cost Elements		- (8) Total	(9) Thru FY '08	(10) Estimate FY '09	(11) Total 6 Years	(12) Year 1 FY '10	(13) Year 2 FY '11	(14) Year 3 FY '12	(15) Year 4 FY '13	(16) Year 5 FY '14	(17) Year 6 FY '15	
Planning, Design &	Supervision	4,939	231	1,150		968	880	800	800	110		
Land		Min.										
Site Improvements	& Utilities		· - , - , - , - , - , - , - , - , - , - 									
Construction		27,841			27,841	461	6,980	9,000	8,800	2,600		
Other		3,255		115	3,140	143	786	980	960	271		
Total		36,035	231	1,265	34,539	1,572	8,646	10,780	10,560	2,981		
C.				Funding	Schedul	e (000's)						
WSSC Bonds		32,432	208	1,139	31,085	1,415	7,781	9,702	9,504	2,683		
SDC		3,603	23	126	3,454	157	865	1,078	1,056	298		

D. Description & Justification

DESCRIPTION

This project provides for the customer outreach, planning, design and construction of a new seven million gallon sewer overflow storage facility and needed power reliability upgrades at the existing Anacostia No.2 Wastewater Pumping Station.

Service Area Lower Anacostla Drainage Basin

Capacity 7 MG

JUSTIFICATION

Plans & Studies

"Anacostia Wastewater Pumping Station No.2 Hydraulic Study", Whitman Requardt and Associates, LLP (October 2005); "Overflow Event June 25 - 26; 2006 Anacostia WWPS", Whitman Requardt and Associates, LLP (November 2006): Preliminary Design Criteria Report, Whitman, Requardt & Associates (March 2008); Anacostia WWPS Power Reliability Study, Whitman Requardt and Associates, Shah & Associates (April 2008).

Specific Data

Currently, Anacostia WWPS No. 2 receives flows from the Hyattsville WWPS and by gravity from several basins within the Tributary Area of the Anacostia River. The WWPS discharge is piped directly to DC WASA's sewer system. By agreement between WSSC and DC WASA, the Anacostia WWPS No. 2 cannot discharge wastewater at a rate in excess of 199 MGD. In the past, during extreme rainfall events, the influent flow to Anacostia WWPS No. 2 exceeded the 199 MGD limit, thus creating sanitary overflows on the station site and/or at Junction Chamber No.1, in the vicinity of the Hyattsville WWPS. The Consent Decree between WSSC, MDE, and the EPA was entered into on December 7, 2005, stipulating that the WSSC develop and formally submit a Facility Plan for the Anacostia No. 2 Pump Station to EPA/MDE. The Facility Plan, which recommends the building of a new storage facility intended to eliminate weather related sanitary sewer overflows at the Anacostia No. 2 Pump Station, was approved by EPA/MDE July 31, 2006.

Cost Change

Cost estimates were increased to include needed power reliability upgrades for the existing Anacostia No. 2 Wastewater Pumping

STATUS Preliminary Design (WSSC Contract No. CS4441A06,).

OTHER

The project scope remains the same. Expenditures shown in Block B are planning level estimates and may change based upon site specific conditions, design constraints and negotiations with the Maryland Department of the Environment (MDE). The new sewer overflow storage facility will be built on the site of the existing Anacostia No.2 Wastewater Pumping Station,

o. Fac.	E. Annual Opera	FY of Impact						
	Program Costs	Staff		···				
	Facility Costs	OtherMaintenance		****				
		Debt Service	2828		15			
	Total Costs	2828	****	15				
	Impact on Water	or Sewer Rate	6¢		15			
(18)	F. Approval and Expenditure Data (000's)							
Beyond 6 Years	Date First in Cap		FY	80				
	Date First Appro		FY	08				
	Initial Cost Estim	33,957						
	Cost Estimate La	35,200						
	Present Cost Es		36,035					
	Approved Reque	1,320						
YGYT	Total Expenditur	es & Encumbrances		23	11			

G. Status Information

Approval Request FY 10

Land Status:

Current FY (09)

Pub. Fac.

Public/Agency owned land

1,572

% Project Completion: D-10%

Supplemental Approval Request

Est. Completion Date:

December 2013

Н, Мар Map Reference Code:

MAP NOT AVAILABLE

D DE	SCRIPTION & HISTIFICATION (CON	וד)			
	SCRIPTION & JUSTIFICATION (CON by Number: S - 89.22	Project Name: Anacostla Storage Facility			
	RDINATION	1 Topoct Harno. Allacostia otorago i acinty			
		a George's County Government, Manyland Department of the Environment, Prince George's			
Č	ounty Department of Environmental R	e George's County Government, Maryland Department of the Environment, Prince George's esources, U.S. Army Corps of Erigineers and U.S. Environmental Protection Agency, Region	III.		
NOTE		and 90% Environmental Regulation.			
		•			
ه					
1					
5					
ယှ					
]	
	•				
İ					
1					