Alternative 2A

Pedestrian / Bicycle Underpass
and TSM / TDM
Improvements

MARYLAND 355

Proposed Roadside Tree Planting

Modify Existing Median to Extend Left Turn Lane

NIH Gate

Improvements to South Wood Road and Gate to be Constructed by Navy

Metrobus / Ride On Bus Stop

Wood Road

South Drive

Existing NNMC Gate to be Relocated

NIH Shuttle Stop

Existing Kiss & Ride Area

NIH Entrance Sign Relocation

Proposed Widening of Curb Radius

NNMC Shuttle Stop

Planned Canopy and Guard House

Metrobus / Ride On Bus Stop

Vents

Need for Physical Barrier to be Determined

Metro Medical Center Station

Proposed Stair & Escalator to Underpass

Metrorail Escalator

Bicycle Parking & Lockers

Proposed Elevators to Underpass

NIH Visitor Center

Metrorail Elevator

Pike

Bus Pullofff

Rockville

NIH Visitor Parking

MARYLAND 355

Legend

- Metro Station
- Existing Signal
- Proposed Signal
- Stormwater Facility
- Proposed Pavement Resurface
- Proposed Full-Depth Pavement
- Proposed Underpass
- Proposed Sidewalk & Bikepath
- Proposed Median
- Proposed In-Roadway Warning Light Crosswalk
- Streams / Waters of the U.S.
- Proposed Fence
- Historic District Boundary
- National Register List
- National Register Eligible
- Proposed Right-of-Way

N W E S

30 0 30 60

DRAFT: WORK IN PROGRESS
CONCEPTUAL LEVEL GRAPHIC
ADDITIONAL ENGINEERING REQUIRED