

Safe Routes to Schools Program's
Additions to Takoma-Langley
Purple Line Station Sidewalk Proposal

Ludlow Street
Public Right-of-Way Construction Impacts

Side: South
Limits: Hood to Barron
Sidewalk Width: 5-Ft
Sidewalk Material: Concrete
Road Width: 23'

ADDRESS	CONSTRUCTION IMPACTS
8502 Hood Street	Remove 5 to 10 feet of existing sidewalk and install a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove existing curved curb and replace with barrier curbing.
717 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete driveway within the County's public right of way. Remove paver sidewalk, concrete steps and block retaining wall within the County's public right of way and replace with concrete. Remove landscaping and hardscaping from County's public right of way. Remove bushes from County's public right-of-way as needed for sidewalk installation.
715 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete driveway within the County's public right of way. Remove and replace concrete steps within the County's public right of way and replace with concrete. Remove concrete retaining wall beside driveway within the County's public right of way as needed. Construct a block retaining wall. Remove landscaping and hardscaping within County's public right of way to make way for the sidewalk. Remove or relocate property drain pipe within the County's public right of way, if needed.
713 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete driveway within the County's public right of way. Remove and replace concrete steps within the County's public right of way. Construct a block retaining wall along front of property, if needed. Remove bricks along curb, as needed. Adjust water meter in driveway apron. Remove landscaping and bricks from County's public right of way, as needed.
711 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete driveway within the County's public right of way. Remove pavers from County's public right of way. Remove and replace concrete lead walk and steps within the County's public right of way. Remove brick retaining wall and replace with block retaining wall.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

**Safe Routes to Schools Program's
Additions to Takoma-Langley
Purple Line Station Sidewalk Proposal**

ADDRESS	CONSTRUCTION IMPACTS
709 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete lead walk and steps within the County's public right of way. Handrail may need to be relocated. Construct a retaining wall.
707 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete lead walk and steps within the County's public right of way. Construct a block retaining wall. Handrail may need to be relocated.
705 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete steps and driveway apron within County's public right of way. Construct a block retaining wall. Handrail may need to be relocated. Adjust water meter. Adjust sewer cleanout. Remove wood retaining wall along driveway apron, if needed.
703 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace. Remove and replace concrete steps within County's public right of way. Construct a block retaining wall. Handrail may need to be relocated. Remove landscaping within County's public right of way. Construct a block retaining wall.
701 Ludlow Street	Construct a 5-foot-wide concrete sidewalk with a 0 to 3-foot-wide greenspace and transition sidewalk to back of curb to meet with existing sidewalk. Remove and replace concrete lead walk within County's public right of way. Move sign. Remove or relocate property drain pipe within the County's public right of way, if needed.

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.

**Safe Routes to Schools Program's
Additions to Takoma-Langley
Purple Line Station Sidewalk Proposal**

Hudson Avenue
Public Right-of-Way Construction Impacts

Side: North
Limits: Garland Avenue to Flower Avenue
Sidewalk Width: 5-Ft
Sidewalk Material: Concrete
Road Width: 24'

ADDRESS	CONSTRUCTION IMPACTS
806 Hudson Avenue	Construct ADA-compliant ramp at Greenwood Avenue. Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Move sign. Remove and replace concrete lead walk steps within the County's public right of way. Remove and replace concrete driveway apron within County's public right of way. Remove bushes within County's public right of way as needed. Construct a retaining wall. Handrail may need to be relocated.
804 Hudson Avenue	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove bushes and landscaping within County's public right of way as needed. Remove stone steps and lead walk within County's public right of way and replace with concrete. Remove and replace concrete driveway apron within the County's public right of way. A retaining wall may be needed.
8301 Flower Avenue	Construct a 5-foot-wide concrete sidewalk with a variable 0 to 3-foot-wide greenspace. Remove and replace concrete driveway apron. Remove wooden fence within County's public right of way. If condition allows, fence may be relocated. Remove bushes from County's public right of way as needed. Move two signs. Reconstruct an ADA-compliant ramp at Flower Avenue.)

PLEASE NOTE: The above impacts are based on a preliminary investigation and are subject to change at any time as field conditions warrant.