




- Please note this meeting is being recorded.
- Everyone is on mute. You cannot unmute yourself. We can unmute you during the Q&A and comment period.
- Your video camera is off by default. To reduce the bandwidth of the meeting, we request that you please do not turn your camera on.
- If you have a question during the presentation, send it via chat.
 Select Lori Main as the recipient.






Outline

- Washington Grove Connector
 - 15% Design
 - Construction Cost Estimate
 - Permitting
 - Schedule
- Q&A/Comments





BROWN STREET CONNECTION











BROWN STREET CONNECTION








CRABBS BRANCH WAY TO AMITY DRIVE (PENDING UPON M-NCPPC APPROVAL)







CRABBS BRANCH WAY TO AMITY DRIVE (PENDING UPON M-NCPPC APPROVAL)




5.1 Site Grading and Earthwork


Three culverts are planned below the new trail. Preliminary fill depths at the culvert locations may range from 7 to 14 feet deep. The weight of these deeper fills may cause excessive settlements of the new culvert pipes and headwalls because of settlement of the on-site soils below these new structures and embankments. The evaluation of potential ground settlements, and measures to minimize the settlements and support the new pipes should be considered in a future design phase. Moreover, the potential exists that weathered to relatively unweathered rock may be encountered within the proposed construction footprint. Recommendations for compacted fill, subgrade preparation, fill soil requirements, placement and compaction criteria, and evaluating rock excavation are presented in subsequent sections.



FOR GENERAL NOTES, SEE DRAWING G-002 FOR PERVIOUS ASPHALT DETAIL.

CRABBS BRANCH WAY TO AMITY DRIVE (PENDING UPON M-NCPPC APPROVAL)





FOR GENERAL NOTES, SEE DRAWING G-002
 FOR PERVIOUS ASPHALT DETAIL,
 SEE DRAWING C-401 DETAIL 1



NOTE:

ERVIOUS ASPHALT TRAIL HAS BEEN PROPOSED TO MEET HE ESD REQUIREMENT OF THE PROJECT, PERMEABLE AVAMEMENT (PERVIOUS ASPHALT) WILL BE INSTALLED AS FER THE STANDARD DETAILS OF THE MONTGOMERY COUNTY (ENDOTHERS OF COMMITTING SET MICE)

5.1.2 Trail Subgrades in Wetlands

Some of the trail will cross floodplains and areas mapped as wetlands. We expect that the surface soils in these areas will be soft and not suitable as compacted fill subgrades. Thus, we expect these areas will fail the proofroll tests and will require undercutting and replacement with compacted fill. For planning purposes, we suggest that 100 percent of the trail subgrades through the areas mapped as wetlands be assumed to require undercutting and placement of a bridge lift as described below.


Due to the soft/loose and wet soils in the wetland areas, we expect that treatment of the subgrades will be necessary. Due to groundwater levels at the site, undercutting to a firm subgrade material may be impractical. At a minimum, deleterious material such as topsoil, organic soil, and loose material should be removed. If the subgrades are still deemed unsuitable by the Geotechnical Engineer after the removal of the deleterious and organic materials, a bridge lift may be placed to facilitate compaction in the first layers of new compacted fill.

Bridge lifts should consist of crushed stone. The stone is expected to consist of AASHTO Size No. 2 or similar depending on the condition of the subgrade at the time of construction. This bridge lift should be






CRABBS BRANCH WAY TO AMITY DRIVE (PENDING UPON M-NCPPC APPROVAL)



5.1.3 Compacted Fill

Compacted structural fill and backfill should consist of non-organic on-site soils. If off-site borrow materials are needed, these soils should classify as SC, SM, SP, SW, GC, GM, GP, or GW according to ASTM D2487. Fill materials should not contain particles larger than 3 inches.

CRABBS BRANCH WAY TO AMITY DRIVE (PENDING UPON M-NCPPC APPROVAL)









Construction Cost Estimate Comparison

	WASH GROVE CONN	BROWN STREET ONLY- PRELIM
CATEGORY 1 - PRELIMINARY	\$302,400	\$180,675
CATEGORY 2 - GRADING	\$632,700	\$215,100
CATEGORY 3 - DRAINAGE	\$87,370	\$27,040
CATEGORY 4 - STRUCTURES	\$332,019	\$190,197
CATEGORY 5 - PAVING	\$284,300	\$106,240
CATEGORY 6 - SHOULDERS	\$18,008	\$10,988
CATEGORY 7 - LANDSCAPING	\$88,692	\$36,577
CATEGORY 8 - TRAFFIC AND UTILITIES	\$349,098	\$153,363
SUBTOTAL	\$2,094,587	\$920,180
CONTINGENCY AT 30%	\$628,376	\$276,054
TOTAL	\$2,722,962	\$1,196,234




Permits

- Preliminary (35%) Design
 - Department of Permitting Services (DPS)-Stormwater Management (SWM)
 Concept Review
 - Maryland-National Capital Park and Planning Commission (M-NCPPC)
 - Natural Resources Inventory/Forest Standard Delineation (NRI/FSD)
 - Parks Concept Review
 - Mandatory Referral
- Final Design
 - DPS-Sediment Control Permit
 - Parks Construction Permit



Project Schedule





Contact



- 240-777-7263
- Rebecca.Park@montgomerycountymd.gov
- https://www.montgomerycountymd.gov/dot-dte/projects/washgroveconnector/index.html





Questions or Comments?

